
### By Email

Our Ref: S3020b/13WSS\_KC/23/004Lg

19 November 2024

North Point Hong Kong

Secretary, Town Planning Board 15/F, North Point Government Offices 333 Java Road



PLANNING LIMITED 規劃顧問有限公司

UNIF K, 161F, MG TOWER 133 HOT BUN ROAD, KWUN TOHG KOWLOON, HONG KONS

九龍戰壕海濱道133號 萬兆豎中心16模K室

電話TEL (852) 3426 8451 傳真FAX (852) 3426 9737 電郵EMAIL kta@ktaplanning.com

Dear Mr Leung,

# Proposed Concrete Batching Plant in "Industrial" zone at Nos.13-17 Wah Sing Street, Kwai Chung - Section 16 Planning Application -

Reference is made to the captioned S16 Planning Application submitted to the Town Planning Board ("TPB") on 31 October 2024 and the various telephone conversations earlier.

Please find attached a replacement page of the Supporting Planning Statement and an updated G/F Plan (to indicated the locations of different internal transport facilities) as per your request.

Meanwhile, should you have any queries in relation to the attached, please do not hesitate to contact Mr Kenneth To or the undersigned at

Thank you for your kind attention.

Yours faithfully

For and on behalf of KTA PLANNING LIMITED

Gladys Ng

Encl.

cc. the Applicant & Team

KT/GN/vy





**Table 3.1** Major Development Parameters

Proposed Concrete Batching Plant	
Site Area	1,777.608m <sup>2</sup>
Site Coverage	Not more than 69%
Gross Floor Area	About 10,500m <sup>2</sup>
Plot Ratio	About 5.9
Maximum Building Height	62.5mPD
Internal Transport Facilities	
No. of Concrete Mixer Truck Waiting Spaces	2
Raw material unloading bay for container	1
Concrete mixer truck loading point	4

### 3.2 Operation Process

3.2.1 The concrete production process involves three major steps, which are (1) delivery of raw materials, (2) materials weighing and mixing, and (3) loading and distribution of ready-mixed concrete with their details provided below:

## Step 1: Delivery of Raw Materials

Majority of the raw materials such as cement, other cementitious materials (such as pulverized fuel ash (PFA)), aggregates, etc. will be delivered by specific vehicles.

Conveyors of the proposed CBP for the transfer of aggregates will be enclosed and water spraying by sprinklers will be turned on during the unloading operation.

Cement and other cementitious materials will be also delivered by tankers. These materials will be pumped to the overhead silos through pipes. The loading, transfer and storage of the materials will be carried out in an enclosed system. Each silo should be equipped with a dust collector to treat the waste gas generated during the loading of the materials to silos.

#### Step 2: Materials Weighing and Mixing

All raw materials, cement, aggregate, water and admixtures will be weighed in hoppers in proper proportion and then discharged into a mixer for concrete production.

Weighing hoppers and mixers will normally be housed inside an enclosed environment.

#### Step 3: Product Loading and Distribution

The produced concrete will be discharged into concrete mixer trucks (CMTs) by gravity via wet concrete guiding chute.

