

For WSD comments below, we have the replies as follows.

(a) No discharge of effluent or foul water into adjoining land, storm water drain, channel, stream or river course is allowed. Such foul water or effluent shall be collected and disposed of outside WGG.

***(a) The generation of effluent or foul water will be minimized. And we will not discharge it into adjoining land, storm water drain, channel, stream, or river course in WGG and will collect and dispose of such foul water or effluent outside WGG during the commencement of CLP works.***

(b) All solid waste and sludge arising from the development shall be disposed of properly outside WGG.

***(b) We will follow the instruction mentioned to dispose of all the solid waste and sludge arising from the development properly outside WGG.***

(c) The use and storage of pesticides, toxicants, flammable solvents, laticidal oil, rodenticide, tar and petroleum oil are strictly prohibited in WGG.

***(c) Pesticides, toxicants, flammable solvents, laticidal oil, rodenticide, tar and petroleum oil will not be used in WGG during the commencement of CLP works.***

(d) No chemicals including fertilizers and detergents shall be used without the prior approval from the Water Authority.

***(d) All chemicals including fertilizers and detergents shall not be used during the commencement of CLP works.***

(e) Oil leakage and spillage are prohibited within WGG at all time.

***(e) We will always follow the above instruction to prohibit Oil leakage and spillage.***

(f) The structures under the development shall be located away from any water courses as possible. Signage for alerting not to pollute WGG should be displayed.

***(f) The erection of poles are located away from all water courses. Furthermore, we will follow the instruction to display the signage to alert not to pollute WGG.***

(g) During construction of the proposed PUI, no earth and other installation materials which may cause contamination to WGG are allowed to be stockpiled or stored on site. Furthermore, all excavation or filled surface shall be protected from erosion and siltation to any water courses

shall be prevented within WGG. All spoils shall be contained and protected; and effluent containing spoils shall be disposed of after desiltation.

***(g) No earth and other installation materials which may cause contamination to WGG will not be stockpiled or stored on site. All trench excavated or filled surface will protected by using desking and polyethylene sheet to prevent erosion and siltation to any water courses within WGG. All spoils shall be contained and protected carefully; and effluent containing spoils shall be disposed of after desiltation.***

(h) Operation and maintenance of the PUI shall not cause any contamination, discharge and leaching of pollutants to WGG.

***(h) We will follow all the instruction to prevent the cause of any contamination, discharge and leaching of pollutants to WGG during operation and maintenance of the PUI.***

(i) The 'Conditions of Working within Gathering Grounds" shall be complied.

***(i) We will always comply with 'Conditions of Working within Gathering Grounds".***