Compensatory Planting Proposal

LOT NOS. 515RP & 524S.B IN D.D. 90

ISA Certified Arborist

Ms. Lee Hiu Wa

ISA Certified Arborist (HK-1104A)

Tree Management Personnel Registration Scheme

Arborist (TM522127)

Tree Risk Assessor (TM522127)

Tree Work Supervisor (TM522127)


CONTENTS

1	OBJECTIVE	3
2	LOCATION PLAN OF COMPENSATORY TREE	4
3	RECOMMAND COMPENSATORY TREE AT AREA 1(CP1)	5
4	SUMMARY OF PROPOSED PLANTING SPECIES FOR COMPENSATORY PLANTING	7

1 OBJECTIVE


The loss of the concerned trees within will be compensated according to item 4 of Section I, Appendix II of LAO PN No. 2/2020 and 2/2020A. In general, implementation of compensatory planting, of a ratio not less than 1:1 in terms of quantity, within the subject Lot would be acceptable. That is, the total number of compensatory trees shall be equal or not less than that of the lost trees. Due to the limited space available, We recommend replanting 2 standard trees within the Lot. *Schefflera heptaphylla* (鵝掌柴) will be used for the compensatory planting.

2 LOCATION PLAN OF COMPENSATORY TREES



3. RECOMMAND COMPENSATORY TREES (CP1)

- The agricultural area of LOT NO. 524S.B IN D.D. 90 (*Picture 3.1*)
- I Replanting area: 4m²
- I The gradient of the landscape: 0°
- I Species: 2 no. of Schefflera heptaphylla (鵝掌柴)
- Height(m): 2Spread(m): 1
- Live-crown ratio (%): 50
- I Rootball: A rootball at least 450 mm in diameter and 300 mm deep
- I Surface treatment: the recipient tree pits will be backfilled with the mixture of 1 part of soil condition with 4 parts of existing soil
- Alinement: 2 meters centre apart will be proposed between the compensatory and existing trees for having better development. Also the compensation trees will be planted at least 1.2m from drainage, channel and curb.
- Depth of soil: at least 1.2m excluding drainage layer



4 SUMMARY OF PROPOSED PLANTING SPECIES FOR COMPENSATORY PLANTING

Summary of Proposed Planting Species for Compensatory Planting										
Location	Species	DBH	Crown	Overall	Quantity	Live-crown	Replanting area			
		(mm)	Spread	Height	(nos.)	ratio (%)				
			(m)	(m)						
agricultural	Schefflera	60	1	3	2	50	4 m²			
area	heptaphylla									
	(鵝掌柴)									