



Item 01a and 01b 14m (L) x 1m x 1.2m (D)



- Excavation on concrete area
- No tree affected
- Minimum 3.5m concrete carriageway is maintained at the entry of village
- The trench will be backfilled and reinstated after the works

Item 01c 6m (L) x 1m x 1.2m (D)



- Excavation on concrete area
- No tree affected
- Minimum 2m footpath is maintained
- The trench will be backfilled and reinstated after the works

Item 02 8m (L) x 1m x 1.2m (D)



- No tree affected
- Minimum 2m footpath is maintained
- The trench will be backfilled and reinstated after the works