

**Appendix III**  
**Revised Traffic Impact Assessment**

**Concrete Batching Plant at Tsing Yi  
- Renewal Application A/TY/147**

**Traffic Impact Assessment**

**Final Report**

**May 2024**



**CTA Consultants Limited**

**志達顧問有限公司**

## LIST OF CONTENTS

<b>1.</b>	<b>INTRODUCTION.....</b>	<b>1</b>
1.1	Background .....	1
1.2	Study Objectives .....	1
1.3	Structure of this Report.....	1
<b>2.</b>	<b>THE DEVELOPMENT.....</b>	<b>3</b>
2.1	Site Location .....	3
2.2	Development Proposal .....	3
2.3	Traffic Arrangement .....	3
<b>3.</b>	<b>EXISTING TRAFFIC CONDITIONS .....</b>	<b>4</b>
3.1	Existing Road Network.....	4
3.2	Critical Junctions .....	4
3.3	Public Transport Services in the Vicinity .....	7
<b>4.</b>	<b>FUTURE TRAFFIC CONDITIONS.....</b>	<b>8</b>
4.1	Design year .....	8
4.2	Reference Traffic Flows .....	8
4.3	Planned / Committed Future Developments .....	9
4.4	Development Traffic Flows .....	12
<b>5.</b>	<b>TRAFFIC IMPACT ASSESSMENT .....</b>	<b>13</b>
5.1	Traffic Generation Calculation .....	13
5.2	Operational Assessment.....	13
5.3	Traffic Management Plan .....	15
<b>6.</b>	<b>SUMMARY AND CONCLUSION .....</b>	<b>17</b>
6.1	Summary .....	17
6.2	Conclusion .....	18



## 1. INTRODUCTION

### 1.1 Background

1.1.1 The concrete batching plant of the captioned Planning Approval is located at Sai Tso Wan Road, Tsing Yi and shown in **Figure 1.1**

1.1.2 The captioned planning approval (previous approved planning application no.: A/TY/136) was granted in 2019 and will expire on 2 Aug 2024. The Applicant would like to submit a renewal planning application for another 5 years.

1.1.3 We, CTA Consultants Limited (CTA), is commissioned as the traffic consultant to undertake a Traffic Impact Assessment (TIA) study for assessing the traffic impact, and to propose any measures if necessary.

### 1.2 Study Objectives

1.2.1 The main objective of this study are as follows:

- to carry out a traffic impact assessment to identify the acceptability of the concrete batching plant in traffic terms;
- to assess the existing traffic conditions in the vicinity of the plant;
- to forecast traffic demands in the adjacent road network in the design year 2029;
- to assess the impacts of traffic generated by the adjacent new developments in the road network; and
- to propose any traffic improvement measures for alleviating any foreseeable traffic problems if necessary.

### 1.3 Structure of this Report

1.3.1 Following this introductory chapter, there are 5 further chapters.

- **Chapter 2 – The Development**, which presents the site location and production information of the plant.
- **Chapter 3 – Existing Traffic Condition**, which describes the existing local road



network in the vicinity of Study Area, presents a summary of the traffic count survey and assesses the existing traffic conditions.

- **Chapter 4 – Future Traffic Conditions**, which estimates the future traffic flows for the plant on the surrounding road network.
- **Chapter 5 – Traffic Impact Assessment**, which study the operation performance of the critical junctions in design year.
- **Chapter 6 – Summary and Conclusion**, which presents the conclusions regarding the traffic issues associated with the plant.



## 2. THE DEVELOPMENT

### 2.1 Site Location

2.1.1 The plant is situated at Sai Tso Wan Road, as shown in **Figure 1.1**. It is located at the Western seaside of Tsing Yi, which can only be accessed by single 2-way 2-lane Sai Tso Wan Road.

### 2.2 Development Proposal

2.2.1 As advised by the operator, the operation of the plant is:

- The operation last for 12 hours from 7am to 7pm every day, from Mondays to Saturdays and occasionally on Sundays and public holidays. Occasional operation at night will be required.
- 3 loading/unloading areas to be provided and operated by the plant.
- The maximum hourly production capacity of the plant will be 300 m<sup>3</sup>/hr. However, the production rate would be limited to not exceeding 80% of the output rate, i.e 240m<sup>3</sup>/hr. This rate is limited under Specific Process (SP) License issued by Environmental Protection Department (EPD)
- Assuming each concrete mixer truck can carry 8m<sup>3</sup> concrete, it is deduced that the maximum number of a truck is be 240 / 8 = 30 trucks/hr.
- Aggregate, cement and PFA are transported by barge.

### 2.3 Traffic Arrangement

2.3.1 To facilitate the operation of the plant, the following types of parking facilities are provided within the plant:

- 22 nos. of HGV Waiting Spaces (11m × 3.5m);
- 3 nos. of Loading/Unloading Areas; and
- 4 nos. of Private Car Parking Spaces (5m × 2.5m)

2.3.2 A maximum of 25 trucks can stack within the Subject Site which could satisfy normal operation needs. Therefore, it is anticipated that the vehicles generated to/ from the plant will not queue along Sai Tso Wan Road outside the plant.



### **3. EXISTING TRAFFIC CONDITIONS**

#### **3.1 Existing Road Network**

3.1.1 The plant will be accessed through Tsing Yi Road West, Tsing Yi Road and Sai Tso Wan Road.

3.1.2 Sai Tso Wan Road is a 2-lane local road connecting Sai Tso Wan area and Tsing Yi Road West/Tsing Yi Road. It is a major road link providing access to/from various sites in Sai Tso Wan area.

#### **3.2 Critical Junctions**

3.2.1 In order to establish the existing traffic condition in the vicinity, traffic survey in form of manual classification counts was conducted at 23 critical junctions. The location of the surveyed junctions is indicated in **Figure 3.1** and their existing junction layout arrangements are given in **Figures 3.2 to 3.24** respectively.



**Table 3.1 Identified Critical Junctions**

Ref.	Junction	Type	Figure No.
J1	Cheung Tsing Highway / Tsing Yi Road West	Signalized	3.2
J2	Tsing Yi Road / Tsing Yi Hong Wan Road / Tsing Sha Highway	Signalized	3.3
J3	Tsing Sheung Road / Tsing Yi Road Priority	Priority	3.4
J4	Sai Tso Wan Road / Tsing Yi Road / Tsing Yi Road West	Signalized	3.5
J5	Entrance of VEC / Sai Tso Wan Road	Signalized	3.6
J6	Tsing Tim Street / Sai Tso Wan Road	Priority	3.7
J7	Tsing Yi Road West / Tsing Chin Street*	Priority	3.8
J8	Tsing Yi Road West / Tsing Hong Road	Signalized	3.9
J9	Tsing Yi Road West / Liu To Road	Signalized	3.10
J10	Tsing Yi Road West / Fung Shue Wo Road	Signalized	3.11
J11	Tsing Yi Road / Tsing Keung Street	Signalized	3.12
J12	Tsing Yi Heung Sze Wui Road / Chung Mei Road	Signalized	3.13
J13	Tsing Yi Heung Sze Wui Road / Cheung Wan Street	Priority	3.14
RA1	Tsing Yi Interchange	Roundabout	3.15
RA2	Tsing Yi Road West / Tsing Yi Hong Wan Road / Tsing Sha Highway	Roundabout	3.16
RA3	Hong Wan Road	Roundabout	3.17
RA4	Hong Wan Road / Tsing Ko Road	Roundabout	3.18
RA5	Tam Kon Shan Interchange	Roundabout	3.19
RA6	Tsing Yi Heung Sze Wui Road / Fung Shue Wo Road / Tsing King Road	Roundabout	3.20
RA7	Tsing Sheung Road / Tsing Yi Hong Wan Road	Roundabout	3.21
RA8	Tsing Hong Road / Tsing Yi Road	Roundabout	3.22
RA9	Tam Kon Shan Road / Tsing Yi North Costal Road	Roundabout	3.23
RA10	Tsing Ko Road / Tsing Sheung Road	Roundabout	3.24





3.2.2 The survey was conducted during the morning, logistic peak and evening peak periods 26 January 2024, at 07:30-09:30, 11:15-13:15 and 17:30-19:30. The survey provides details of the traffic situation in the nearby area. Based on surveyed traffic flows, it was found that the AM, logistic and PM peak hour occurred from 08:00 to 09:00, 11:15 to 12:15 and 17:30 to 18:30 respectively. The results of the observed traffic flows are presented in **Figure 3.25**.

3.2.3 Based on the observed traffic flows in **Figure 3.25**, the junction capacity assessment is carried out for the critical junctions and the results of the assessment are summarized in **Table 3.2** below.

**Table 3.2 Operational Performance of Identified Critical Junctions in 2024**

Ref.	Junction	Method of Control	Year 2024 Observed Case		
			RC/RFC <sup>(1)</sup>		
			AM Peak	Logistic Peak	PM Peak
J1	Cheung Tsing Highway / Tsing Yi Road West	Signalized	72%	62%	107%
J2	Tsing Yi Road / Tsing Yi Hong Wan Road / Tsing Sha Highway	Signalized	74%	88%	96%
J3	Tsing Sheung Road / Tsing Yi Road Priority	Priority	0.5	0.41	0.41
J4	Sai Tso Wan Road / Tsing Yi Road / Tsing Yi Road West	Signalized	46%	35%	115%
J5	Car Park Entrance / Sai Tso Wan Road	Signalized	121%	82%	127%
J6	Tsing Tim Street / Sai Tso Wan Road	Priority	0.34	0.27	0.21
J7	Tsing Yi Road West / Tsing Chin Street <sup>(2)</sup>	Priority	N/A	N/A	N/A
J8	Tsing Yi Road West / Tsing Hong Road	Signalized	60%	87%	103%
J9	Tsing Yi Road West / Liu To Road	Signalized	44%	69%	57%
J10	Tsing Yi Road West / Fung Shue Wo Road	Signalized	42%	82%	78%
J11	Tsing Yi Road / Tsing Keung Street	Signalized	21%	40%	42%
J12	Tsing Yi Heung Sze Wui Road / Chung Mei Road	Signalized	45%	78%	70%
J13	Tsing Yi Heung Sze Wui Road / Cheung Wan Street	Priority	0.17	0.25	0.13
RA1	Tsing Yi Interchange (North)	Roundabout	0.71	0.59	0.37
	Tsing Yi Interchange (South)	Roundabout	0.58	0.44	0.66
RA2	Tsing Yi Road West / Tsing Yi Hong Wan Road / Tsing Sha Highway	Roundabout	0.45	0.45	0.49
RA3	Hong Wan Road	Roundabout	0.45	0.37	0.40



RA4	Hong Wan Road / Tsing Ko Road	Roundabout	0.26	0.25	0.26
RA5	Tam Kon Shan Interchange	Roundabout	0.72	0.70	0.79
RA6	Tsing Yi Heung Sze Wui Road / Fung Shue Wo Road / Tsing King Road	Roundabout	0.38	0.32	0.38
RA7	Tsing Sheung Road / Tsing Yi Hong Wan Road	Roundabout	0.07	0.09	0.10
RA8	Tsing Hong Road / Tsing Yi Road	Roundabout	0.43	0.43	0.43
RA9	Tam Kon Shan Road / Tsing Yi North Costal Road	Roundabout	0.06	0.08	0.08
RA10	Tsing Ko Road / Tsing Sheung Road	Roundabout	0.27	0.25	0.19

Note: (1) RC = Reserve Capacity RFC = Ratio of Flow to Capacity for Priority Junction  
 (2) Only ingress traffic is allowed on Tsing Chin Street. No traffic conflicts or delay is expected in this location. Therefore, no junction assessment is required.

3.2.4 The results in **Table 3.2** show that the junctions are now operating with ample capacities in peak hours.

### 3.3 Public Transport Services in the Vicinity

3.3.1 Limited road-based public transport services are currently operating in the vicinity of the plant. Only one GMB route is operating close to the plant (within 500m radius from the plant) and the details of the GMB route are presented in **Table 3.3** below.

**Table 3.3 Existing Road-based Public Transport Services in the Vicinity**

Service	Route	Origin - Destination	Frequency (min)
GMB	88M	Kwai Fong Station – Sai Tso Wan Road (Hong Kong Unit Dockyard)	5 – 15



## 4. FUTURE TRAFFIC CONDITIONS

### 4.1 Design year

4.1.1 The original planning approval will be expire on 2 Aug 2024, as another 5 year of temporary use is applied, year 2029 is adopted as the design year for this study to assess the impact of the development related traffic on the local road network.

### 4.2 Reference Traffic Flows

4.2.1 To estimate the 2029 traffic flows in the local road network, an appropriate growth factor has to be identified for the area in the first instance based on historical trend and planning data.

#### Historical Trend

4.2.2 Transport Department has traffic count stations in the vicinity of the development. The traffic counts reported in the Annual Traffic Census (ATC) over a period of 6 years, between 2017 and 2022 are summarized in **Table 4.1**.

**Table 4.1 Historical Traffic Data from Annual Traffic Census**

ATC Stn No.	Road Name	Annual Average Daily Traffic						Annual Growth Rate
		2017	2018	2019	2020	2021	2022	
5038	Nam Wan Tunnel (from East Tsing Yi Viaduct to Cheung Tsing Highway)	50,940	54,280	55,040	37,850	41,090	41,060	-4.22%
5849	Tsing Yi Rd W (Tsing Nam St – Ching Hong Road)	15,410	15,640*	15,580*	15,430*	13,690	15,820	0.53%
6044	Tsing Yi Rd W (Tsing Hong Road – Fung Shue Wo Road)	20,260	19,350	19,280*	19,100*	19,840*	21,050	0.77%
6643	Sai Tso Wan Rd (Tsing Yi Rd – Dockyard Front Gate)	5,020	10,030	8,390	8,960	9,410	11,200	17.41%
<b>TOTAL</b>		<b>91,630</b>	<b>99,300</b>	<b>98,290</b>	<b>81,340</b>	<b>84,030</b>	<b>89,130</b>	<b>-0.55%</b>

\*AADT estimated by Growth Factor

4.2.3 As shown in **Table 4.1**, the average annual traffic growth pattern in the vicinity of the development shows a growth trend of -0.55% per year.

*2019-Based TPEDM planning data*

4.2.4 Reference has also been made to the latest 2019-Based Territorial Population Employment Data Matrices (TPEDM) planning data published by the Planning Department for projection of population and employment within the study district. The average annual growth rates in terms of population and employment from 2019 to 2031 are tabulated in **Table 4.2**.

**Table 4.2 2019-based Population and Employment Growth**

Data	Tsing Yi			Average Annual Growth Rate
	Year			
	2019	2026	2031	
Population	182,350	188,550	184,400	+0.09%
Employment	38,500	38,700	36,650	-0.41%
<b>Total</b>	<b>220,850</b>	<b>227,250</b>	<b>221,050</b>	<b>0.01%</b>

4.2.5 From **Table 4.2**, it is found that the average annual growth rates of population and employment in Tsing Yi are +0.01% per annum respectively.

*Adopted Growth Rate*

4.2.6 A.A.D.T. of ATC indicates that the traffic flow of the local road network has an average annual growth rate of -0.55%.

4.2.7 Whilst, the planning data indicates that the population and employment of the study area are expected to grow with an average annual growth rate of +0.01%.

4.2.8 As a conservative approach, annual growth rate **+1.0%** p.a. has been adopted for projecting traffic forecasts. It is deemed sufficient to allow for any unexpected future growth as a result of some changes in land use or development in the study area.

### 4.3 Planned / Committed Future Developments

4.3.1 There are numbers of planned/committed future developments in vicinity. The updated planning parameters are shown in **Table 4.3**. The locations of these future developments are shown in **Figure 4.1**.

4.3.2 The traffic trips generated from these planned/committed developments are estimated and shown in **Table 4.4**.

4.3.3 These traffic trips were assigned to the road network to obtain the reference traffic in the design year.

**Table 4.3 Development Schedule of Planned Development at Vicinity**

Ref.	Development Site / Planning Application No.	Use	Development Parameters	Completion Year
A	A/TY/131	Animal Welfare Centre	About 8,720m <sup>2</sup>	2024
B	Ching Hong Road North Public Housing Development	Public Housing	Phase 1: 851 units	2024
			Phase 2: 612 units	2024
			Phase 3: 1680 units	2029
			Retail: 2000m <sup>2</sup> Social Welfare Facilities	2024 - 2029
C	Agreement No. WQ/216/22	No details in public domain		
D	Proposed Advanced Construction Industry Building (ACIB) development in Tsing Yi	The project is under preliminary study stage and project details is not observed in public domain		
E	Housing Development at Tsing Yi Road West	Public Housing	3,400 units	2034/35
F <sup>(1)</sup>	Y/TY/2 - Tsing Yi Town Lot 80 and 108RP (Phase 1)	Private Housing	5,048 units	2028
	Y/TY/2 - Tsing Yi Town Lot 80 and 108RP (Phase 2)	Public Housing	4,704 units	2036
		Private Housing	5,323 units	2036
G	Government Dangerous Goods Warehouse and a government Owned Rental Dangerous Goods Warehouse to FSD	Warehouse	No details in public domain	
H	Multi-Storey Complex at Tsing Hung Road (CE 14/2016)	Container Storage and Cargo Handling	Site area: About 6 a	No target completion year
I	Land Exchange at Tsing Yi Hong Wan Road	No details in public domain		
J	Renewal of A/TY/135	Asphalt Plant	260 tonnes/hr (208 tones/hr as limited by SP License)	2024

4.3.4 Some of the planned developments in **Table 4.3** could not found in public domain, or no target completion year. Y/TY/2- Tsing Yi Town Lot 80 and 108RP is still under planning application and not approved yet. Thus, they would not be included in this assessment. The anticipated commissioning date of Route 11 (section between Yuen Long and North Lantau) is 2033, but no programme on TYLL section yet. The construction scale, methodology and works programme, etc., of Route 11 are unknown by the public, it is unlikely for us to estimate their construction traffic and it is the duty of the project proponents to conduct CTIAs to access the traffic condition and provide mitigation measures, such as TTA, road widening, junction improvement, peak hour banning, etc., to ensure their trips will not affect the traffic network.

**Table 4.4 Estimated Traffic Generations of Planned Vicinity Development**

Development Type	Average Flat Size m <sup>2</sup>	Unit	Trip Rate			
			AM Peak		PM Peak	
			Gen.	Att.	Gen.	Att.
Public Rental	40	Pcu/hr/flat	0.0432	0.0326	0.0237	0.0301
Retail	-	pcu/hr/100 sqm GFA	0.2296	0.2434	0.3100	0.3563
Developments			Trips (Pcu/hr)			
A <sup>(1)</sup>	A/TY/131		64	172	115	72
B	Ching Hong Road North Public Housing Development	Phase 1	37	28	20	26
		Phase 2	26	20	15	18
		Phase 3	73	55	40	51
		Retail	5	5	6	7
		Kindergarten <sup>(2)</sup>	30	30	30	30
		Social Welfare Facilities <sup>(3)</sup>	10	10	10	10
C <sup>(1)</sup>	Renewal of A/TY/135		45	45	45	45

Note: (1) Development trips according to its TIA report

(2) Reference from other public housing TIA reports (Sheung Shui Area 4 and 30)

(3) Nominal Trips

4.3.5 The 2029 reference flows are then derived by applying the annual growth rate plus the additional traffic generations of the developments in Tsing Yi.

$$\begin{array}{l}
 \text{2029} \\
 \text{Reference Flows} \\
 \text{(without the} \\
 \text{Plant)} \\
 \text{=} \\
 \text{2024} \\
 \text{Observed} \\
 \text{Flows} \\
 \text{x} \\
 \text{Adopted Growth} \\
 \text{Factor} \\
 \text{(i.e. +1\% p.a. for} \\
 \text{5 years)} \\
 \text{+} \\
 \text{Traffic Flows of} \\
 \text{Proposed} \\
 \text{Developments at} \\
 \text{Tsing Yi}
 \end{array}$$



#### **4.4 Development Traffic Flows**

4.4.1 It is revealed that this is a renewal application, the concrete batching plant is already under operation and the development parameter is no change. Therefore, there will be **no additional traffic trip**. The 2029 design flows are shown in **Figure 4.2**.

**2029 Design Flows = 2029 Reference Flows**

## 5. TRAFFIC IMPACT ASSESSMENT

### 5.1 Traffic Generation Calculation

5.1.1 As there is no change in the operation scale of the plant, no additional trips are generated. The traffic generation adopted in the approved TIA for the exiting plant (A/TY/136) is summarized in **Table 5.1** below for reference:

**Table 5.1 Adopted Hourly Traffic Generation of the Concrete Batching Plant**

Types of Vehicles	Traffic Generation (in veh/hr)	Traffic Generation (in pcu/hr) <sup>(1)</sup>
Concrete Mixer Truck	<u>30</u>	<u>75</u>
Admixture tanker & Waste Disposal Truck	N/A <sup>(2)</sup>	N/A <sup>(2)</sup>

Notes: (1) PCU factor of 2.5 has been adopted for trucks.

(2) Delivery of admixture and waste will be carried out during off-peak hours.

The admixture tanker will only be required twice a week during off-peak hours.

The waste disposal truck will only be required once per 2-3 days during off-peak hours.

Aggregates and cement will be delivered by barge.

### 5.2 Operational Assessment

5.2.1 Based on the design traffic flows in **Figure 5.1**, a junction capacity assessment is carried out for the key junctions and the results of the assessment are summarized in **Table 5.2** below.





**Table 5.2 Junction Performance of Critical Junctions in Design Year 2029**

Ref.	Junction	Method of Control	Year 2029 Design Case		
			RC/RFC <sup>(1)</sup>		
			AM Peak	Logistic Peak	PM Peak
J1	Cheung Tsing Highway / Tsing Yi Road West	Signalized	42%	42%	78%
J2	Tsing Yi Road / Tsing Yi Hong Wan Road / Tsing Sha Highway	Signalized	66%	78%	85%
J3	Tsing Sheung Road / Tsing Yi Road Priority	Priority	0.54	0.45	0.45
J4	Sai Tso Wan Road / Tsing Yi Road / Tsing Yi Road West	Signalized	33%	24%	89%
J5	Entrance of VEC / Sai Tso Wan Road	Signalized	99%	65%	102%
J6	Tsing Tim Street / Sai Tso Wan Road	Priority	0.38	0.30	0.23
J7	Tsing Yi Road West / Tsing Chin Street <sup>(2)</sup>	Priority	N/A	N/A	N/A
J8	Tsing Yi Road West / Tsing Hong Road	Signalized	39%	59%	81%
J9	Tsing Yi Road West / Liu To Road	Signalized	38%	61%	49%
J10	Tsing Yi Road West / Fung Shue Wo Road	Signalized	17%	44%	45%
J11	Tsing Yi Road / Tsing Keung Street	Signalized	<b>2%</b>	15%	23%
J12	Tsing Yi Heung Sze Wui Road / Chung Mei Road	Signalized	26%	52%	51%
J13	Tsing Yi Heung Sze Wui Road / Cheung Wan Street	Priority	0.18	0.26	0.14
J14	Tsing Yi Road / Planned New Road <sup>(3)</sup>	Signalized	>100%	>100%	>100%
RA1	Tsing Yi Interchange (North)	Roundabout	0.76	0.63	0.40
	Tsing Yi Interchange (South)	Roundabout	0.63	0.48	0.73
RA2	Tsing Yi Road West / Tsing Yi Hong Wan Road / Tsing Sha Highway	Roundabout	0.48	0.48	0.53
RA3	Hong Wan Road / Planned New Road <sup>(3)</sup>	Roundabout	0.47	0.39	0.42
RA4	Hong Wan Road / Tsing Ko Road	Roundabout	0.27	0.26	0.28
RA5	Tam Kon Shan Interchange	Roundabout	0.82	0.79	0.89
RA6	Tsing Yi Heung Sze Wui Road / Fung Shue Wo Road / Tsing King Road	Roundabout	0.47	0.40	0.46
RA7	Tsing Sheung Road / Tsing Yi Hong Wan Road	Roundabout	0.08	0.09	0.11
RA8	Tsing Hong Road / Tsing Yi Road	Roundabout	0.46	0.46	0.46
RA9	Tam Kon Shan Road / Tsing Yi North Costal Road	Roundabout	0.07	0.08	0.08
RA10	Tsing Ko Road / Tsing Sheung Road	Roundabout	0.28	0.27	0.20

Note: (1) RC = Reserve Capacity RFC = Ratio of Flow to Capacity for Priority Junction  
(2) Only ingress traffic is allowed on Tsing Chin Street. No traffic conflicts or delay is expected

*in this location. Therefore, no junction assessment is required.*

(3) *New Road between Tsing Yi Road / Hong Wan Road was considered*

5.2.2 Based on the assessment presented in **Table 5.2**, all junctions will be operating with ample capacities during design year except J11. As the concrete batching plant is already under operation and the development parameter is no change under this renewal application, there will be no additional traffic impact caused by the plant.

5.2.3 J11 will near its capacity due to the increase of left turn traffic by Animal Welfare Centre (A/TY/131) from Tsing Yi Road southbound to Tsing Keung Street. However, due to the committed restriction listed in **Tables 5.2** and **5.3** below, our concrete trucks cannot pass through RA6 in peak hour which is connected to J11 at the north. Thus will not concrete trucks will move to the Tsing Yi Road southbound of J11 and will not worsen the case.

### 5.3 Traffic Management Plan

5.3.1 In previous application, in order to avoid traffic impact induced by the plant to Tsing Yi Town Centre, restrictions were given to the concrete trucks of the plant. They are not allowed to pass through critical junctions during the peak hour periods (Except emergency and exceptional cases which would be considered by various Government Departments) and are summarized in **Table 5.2**.

**Table 5.2 Restrictions at Junction of Sai Tso Wan Road / Tsing Yi Road / Tsing Yi Road West**

Ref.	Junction	Restriction	Restricted Hours
J4	Sai Tso Wan Road / Tsing Yi Road / Tsing Yi Road West	<u>No right turn</u> from Sai Tso Wan Road to Tsing Yi Road West	AM Peak 07:45-09:15



**Table 5.3 Restriction at Other Critical Junctions**

Ref.	<u>No trucks</u> should be allowed to pass through the following junctions	Restricted Hours		
		AM Peak 07:45 – 9:15	Logistic Peak 11:45 – 12:45	PM Peak 16:30 – 17:30
J8	Tsing Yi Road West / Ching Hong Road	X	X	X
RA1	Tsing Yi Interchange	X	○	X
RA2	Tsing Yi Road West / Tsing Yi Hong Wan Road / Tsing Sha Highway	X	X	X
RA5	Tam Kon Shan Interchange	X	○	○
RA6	Tsing Yi Heung Sze Wui Road / Fung Shue Wo Road / Tsing King Road (Together with Junction Cheung Wan Street / Tsing Yi Heung Sze Wui Road)	X	X	X

X: Not allowed to pass through

○: Allow to pass through

5.3.2 Detailed Traffic Management Plan will be formulated and submitted to Transport Department separately.



## 6. SUMMARY AND CONCLUSION

### 6.1 Summary

- 6.1.1 The captioned planning approval (previous approved planning application no.: A/TY/136) was granted in 2019 and will expire on 2 Aug 2024. The Applicant would like to submit a renewal planning application for another 5 years.
- 6.1.2 We, CTA Consultants Limited (CTA), is commissioned as the traffic consultant to undertake a Traffic Impact Assessment (TIA) study for assessing the traffic impact, and to propose any measures if necessary.
- 6.1.3 To appraise the existing traffic conditions, a traffic count survey was conducted in the surrounding road network of the plant. Moreover, current operational performance of the critical junctions was assessed with the observed traffic flows. The operational assessment results revealed that all critical junctions are at present operating with reasonable capacity in peak hours.
- 6.1.4 In order to assess the impact of the development related traffic on the local road network, the 5th year after the approval of planning application of the plant (i.e. year 2029) has been adopted as the design year for this study.
- 6.1.5 To reveal the traffic impact of various proposed developments in the vicinity, traffic generations by the developments in the vicinity have also been taken into consideration.
- 6.1.6 It is noted that the concrete plant is already operating currently, thus **no additional traffic** would be added to the road network by this plant under this application and 2029 design flows are the same as reference flows. It is noted that growth rate is also applied to the existing trips of the application plant as conservative approach.




6.1.7 All the assessed junctions will be operating with ample spare capacity in design year except J11, but our concrete trucks will not pass through this junction in peak hour due to the committed restriction in previous planning application and therefore would not worsen the case.

## **6.2 Conclusion**

6.2.1 In conclusion, this Traffic Impact Assessment (TIA) has demonstrated that the application plant will not generate additional traffic to the surrounding road network and the junctions in vicinity would have ample capacities during design year 2029.


6.2.2 Hence, it is concluded that the renewal of plant at the Application Site is acceptable from traffic engineering view point.




**LEGEND :**



**SUBJECT SITE**

FIGURE NO.: <b>1.1</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.: 24001HK		DRAWING TITLE: <b>LOCATION PLAN</b>	
SCALE: 1 : 7000 (IN A4 SIZE)	DATE: 22 FEB 2024	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>	



**LEGEND :**






-  22 NOS OF TRUCK PARKING SPACE FOR OPERATION (11m x 3.5m)
-  3 NOS OF LOADING / UNLOADING AREA
-  4 NOS OF PRIVATE CAR PARKING SPACE (5m x 2.5m)

FIGURE NO.:	<b>2.1</b>	PROJECT TITLE:	Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136
PROJECT NO.:	24001HK	DRAWING TITLE:	THE PRELIMINARY LAYOUT OF THE PROPOSED CONCRETE BATCHING PLANT
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 20 MAY 2024	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>	




**LEGEND :**  
 SUBJECT SITE

FIGURE NO.: **3.1**  
 PROJECT NO.: 24001HK  
 SCALE: 1: 12000 @A3  
 DATE: 13 MAY 2024

PROJECT TITLE:  
 Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136  
 DRAWING TITLE:  
**CRITICAL JUNCTION**



**CTA Consultants Limited**  
 志達顧問有限公司






FIGURE NO.:		PROJECT TITLE:	
3.2		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		DRAWING TITLE:	
24001HK		EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / CHEUNG TSING HIGHWAY (J1)	
SCALE:	DATE:		
1 : 500 @A4	13 MAY 2024		



CTA Consultants Limited  
志達顧問有限公司





FIGURE NO.: <b>3.3</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> 志達顧問有限公司
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING HUNG ROAD / TSING YI ROAD (J2)</b>	
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024		





FIGURE NO.:		PROJECT TITLE:		 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
3.4		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136		
PROJECT NO.:		DRAWING TITLE:		
24001HK		EXISTING JUNCTION LAYOUT OF TSING SHEUNG ROAD / TSING YI ROAD (J3)		
SCALE:	DATE:			
1 : 500 (IN A4 SIZE)	13 MAY 2024			





FIGURE NO.: <b>3.5</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF SAI TSO WAN ROAD / TSING YI ROAD WEST / TSING YI ROAD (J4)</b>
SCALE: 1 : 500 @A4	DATE: 13 MAY 2024	





EXISTING METHOD OF CONTROL

14.0




FIGURE NO.:  
**3.6**

PROJECT TITLE:  
Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136

PROJECT NO.:  
**24001HK**

DRAWING TITLE:  
**EXISTING JUNCTION LAYOUT OF ENTRANCE OF VEC / SAI TSO ROAD (J5)**

SCALE:  
1 : 500 @A4

DATE:  
13 MAY 2024








FIGURE NO.: <b>3.7</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> 志達顧問有限公司
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING TIM STREET / SAI TSO WAN ROAD (J6)</b>	
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024		



FIGURE NO.: <b>3.8</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: EXISTING JUNCTION LAYOUT OF YI ROAD WEST / TSING CHIN STREET (J7)	
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024		




FIGURE NO.:		3.9		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / TSING HONG ROAD (J8)	
SCALE:	DATE:						
1 : 500 (IN A4 SIZE)	13 MAY 2024						









FIGURE NO.: <b>3.10</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / LIU TO ROAD (J9)	
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024		

EXISTING METHOD OF CONTROL






FIGURE NO.: <b>3.11</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136
PROJECT NO.: 24001HK		DRAWING TITLE: EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / FUNG SHUE WO ROAD (J10)
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024	





EXISTING METHOD OF CONTROL





FIGURE NO.: <b>3.12</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> 志達顧問有限公司
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING YI HEUNG SZE WUI ROAD / CHEUNG WAN STREET (J11)</b>	
SCALE: 1 : 500 @A4	DATE: 14 MAY 2024		





FIGURE NO.: <b>3.13</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING YI HEUNG SZE WUI ROAD / CHUNG MEI STREET (J12)</b>	
SCALE: 1 : 500 @A4	DATE: 14 MAY 2024		





FIGURE NO.: <b>3.14</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING YIP ROAD / TSING KEUNG STREET (J13)</b>	
SCALE: 1 : 500 (IN A4 SIZE)	DATE: 13 MAY 2024		




FIGURE NO.:  
**3.15**

PROJECT TITLE:  
Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136

PROJECT NO.:  
24001HK

DRAWING TITLE:  
EXISTING JUNCTION LAYOUT OF  
SING YI INTERCHANGE (RA1)

SCALE:  
1 : 1000  
(IN A4 SIZE)

DATE:  
14 MAY 2024






FIGURE NO.:		PROJECT TITLE:	
<b>3.16</b>		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		DRAWING TITLE:	
24001HK		<b>EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / TSING YI HONG WAN ROAD / TSING SHA HIGHWAY (RA2)</b>	
SCALE:	DATE:		
1 : 1000 (IN A4 SIZE)	13 MAY 2024		







FIGURE NO.: <b>3.17</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: <b>EXISTING JUNCTION LAYOUT OF TSING YI ROAD WEST / FUNG SHUE WO ROAD (RA3)</b>	
SCALE: 1 : 1000 (IN A4 SIZE)	DATE: 13 MAY 2024		






FIGURE NO.:		3.18		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TSING YI HONG WAN ROAD / TSING KO ROAD (RA4)	
SCALE:	DATE:						
1 : 1000 (IN A4 SIZE)	13 MAY 2024						






FIGURE NO.:		3.19		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TAM KON SHAN INTERCHANGE (RA5)	
SCALE:	DATE:						
1 : 1200 (IN A4 SIZE)	13 MAY 2024						







FIGURE NO.: <b>3.20</b>		PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	 <b>CTA Consultants Limited</b> <b>志達顧問有限公司</b>
PROJECT NO.: 24001HK		DRAWING TITLE: EXISTING JUNCTION LAYOUT OF TSING YI HEUNG SZE WUI ROAD / FUNG SHUE WO ROAD / TSING KING ROAD (RA6)	
SCALE: 1 : 1200 (IN A4 SIZE)	DATE: 13 MAY 2024		




FIGURE NO.:		3.21		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TSING SHEUNG ROAD / TSING YI HONG WAN ROAD (RA7)	
SCALE:	DATE:						
1 : 1000 (IN A4 SIZE)	13 MAY2024						






FIGURE NO.:		3.22		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TSING HONG ROAD / TSING YI ROAD (RA8)	
SCALE:	DATE:						
1 : 500	13 MAY 2024						
(IN A4 SIZE)							



**CTA Consultants Limited**  
志達顧問有限公司




FIGURE NO.:		3.23		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TAM KON SHAN ROAD / TSING YI NORTH COSTAL ROAD (RA9)	
SCALE:	DATE:						
1 : 500 (IN A4 SIZE)	13 MAY 2024						



CTA Consultants Limited  
志達顧問有限公司





FIGURE NO.:		<b>3.24</b>		PROJECT TITLE:		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		24001HK		DRAWING TITLE:		EXISTING JUNCTION LAYOUT OF TSING KO ROAD / TSING SHEUNG ROAD (RA10)	
SCALE:	DATE:						
1 : 1000 (IN A4 SIZE)	13 MAY 2024						




**CTA Consultants Limited**  
**志達顧問有限公司**







**LEGEND :**



**SUBJECT SITE**  
**PLANNED DEVELOPMENT**



FIGURE NO.:	<b>4.1</b>
PROJECT NO.:	24001HK
SCALE:	DATE:
1 : 11000 @A3	04 MAR 2024

PROJECT TITLE:	Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136
DRAWING TITLE:	<b>PLANNED DEVELOPMENT IN VICINITY</b>



**CTA Consultants Limited**  
**志達顧問有限公司**

METHOD OF CONTROL



LEGEND :

- [Symbol] LIMIT OF WORKS SITE
- [Symbol] PROPOSED CARRIAGEWAY WITH FLEXIBLE PAVEMENT
- [Symbol] PROPOSED FOOTPATH WITH SINGLE'S POWER
- [Symbol] PROPOSED PESTERIAN REFUGE ISLAND
- [Symbol] PROPOSED KERBED TRAFFIC COLLECTION ISLAND
- [Symbol] EXISTING CARRIAGEWAY TO BE RECONSTRUCTED
- [Symbol] EXISTING FOOTPATH TO BE RECONSTRUCTED
- [Symbol] EXISTING SIDEWALK AREA TO BE RECONSTRUCTED
- [Symbol] PROPOSED PESTERIAN CROSSING

NO.	DATE	REVISION
1	08/05/2024	GENERAL REVISION

NO.	DATE	REVISION
1	08/05/2024	GENERAL REVISION

DESIGNED BY: P. F. YU  
 CHECKED BY: H. K. CHU  
 DATE: 08/05/2024

PROJECT NO.: HW/2021/11  
 DRAWING NO.: HW/2021/11-GL001-A  
 SCALE: 1:500

PROJECT TITLE: NEW ROAD CONNECTING TSING YI ROAD AND TSING YI HONG WAN ROAD, TSING YI

GENERAL LAYOUT

WORKS DIVISION  
 HIGHWAYS DEPARTMENT  
 HONG KONG

FIGURE NO.: **4.2**

PROJECT NO.: 24001HK

SCALE: N.T.S (IN A4 SIZE)  
 DATE: 07 MAY 2024

PROJECT TITLE: Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136

DRAWING TITLE: PLANNED JUNCTION LAYOUT OF NEW ROAD CONNECTING TSING YI HONG WAN ROAD AND TSING YI ROAD






FIGURE NO.:		PROJECT TITLE:	
5.1		Concrete Batching Plant at Tsing Yi - Renewal Application A/TY/136	
PROJECT NO.:		DRAWING TITLE:	
24001HK		2029 DESIGN TRAFFIC FLOW	
SCALE:	DATE:	<b>CTA Consultants Limited</b> 志達顧問有限公司	
1 : 12000 @ A3	14 MAY 2024		



# **Appendix 1**


## **Junction Calculation Sheets**

Junction: (J1) Tsing Yi Road West / Cheung Tsing Highway																										
Description: 2024 Observed Traffic Flow																										
Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		A.M. Peak			P.M. Peak					
						Left	Right			A.M.	P.M.			A.M.	P.M.	A.M.	P.M.	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y			
Tsing Yi Road West	S	↓	2	A	3.5	0	0	0	1	0%	0%	1965	6135	1965	1965	5905	5825	205	0.104	0.104	150	0.076	0.078			
	S	↔	2	A	3.3	0	20	0	0	43%	100%	2085	0	2020	1940	0	0	210	0.104		151	0.078				
	S	↔	2	A	3.3	0	17.5	0	0	100%	100%	2085	0	1920	1920	0	0	200	0.104		149	0.078				
Cheung Tsing Highway	E	↑	3	A,B	3.4	20	0	0	1	100%	100%	1955	1955	1820	1820	1820	1820	435	0.239		355	0.195				
	E	↔	4	B	3.5	0	30	0	0	100%	100%	2105	4210	2005	2005	3990	3990	211	0.105		138	0.069				
	E	↓	4	B	3.5	0	25	0	0	100%	100%	2105	0	1985	1985	0	0	209	0.105	0.105	137	0.069	0.069			
Tsing Yi Road West	N	↔	1	C	3.6	20	0	6.5	1	100%	100%	1702	3544	1585	1585	3425	3425	375	0.237	0.237	320	0.202	0.202			
	N	↑	1	C	3.6	0	0	6.5	0	0%	0%	1842	0	1840	1840	0	0	310	0.168		275	0.149				
*																										
Pedestrian crossing		↔	5P	C	Min. Green time = 5GM + 10FG = 15s																					
		↕	6P	C	Min. Green time = 5GM + 6FG = 11s																					
		↔	7P	A,B	Min. Green time = 5GM + 9FG = 14s																					
		↕	8P	B	Min. Green time = 5GM + 10FG = 15s																					
Notes:												Traffic Flow (pcu / hr)				A.M. Check Phase		P.M. Check Phase								
																ey 0.446 0.476 L (sec) 13 9 C (sec) 100 100 y pract. 0.783 0.819 R.C. (%) 76% 72%		ey 0.349 0.397 L (sec) 13 9 C (sec) 105 105 y pract. 0.789 0.823 R.C. (%) 126% 107%								
Stage / Phase Diagrams																										
																					I/G = 5		I/G = 5		I/G = 6	

Junction: (J2) Tsing Hung Road / Tsing Yi Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)			Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right	N	AM	PM		AM	PM			AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Tsing Yi Road	S	↓	1	A	3.5	0.0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	362	0.184		261	0.133			
	S	↓	1	A	3.5	0.0	0	0	0%	0%	2105	0	2105	2105	0	0	388	0.184		279	0.133			
	S	←	1	A	3.6	0.0	18	0	100%	100%	2115	2115	1950	1950	1950	1950	350	0.179		360	0.185	0.185		
Tsing Yi Road	N	↑	4	C	4.0	30.0	0	1	100%	100%	2015	2015	1920	1920	1920	1920	55	0.029		50	0.026			
	N	↑	4	C	3.5	0.0	0	0	0%	0%	2105	4210	2105	2105	4210	4210	315	0.150	0.150	258	0.122			
	N	↑	4	C	3.5	0.0	0	0	0%	0%	2105	0	2105	2105	0	0	315	0.150		258	0.122	0.122		
Tsing Hung Road	E	→	2	A,B	3.3	25.0	0	1	100%	100%	1945	1945	1835	1835	1835	1835	500	0.272	0.272	325	0.177			
	E	→	3	B	4.0	0.0	22	0	100%	100%	2155	2155	2015	2015	2015	2015	45	0.022		30	0.015			
Pedestrian Crossing		↔	5P	D	Min. Green time = 5GM + 7FG = 12s																			
		↔	6P	A,B,D	Min. Green time = 5GM + 5FG = 10s																			
		↔	7P	C,D	Min. Green time = 5GM + 10FG = 15s																			
		↔	8P	C,D	Min. Green time = 5GM + 5FG = 10s																			

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	A,B,C,D		A,B,C,D		A,B,C,D		A,B,C,D	
			AM Peak Check Phase	AB,C,D	PM Peak Check Phase	AB,C,D	AB,C,D	AB,C,D		
	500(325) 45(30)		Ey 0.356 L (sec) 33 C (sec) 120 y pract. 0.653 R.C. (%) 83%	0.422	Ey 0.307 L (sec) 33 C (sec) 100 y pract. 0.603 R.C. (%) 96%	0.299	22	100	0.702	134%



I/G = 2	I/G = 6 + Min. G 5	I/G = 5	I/G = 5 + 12		
I/G = 2	I/G = 6 + Min. G 5	I/G = 5	I/G = 5 + 12		

Junction: ( J4 ) Sai Tso Wan Road / Tsing Yi Road West / Tsing Yi Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% ) uphill Gradient	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		A.M. Peak			P.M. Peak		
					Left	Right	A.M.	P.M.			A.M.	P.M.			Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Tsing Yi Road	NE	↖	1	A	4.5	15	0	6.5	1	100%	100%	1792	1792	1630	1630	260	0.160	0.160	220	0.135	0.135	
	NE	↗	1	A	3.4	0	0	6.5	0	0%	0%	1822	1822	1820	1820	220	0.121		210	0.115		
Sai Tso Wan Road	NW	↖	3	C,D	3.8	15	0	0	1	100%	100%	1995	1995	1815	1815	460	0.253		390	0.215		
	NW	↗	4	D	3.8	0	25	0	0	100%	100%	2135	2135	2015	2015	215	0.107	0.107	180	0.089	0.089	
Tsing Yi Road West	SE	↘	2	B,C	3.4	0	0	0	1	0%	0%	1955	1955	1955	1955	225	0.115		140	0.072		
	SE	↙	2	B,C	3.7	0	25	0	0	100%	100%	2125	2125	2005	2005	510	0.254	0.254	245	0.122	0.122	
Pedestrian crossing		↑ ↓ ← →	5p 6p 7p 8p	A,B D B,C A,D	Min. Green time = 5GM + 8FG = 13s Min. Green time = 5GM + 10FG = 15s Min. Green time = 5GM + 9FG = 14s Min. Green time = 5GM + 7FG = 12s																	

Notes:	<p>Traffic Flow (pcu / hr)</p>	<p>A.M. Check Phase</p> <p>Ey 0.521 L (sec) 19 C (sec) 120 y pract. 0.758 R.C. (%) 46%</p>	<p>P.M. Check Phase</p> <p>Ey 0.346 L (sec) 19 C (sec) 110 y pract. 0.745 R.C. (%) 115%</p>
--------	--------------------------------	--	---

Stage / Phase Diagrams			
<p><b>A</b></p>	<p><b>B</b></p>	<p><b>C</b></p>	<p><b>D</b></p>
I/G = 7	I/G = 10		I/G = 5


TRAFFIC SIGNALS CALCULATION

Job No: 24001HK

Junction: **(J5) Sai Tso Wan Road Near VEC**  
 Description: **2024 Observed Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak					
						Left	Right		AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y			
						Sai Tso Wan Road	EB		→	3			A	4.0	0.0	0	1	0%	0%	2015	2015	2015	2015	2015	2015
Sai Tso Wan Road	WB	←	1	A,B	4.0	0.0	0	1	0%	0%	2015	2015	2015	2015	2015	2015	530	0.263		640	0.318	0.318			
Sai Tso Wan Road	WB	↖	2	B,C	4.0	0.0	10	0	100%	100%	2155	2155	1875	1875	1875	1875	145	0.077	0.077	35	0.019				

Notes: (None)	Traffic Flow (pcu / hr)	AM (PM) Peak	A,BC		AB,C		A,BC		AB,C	
			AM Peak Check Phase		PM Peak Check Phase					
		565(465) →	εy	0.358	0.263	εy	0.249	0.318		
		↖ 145(35)	L (sec)	11	18	L (sec)	11	18		
		← 530(640)	C (sec)	91	91	C (sec)	91	91		
			y pract.	0.791	0.722	y pract.	0.791	0.722		
			R.C. (%)	<b>121%</b>	<b>174%</b>	R.C. (%)	<b>217%</b>	<b>127%</b>		




I/G = 6      I/G = 7



Junction: (J8) Tsing Yi Road West / Ching Hong Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right	AM	PM			AM	PM			AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Tsing Yi Road West	S	↓	1	A	3.0	0.0	0	0	5.5	0	0%	0%	1824	3698	1824	1824	3698	3698	180	0.099	0.197	121	0.066	0.121
	S	↓	1	A	3.5	0.0	0	0	5.5	0	0%	0%	1874	0	1874	1874	0	0	185	0.099		124	0.066	
	S	↘	1	A	3.7	10.0	0	0	5.5	1	100%	100%	1754	1754	1525	1525	1525	1525	300	0.197		185	0.121	
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	179	0.091		200	0.102	
	N	↑	2	A,B	3.5	0.0	0	0	0	0	0%	0%	2105	0	2105	2105	0	0	191	0.091		215	0.102	
	N	↗	3	B	3.3	0.0	18	0	0	0	100%	100%	2085	2085	1925	1925	1925	1925	275	0.143	0.143	255	0.132	0.132
Ching Hong Road	W	←	4	C	3.4	18.0	20	0	0	16% / 84%	15% / 85%	2095	0	1945	1945	0	0	280	0.144	0.144	248	0.128	0.128	
	W	↓	4	C	3.4	15.0	0	0	0	1	100%	100%	1955	4050	1775	1775	3720	3720	255	0.144		227	0.128	
Pedestrian crossing		↕	5P	A,B																				
		↕	6P	C																				
Min. Green time = 11s (G) + 8s (FS) = 19s Min. Green time = 5s (G) + 12s (FS) = 17s																								
Pedestrian Crossing																								

Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 370(415) 275(255)	Weekday AM Peak 365(245) 300(185)	AM Peak Check Phase Ey 0.483 L (sec) 14 C (sec) 100 y pract. 0.774 R.C. (%) 60%	PM Peak Check Phase Ey 0.382 L (sec) 14 C (sec) 100 y pract. 0.774 R.C. (%) 103%



Junction: (J9) Tsing Yi Road West / Liu To Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Tsing Yi Road West	S	↓	2	A,B	3.3	0.0	0	5	1	0%	0%	1735	3610	1735	1735	3610	3610	202	0.116		171	0.098	
	S	↓	2	A,B	3.3	0.0	0	5	0	0%	0%	1875	0	1875	1875	0	0	218	0.116		184	0.098	
	S	↙	3	B	3.3	0.0	22	5	0	100%	100%	1875	1875	1755	1755	1755	1755	295	0.168	0.168	320	0.182	0.182
Tsing Yi Road West	N	↕	1	A	3.2	10.0	0	0	1	51%	38%	1935	4100	1795	1830	3960	3995	274	0.153	0.153	286	0.156	0.156
	N	↑	1	A	4.1	0.0	0	0	0	0%	0%	2165	0	2165	2165	0	0	331	0.153		339	0.156	
Liu To Road	E	↗	5	B,C	3.2	10.0	0	0	1	100%	100%	1935	1935	1685	1685	1685	1685	390	0.231		280	0.166	
	E	↘	4	C	4.1	0.0	18	0	0	100%	100%	2165	2165	2000	2000	2000	2000	240	0.120	0.120	75	0.038	0.038
Pedestrian crossing		↕	6P	A,D																			
		↕	7P	C,D																			
		↔	8P	D																			
Pedestrian Crossing																							

A,B,C,D A,B,C,D A,B,C,D A,B,C,D


Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 	AM Peak Check Phase		PM Peak Check Phase	
		6y 0.384 0.441 L (sec) 34 38 C (sec) 130 130 y pract. 0.665 0.637 R.C. (%) 73% 44%	6y 0.323 0.376 L (sec) 34 38 C (sec) 110 110 y pract. 0.622 0.589 R.C. (%) 93% 57%		

Stage / Phase Diagrams			
L/G = 5	L/G = 7	L/G = 5	L/G = 11 + Ped 13

Junction: (J10) Tsing Yi Road West / Fung Shue Wo Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Site Factor	Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM				AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Fung Shue Wo Road (To Tsing Yi Road West)	S	↓	1	A,D	4.1	0.0	0	3	0	0%	0%	1	2039	4058	2039	2039	4058	4058	289	0.142	0.233	266	0.131	0.194
	S	↓	1	A,D	3.9	0.0	0	3	0	0%	0%	1	2019	0	2019	2019	0	0	286	0.142		264	0.131	
Fung Shue Wo Road (To Fung Shue Wo Road)	S	↓	1	A,D	4.0	0.0	0	3	1	0%	0%	1	1889	2294.8	1889	1889	2294.8	2294.8	440	0.233		366	0.194	
	S	↓	1	A,D	4.0	0.0	0	3	0	0%	0%	0.2	405.8	0	405.8	405.8	0	0	95	0.233		79	0.194	
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%	0%	1	1965	2491.3	1965	1965	2491.25	2491.25	513	0.261		517	0.263	
	N	↑	2	A,B	3.5	0.0	0	0	0	0%	0%	0.25	526.25	0	526.25	526.25	0	0	137	0.261		138	0.263	
	N	↗	3	B	3.6	0.0	18	0	0	100%	100%	1	2115	2115	1950	1950	1950	1950	210	0.108	0.108	140	0.072	0.072
Fung Shue Wo Road	N	↙	4	C	3.8	35.0	0	3	1	100%	100%	1	1869	2193.6	1790	1790	2100	2100	124	0.069		119	0.067	
	N	↙	4	C	4.0	38.0	0	3	0	100%	100%	0.16	324.64	0	310	310	0	0	21	0.069		21	0.067	
Fung Shue Wo Road	N	↗	4	C	3.6	0.0	43	3	0	100%	100%	0.23	457.47	2446.5	440	440	2355	2355	96	0.219	0.219	79	0.180	0.180
	N	↗	4	C	3.6	0.0	40	3	0	100%	100%	1	1989	0	1915	1915	0	0	419	0.219		346	0.180	
Pedestrian crossing		↔	5P	D																				
		↔	6P	B,C																				
		↕	7P	A,C,D																				
		↕	8P	A,B,D																				

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	AM Peak Check Phase	PM Peak Check Phase
		575(530) 535(445)	Ey 0.560 L (sec) 12 C (sec) 100 y pract. 0.792 R.C. (%) 42%	Ey 0.446 L (sec) 12 C (sec) 100 y pract. 0.792 R.C. (%) 78%



Junction: (J11) Tsing Yi Heung Sze Wui Road / Cheung Wan Street  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak			
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y	
Tsing Yi Heung Sze Wui Road	N	↑	2	A,B	3.5	0.0	0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	616	0.313		555	0.283	0.283	
	N	↑	2	A,B	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	659	0.313		595	0.283		
Cheung Wan Street	W	↙	3	C	3.5	18.0	20	0	0	33% / 67%	55% / 45%	2105	0	1955	1950	0	0	374	0.191	0.191	287	0.147	0.147	
	W	↘	3	C	3.5	15.0	0	0	1	100%	100%	1965	4070	1785	1785	3740	3735	341	0.191		263	0.147		
Tsing Yi Heung Sze Wui Road	S	↘	1	A,D	3.5	10.0	0	0	1	100%	100%	1965	6175	1710	1710	5920	5920	575	0.336	0.336	440	0.257		
	S	↓	1	A,D	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	518	0.246		398	0.189		
	S	↓	1	A,D	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	518	0.246		398	0.189		
Pedestrian crossing		↑ ↓	4P	B																			Min. Green time = 8GM + 11FG = 19s	
		← →	5P	D																				Min. Green time = 5GM + 10FG = 15s
		← →	6P	C																				Min. Green time = 5GM + 8FG = 13s

AB,C,D AD,B,C AB,C,D AD,B,C


Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak		AM Peak Check Phase		PM Peak Check Phase	
		1275(1150)	1035(795)	575(440)	Ey 0.505	0.528	Ey 0.430
				L (sec) 32	33	L (sec) 32	33
				C (sec) 114	114	C (sec) 100	100
				y pract. 0.647	0.639	y pract. 0.612	0.603
				R.C. (%) 28%	21%	R.C. (%) 42%	49%

Stage / Phase Diagrams							
I/G = 2	I/G = 8 + Ped 19	I/G = 3 I/G = 5	I/G = 5 I/G = 12 + Ped 15				

Junction: (J12) Tsing Yi Heung Sze Wui Road / Chung Mei Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Chung Mei Road	E	↗	5	B,C	3.3	10.0	0	0	1	100%	100%	1945	1945	1690	1690	1690	1690	225	0.133		250	0.148	
	E	↘	6	C	3.3	0.0	18	0	0	100%	100%	2085	2085	1925	1925	1925	1925	275	0.143	0.143	210	0.109	0.109
Tsing Yi Heung Sze Wui Road	N	↖	2	A,C	3.3	25.0	0	0	1	100%	100%	1945	1945	1835	1835	1835	1835	240	0.131		285	0.155	
	N	↑	3	A	3.5	0.0	0	0	0	0%	0%	2105	4210	2105	2105	4210	4210	513	0.243	0.243	443	0.210	0.210
	N	↑	3	A	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	513	0.243		443	0.210	
Tsing Yi Heung Sze Wui Road	S	↘	1	A,B	3.5	0.0	0	3	1	0%	0%	1839	3818	1839	1839	3818	3818	573	0.312		455	0.248	
	S	↙	1	A,B	3.5	0.0	0	3	0	0%	0%	1979	0	1979	1979	0	0	617	0.312		490	0.248	
	S	↖	4	B	3.5	0.0	22	3	0	100%	100%	1979	1979	1855	1855	1855	1855	285	0.154	0.154	240	0.129	0.129

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	AM Peak Check Phase	PM Peak Check Phase
	225(250) 275(210)		285(240) 1190(945) Ey 0.540 L (sec) 15 C (sec) 114 y pract. 0.782 R.C. (%) 45%	Ey 0.449 L (sec) 15 C (sec) 100 y pract. 0.765 R.C. (%) 70%



Junction: (J1) Cheung Tsing Highway / Tsing Yi Road West  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside O/I	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak				
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y	
Tsing Yi Road West	S	↓	2	A	3.5	0	0	0	1	0%		1965	6135	1965	5900	148	0.075	0.075				
	S	↙	2	A	3.3	0	20	0	0	46%		2085	0	2015	0	152	0.075					
	S	↘	2	A	3.3	0	17.5	0	0	100%		2085	0	1920	0	145	0.075					
Cheung Tsing Highway	E	↗	3	A,B	3.4	20	0	0	1	100%		1955	1955	1820	1820	300	0.165					
	E	↘	4	B	3.5	0	30	0	0	100%		2105	4070	2005	3860	244	0.122					
	E	↙	4	B	3.5	0	25	0	1	100%		1965	0	1855	0	226	0.122	0.122				
Tsing Yi Road West	N	↙	1	C	3.6	20	0	6.5	1	100%		1702	3544	1585	3425	455	0.287	0.287				
	N	↘	1	C	3.6	0	0	6.5	0	0%		1842	0	1840	0	310	0.168					
Pedestrian crossing		↕	5P	C	Min. Green time = 5GM + 10FG = 15s																	
		↕	6P	C	Min. Green time = 5GM + 6FG = 11s																	
		↕	7P	A,B	Min. Green time = 5GM + 9FG = 14s																	
		↕	8P	B	Min. Green time = 5GM + 10FG = 15s																	

A,B,C AB,C

Notes:	Traffic Flow (pcu / hr)		Logistic Peak Check Phase	
			Ey 0.484 0.452 L (sec) 13 9 C (sec) 100 100 y pract. 0.783 0.819 R.C. (%) <b>62%</b> <b>81%</b>	

Stage / Phase Diagrams		
I/G = 5	I/G = 5	I/G = 6

Junction: (J2) Tsing Hung Road / Tsing Yi Road																				
Description: 2024 Observed Traffic Flow																				
Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
						Left	Right		Logistic Peak				Logistic Peak		Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Tsing Yi Road	S	↓	1	A	3.5	0.0	0	1	0%		1965	4070	1965		4070	321	0.163			
	S	↓	1	A	3.5	0.0	0	0	0%		2105	0	2105		0	344	0.163			
	S	←	1	A	3.6	0.0	18	0	100%		2115	2115	1950		1950	305	0.156	0.163		
Tsing Yi Road	N	↑	4	C	4.0	30.0	0	1	100%		2015	2015	1920		1920	55	0.029			
	N	↑	4	C	3.5	0.0	0	0	0%		2105	4210	2105		4210	333	0.158			
	N	↑	4	C	3.5	0.0	0	0	0%		2105	0	2105		0	333	0.158	0.158		
Tsing Hung Road	E	→	2	A,B	3.3	25.0	0	1	100%		1945	1945	1835		1835	300	0.163			
	E	→	3	B	4.0	0.0	22	0	100%		2155	2155	2015		2015	45	0.022			
Pedestrian Crossing		↔	5P	D																
		↔	6P	A,B,D																
		↔	7P	C,D																
		↔	8P	C,D																
											A,B,C,D		A,B,C,D							
Notes:											Traffic Flow (pcu / hr) Weekday AM Peak					Logistic Peak Check Phase				
																Ey 0.321 0.321 L (sec) 33 22 C (sec) 100 100 y pract. 0.603 0.702 R.C. (%) <b>88%</b> <b>118%</b>				
Stage / Phase Diagrams																				
I/G = 2				I/G = 6 + Min. G 5				I/G = 5				I/G = 5 + 12								

Junction: (J4) Sai Tso Wan Road / Tsing Yi Road West / Tsing Yi Road  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Logistic Peak			
					Left	Right	Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Tsing Yi Road	NE	↖	1	A	4.5	15	0	6.5	1	100%		1792	1792	1630	260	0.160	0.160			
	NE	↗	1	A	3.4	0	0	6.5	0	0%		1822	1822	1820	250	0.137				
Sai Tso Wan Road	NW	↖	3	C,D	3.8	15	0	0	1	100%		1995	1995	1815	560	0.309				
	NW	↗	4	D	3.8	0	25	0	0	100%		2135	2135	2015	305	0.151	0.151			
Tsing Yi Road West	SE	↘	2	B,C	3.4	0	0	0	1	0%		1955	1955	1955	205	0.105				
	SE	↙	2	B,C	3.7	0	25	0	0	100%		2125	2125	2005	480	0.239	0.239			
Pedestrian crossing		↑ ↓ ↔	5p 6p 7p 8p	A,B D B,C A,D	Min. Green time = 5GM + 8FG = 13s Min. Green time = 5GM + 10FG = 15s Min. Green time = 5GM + 9FG = 14s Min. Green time = 5GM + 7FG = 12s															

Notes:	<p>Traffic Flow (pcu / hr)</p>	<p>Logistic Peak Check Phase</p> <p>ey 0.550                  L (sec) 19                  C (sec) 110                  y pract. 0.745                  R.C. (%) 35%</p>
--------	--------------------------------	---

Stage / Phase Diagrams			
<p><b>A</b></p>	<p><b>B</b></p>	<p><b>C</b></p>	<p><b>D</b></p>
I/G = 5	I/G = 5	I/G = 2	I/G = 5
I/G = 5	I/G = 8+12	I/G = 2	




Junction: (J5) Sai Tso Wan Road Near VEC

Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak		
						Left	Right		Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value
Sai Tso Wan Road	EB	→	3	A	4.0	0.0	0	1	0%		2015	2015	2015		2015		740	0.367	0.367
Sai Tso Wan Road	WB	←	1	A,B	4.0	0.0	0	1	0%		2015	2015	2015		2015		550	0.273	
Sai Tso Wan Road	WB	↖	2	B,C	4.0	0.0	10	0	100%		2155	2155	1875		1875		125	0.067	0.067

Pedestrian Crossing 4P C Min. green time = 6Gm + 5 FGm = 11s

Notes: (None)	Traffic Flow (pcu / hr)	AM (PM) Peak		Logistic Peak Check Phase		
		740	→	εy	0.434	0.273
			↖	L (sec)	11	18
			←	C (sec)	91	91
				y pract.	0.791	0.722
				R.C. (%)	82%	165%




I/G = 6	I/G = 7		
I/G = 3	I/G = 7	I/G = 5 + P11s	

Junction: **(J8) Tsing Yi Road West / Ching Hong Road**  
 Description: **2024 Observed Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside O/I	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
					Left	Right	Left	Right			Left	Right			Logistic Peak	Peak	Logistic Peak	Peak	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Tsing Yi Road West	S	↓	1	A	3.0	0.0	0	5.5	0	0	0%		1824	3698	1824	3698	148	0.081	0.118			
	S	↓	1	A	3.5	0.0	0	5.5	0	0	0%		1874	0	1874	0	152	0.081				
	S	↘	1	A	3.7	10.0	0	5.5	1	100%			1754	1754	1525	1525	180	0.118				
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%			1965	4070	1965	4070	191	0.097				
	N	↑	2	A,B	3.5	0.0	0	0	0	0%			2105	0	2105	0	204	0.097				
	N	↗	3	B	3.3	0.0	18	0	0	100%			2085	2085	1925	1925	300	0.156	0.156			
Ching Hong Road	W	←	4	C	3.4	18.0	20	0	0	19% / 81%			2095	0	1945	0	246	0.126	0.126			
	W	↙	4	C	3.4	15.0	0	0	1	100%			1955	4050	1775	3720	224	0.126				
Pedestrian crossing		↑	5P	A,B	Min. Green time = 11s (G) + 8s (FS) = 19s																	
		↓	6P	C	Min. Green time = 5s (G) + 12s (FS) = 17s																	
Pedestrian Crossing																						

Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 	Logistic Peak Check Phase Eye 0.400 L (sec) 12 C (sec) 71 y pract. 0.748 R.C. (%) <b>87%</b>
--------	---	---



Junction: **J9 - Tsing Yi Road West / Liu To Road**  
 Description: **2024 Observed Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		uphill Gradient (%)	Nearside O/I	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak		
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value
Tsing Yi Road West	S	↓	2	A,B	3.3	0.0	0	5	1	0%		1735	3610	1735	3610	197	0.114			
	S	↓	2	A,B	3.3	0.0	0	5	0	0%		1875	0	1875	0	213	0.114			
	S	↙	3	B	3.3	0.0	22	5	0	100%		1875	1875	1755	1755	340	0.194	0.194		
Tsing Yi Road West	N	↑	1	A	3.2	10.0	0	0	1	48%		1935	4100	1805	3970	271	0.150	0.150		
	N	↑	1	A	4.1	0.0	0	0	0	0%		2165	0	2165	0	324	0.150			
Liu To Road	E	↘	5	B,C	3.2	10.0	0	0	1	100%		1935	1935	1685	1685	305	0.181			
	E	↘	4	C	4.1	0.0	18	0	0	100%		2165	2165	2000	2000	65	0.033	0.033		
Pedestrian crossing		↑ ↓ ← →	6P 7P 8P	A,D C,D D																
Pedestrian Crossing																				

A,B,C,D A,B,C,D


Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	Logistic Peak Check Phase
	305 65		Day 0.331 0.376 L (sec) 34 38 C (sec) 130 130 y pract. 0.665 0.637 R.C. (%) <b>101%</b> <b>69%</b>

Stage / Phase Diagrams			
<p>L/G = 5</p>	<p>L/G = 7</p>	<p>L/G = 5</p>	<p>L/G = 11 + Ped 13</p>

Junction: **J10 - Tsing Yi Road West / Fung Shue Wo Road**  
 Description: **2024 Observed Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside O/I	Pro. Turning (%)		Site Factor	Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
					Left	Right	Logistic Peak				Logistic Peak					Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Fung Shue Wo Road	S	↓	1	A,D	4.1	0.0	0	3	0	0%			1	2039	4058	2039	4058	314	0.154	0.172			
(To Tsing Yi Road West)	S	↓	1	A,D	3.9	0.0	0	3	0	0%			1	2019	0	2019	0	311	0.154				
Fung Shue Wo Road	S	↓	1	A,D	4.0	0.0	0	3	1	0%			1	1889	2294.8	1889	2294.8	325	0.172				
(To Fung Shue Wo Road)	S	↓	1	A,D	4.0	0.0	0	3	0	0%			0.2	405.8	0	405.8	0	70	0.172				
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%			1	1965	2491.3	1965	2491.25	481	0.245				
	N	↑	2	A,B	3.5	0.0	0	0	0	0%			0.25	526.25	0	526.25	0	129	0.245				
	N	↗	3	B	3.6	0.0	18	0	0	100%			1	2115	2115	1950	1950	155	0.079	0.079			
Fung Shue Wo Road	N	↖	4	C	3.8	35.0	0	3	1	100%			1	1869	2193.6	1790	2100	107	0.060				
	N	↖	4	C	4.0	38.0	0	3	0	100%			0.16	324.64	0	310	0	18	0.060				
Fung Shue Wo Road	N	↗	4	C	3.6	0.0	43	3	0	100%			0.23	457.47	2446.5	440	2355	78	0.176	0.176			
	N	↗	4	C	3.6	0.0	40	3	0	100%			1	1989	0	1915	0	337	0.176				
Pedestrian crossing		←---→	5p	D																			
		←---→	6P	B,C																			
		↑	7P	A,C,D																			
		↓	8P	A,B,D																			

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	Logistic Peak Check Phase
			Ey 0.428 L (sec) 12 C (sec) 90 y pract. 0.780 R.C. (%) <b>82%</b>



Junction: (J11) Tsing Yi Heung Sze Wui Road / Cheung Wan Street  
 Description: 2024 Observed Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak		
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value
Tsing Yi Heung Sze Wui Road	N	↑	2	A,B	3.5	0.0	0	0	1	0%		1965	4070	1965	4070	478	0.243			
	N	↑	2	A,B	3.5	0.0	0	0	0	0%		2105	0	2105	0	512	0.243			
Cheung Wan Street	W	↙	3	C	3.5	18.0	20	0	0	47% / 53%		2105	0	1950	0	332	0.170	0.170		
	W	↘	3	C	3.5	15.0	0	0	1	100%		1965	4070	1785	3735	303	0.170			
Tsing Yi Heung Sze Wui Road	S	↘	1	A,D	3.0	10.0	0	0	1	100%		1915	6025	1665	5775	480	0.288	0.288		
	S	↓	1	A,D	3.0	0.0	0	0	0	0%		2055	0	2055	0	333	0.162			
	S	↓	1	A,D	3.0	0.0	0	0	0	0%		2055	0	2055	0	333	0.162			
Pedestrian crossing		↑ ↓	4P	B						Min. Green time = 8GM + 11FG = 19s										
		← →	5P	D						Min. Green time = 5GM + 10FG = 15s										
		← →	6P	C						Min. Green time = 5GM + 8FG = 13s										

AB,C,D AD,B,C


Notes:	Traffic Flow (pcu / hr)    Weekday AM Peak 665    480 ↓    ↘ ↑    ↙ 990	Logistic Peak Check Phase Ey    0.413    0.458 L (sec)    32    33 C (sec)    114    114 y pract.    0.647    0.639 R.C. (%)    57%    40%
--------	---	---

Stage / Phase Diagrams							
I/G = 2	I/G = 5	I/G = 12 + Ped 15					

Junction: (J12) Tsing Yi Heung Sze Wui Road / Chung Mei Road  
 Description: 2024 Observed Traffic Flow


Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Chung Mei Road	E	↗	5	B,C	3.3	10.0	0	0	1	100%		1945	1945	1690		1690	245	0.145			
	E	↘	6	C	3.3	0.0	18	0	0	100%		2085	2085	1925		1925	220	0.114	0.114		
Tsing Yi Heung Sze Wui Road	N	↖	2	A,C	3.3	25.0	0	0	1	100%		1945	1945	1835		1835	235	0.128			
	N	↑	3	A	3.5	0.0	0	0	0	0%		2105	4210	2105		4210	365	0.173	0.173		
	N	↑	3	A	3.5	0.0	0	0	0	0%		2105	0	2105		0	365	0.173			
Tsing Yi Heung Sze Wui Road	S	↘	1	A,B	3.5	0.0	0	3	1	0%		1839	3818	1839		3818	405	0.220			
	S	↙	1	A,B	3.5	0.0	0	3	0	0%		1979	0	1979		0	435	0.220			
	S	↖	4	B	3.5	0.0	22	3	0	100%		1979	1979	1855		1855	280	0.151	0.151		
Pedestrian crossing																					

Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 245 ↗ 220 ↘ 280 ↖ 840.00 ↓ 235 ↖ 730 ↑	Logistic Peak Check Phase g <sub>y</sub> 0.439 L (sec) 15 C (sec) 114 y <sub>pract.</sub> 0.782 R.C. (%) <b>78%</b>
--------	--	--



# Priority Junction Calculation

Junction : ( J3 ) Tsing Yi Road / Tsing Sheung Road Job No.: 24001HK  
 Scenario : 2024 Observed Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

- Y = 1 - 0.0345W
- q-AB, etc = the design flow of movement AB, etc
- W = major road width
- W-CR = central reserve width
- w-BA, etc = lane width to vehicle
- v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc
- v-IBA = visibility to the left for waiting vehicles in stream BA, etc

Geometry :	Input	Calculated
W	14	V-rBA <span style="margin-left: 100px;">30</span>
W-CR	0	V-IBA <span style="margin-left: 100px;">50</span>
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	V-rBC <span style="margin-left: 100px;">50</span>
Minor Road Share LT&RT? (Yes: 1, No: 0)	0	V-rCB <span style="margin-left: 100px;">50</span>
		D <span style="margin-left: 100px;">0.933</span>
		E <span style="margin-left: 100px;">1.012</span>
		F <span style="margin-left: 100px;">0.616</span>
		Y <span style="margin-left: 100px;">0.517</span>

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM
	pcu/hr				pcu/hr			
	q-CA	415	530	360	Q-BA	409	399	435
	q-CB	115	85	100	Q-BC	644	638	662
	q-AB	225	230	210	Q-CB	376	372	388
	q-AC	490	515	400	Q-CA	N/A	N/A	N/A
	q-BA	205	165	180	Q-BAC	N/A	N/A	N/A
	q-BC	140	135	130				
	f	0.406	0.450	0.419				

(If C-B blocked C-  
(If Minor Road Share LT&RT)


Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
	B-A	0.50	0.41	0.41
	B-C	0.22	0.21	0.20
	C-B	0.31	0.23	0.26
	C-A	N/A	N/A	N/A
	B-AC	N/A	N/A	N/A

**Critical DFC** **0.50** **0.41** **0.41**

# Priority Junction Calculation

Junction : ( J6 ) Sai Tso Wan Road / Tsing Tim Street Job No.: 24001HK

Scenario : 2024 Observed Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

- Y = 1 - 0.0345W
- q-AB, etc = the design flow of movement AB, etc
- W = major road width
- W-CR = central reserve width
- w-BA, etc = lane width to vehicle
- v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc
- v-IBA = visibility to the left for waiting vehicles in stream BA, etc

Geometry :	Input			Calculated			
W	7	V-rBA	50	w-BA	3.6	D	0.877
W-CR	0	V-IBA	50	w-BC	3.6	E	0.933
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	V-rBC	50	w-CB	0	F	0.616
Minor Road Share LT&RT? (Yes: 1, No: 0)	1	V-rCB	50			Y	0.759

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM	
	pcu/hr				pcu/hr				
	q-CA	360	360	275	Q-BA	376	387	446	
	q-CB	35	30	10	Q-BC	581	591	633	
	q-AB	120	100	65	Q-CB	371	380	411	
	q-AC	395	365	215	Q-CA	N/A	N/A	N/A	(If C-B blocked C- (If Minor Road Share LT&RT)
	q-BA	110	90	90	Q-BAC	406	412	453	
	q-BC	30	20	5					
	f	0.214	0.182	0.053					


Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
	B-A	N/A	N/A	N/A
	B-C	N/A	N/A	N/A
	C-B	0.09	0.08	0.02
	C-A	N/A	N/A	N/A
	B-AC	0.34	0.27	0.21

**Critical DFC** **0.34    0.27    0.21**



# Priority Junction Calculation

Junction : ( J13 ) Tsing Yi Road / Tsing Keung Street Job No.: 24001HK  
 Scenario : 2024 Observed Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

- Y = 1 - 0.0345W
- q-AB, etc = the design flow of movement AB, etc
- W = major road width
- W-CR = central reserve width
- w-BA, etc = lane width to vehicle
- v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc
- v-IBA = visibility to the left for waiting vehicles in stream BA, etc

Geometry :	Input			Calculated			
W	15	V-rBA	50	w-BA	4	D	0.910
W-CR	0	V-IBA	50	w-BC	4	E	0.968
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	V-rBC	50	w-CB	4.7	F	1.029
Minor Road Share LT&RT? (Yes: 1, No: 0)	0	V-rCB	50			Y	0.483

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM	
	pcu/hr				pcu/hr				
q-CA	365	400	315		Q-BA	450	442	469	
q-CB	60	85	25		Q-BC	646	648	652	
q-AB	125	125	60		Q-CB	674	676	687	
q-AC	390	380	380		Q-CA	N/A	N/A	N/A	(If C-B blocked C-
q-BA	65	110	60		Q-BAC	N/A	N/A	N/A	(If Minor Road Share LT&RT)
q-BC	110	95	60						
f	0.629	0.463	0.500						

Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
	B-A	0.14	0.25	0.13
	B-C	0.17	0.15	0.09
	C-B	0.09	0.13	0.04
	C-A	N/A	N/A	N/A
	B-AC	N/A	N/A	N/A

**Critical DFC** **0.17    0.25    0.13**

# Roundabout Junction Calculation

Junction : (RA1) Tsing Yi Interchange (North) Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

**Arm 4 Tsing Yi Heung Sze Wui Road**

0	420	0
<0>	<315>	<0>
(0)	(320)	(0)

**Arm 1 Tsing Yi Bridge**

420	<315>	(320)

**Arm 3**

1225	<995>	(600)

**Arm 2 Tsing Yi Interchange Access Road**

1590	<1325>	(835)

365	1225	0
<330>	<995>	<0>
(235)	(600)	(0)

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

**Input Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4
V	=	Approach half width (m)	6		6
E	=	Entry width (m)	7		7
L	=	Effective length of flare (m)	5		5
R	=	Entry radius	62		41
D	=	Inscribed circle diameter (m)	60		60
A	=	Entry angle (degree)	27		60
Q	=	Entry flow (pcu/hr)	AM	1590	420
			Logistic	1325	315
			PM	835	320
Qc	=	Circulating flow across entry (pcu/hr)	AM	0	1225
			Logistic	0	995
			PM	0	600

**Output Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4
S	=	Sharpness of flare = $1.6*(E-V)/L$	0.32		0.32
K	=	$1-0.00347*(A-30)-0.978*(1/R-0.05)$	1.04		0.92
X2	=	$V+((E-V)/(1+2*S))$	6.61		6.61
M	=	$Exp((D-60)/10)$	1.00		1.00
F	=	$303*X2$	2003		2003
Td	=	$1+(0.5/(1+M))$	1.25		1.25
Fc	=	$0.21*Td*(1+0.2*X2)$	0.61		0.61
Qe	=	Capacity = $K*(F-Fc*Qc)$	AM	2090	1157
			Logistic	2090	1286
			PM	2090	1508
DFC	=	Entry Flow/Capacity = $Q/Qe$	AM	0.76	0.36
			Logistic	0.63	0.24
			PM	0.40	0.21

**DFC of Critical Approach**

	=	AM	0.76
		Logistic	0.63
		PM	0.40

**CTA Consultants Ltd.**

# Roundabout Junction Calculation

Junction : (RA1) Tsing Yi Interchange (South) Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

645	<515>	(420)
-----	-------	-------

0	610	0
<0>	<635>	<0>
(0)	(685)	(0)

640	<655>	(720)
-----	-------	-------

0	<0>	(0)
245	<265>	(375)
505	<430>	(270)

1385	<1125>	(1350)
------	--------	--------

910	230	0
<665>	<195>	<0>
(875)	(100)	(0)

245	<265>	(1060)
-----	-------	--------

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	= Approach half width (m)	7	6.8	7	6
E	= Entry width (m)	7.2	7	7.3	6.3
L	= Effective length of flare (m)	5	5	5	5
R	= Entry radius	23	25	24	44
D	= Inscribed circle diameter (m)	60	60	60	60
A	= Entry angle (degree)	43	54	27	23
Q	= Entry flow (pcu/hr)	750	1140	415	610
		AM			
		Logistic			
		PM			
Qc	= Circulating flow across entry (pcu/hr)	640	245	1385	645
		AM			
		Logistic			
		PM			

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	= Sharpness of flare = 1.6*(E-V)/L	0.06	0.06	0.10	0.10
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	0.96	0.93	1.02	1.05
X2	= V+((E-V)/(1+2*S))	7.18	6.98	7.25	6.25
M	= Exp((D-60)/10)	1.00	1.00	1.00	1.00
F	= 303*X2	2175	2114	2197	1894
Td	= 1+(0.5/(1+M))	1.25	1.25	1.25	1.25
Fc	= 0.21*Td*(1+0.2*X2)	0.64	0.63	0.64	0.59
Qe	= Capacity = K*(F-Fc*Qc)	1697	1816	1331	1590
		AM			
		Logistic			
		PM			
DFC	= Entry Flow/Capacity = Q/Qe	0.44	0.63	0.31	0.38
		AM			
		Logistic			
		PM			

DFC of Critical Approach	=				
		AM	0.63		
		Logistic	0.48		
		PM	0.73		

# Roundabout Junction Calculation

Junction :		(RA2) Tsing Yi Road / Tsing Yi Hong Wan Road / Tsing Sha Hig Job No.: 24001HK																	
Scenario :		2029 Design Traffic Flow																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 4 Tsing Yi Road SB</b></td> </tr> <tr> <td style="text-align: center;">0</td> <td style="text-align: center;">160</td> <td style="text-align: center;">655</td> <td style="text-align: center;">0</td> </tr> <tr> <td style="text-align: center;">&lt;0&gt;</td> <td style="text-align: center;">&lt;125&gt;</td> <td style="text-align: center;">&lt;550&gt;</td> <td style="text-align: center;">&lt;0&gt;</td> </tr> <tr> <td style="text-align: center;">(5)</td> <td style="text-align: center;">(90)</td> <td style="text-align: center;">(415)</td> <td style="text-align: center;">(0)</td> </tr> </table>						<b>Arm 4 Tsing Yi Road SB</b>		0	160	655	0	<0>	<125>	<550>	<0>	(5)	(90)	(415)	(0)
<b>Arm 4 Tsing Yi Road SB</b>																			
0	160	655	0																
<0>	<125>	<550>	<0>																
(5)	(90)	(415)	(0)																
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">875</td> <td style="text-align: center;">&lt;870&gt;</td> <td style="text-align: center;">(815)</td> </tr> </table>						875	<870>	(815)											
875	<870>	(815)																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">70</td> <td style="text-align: center;">&lt;60&gt;</td> <td style="text-align: center;">(85)</td> </tr> <tr> <td style="text-align: center;">385</td> <td style="text-align: center;">&lt;375&gt;</td> <td style="text-align: center;">(295)</td> </tr> <tr> <td style="text-align: center;">225</td> <td style="text-align: center;">&lt;215&gt;</td> <td style="text-align: center;">(225)</td> </tr> <tr> <td style="text-align: center;">5</td> <td style="text-align: center;">&lt;5&gt;</td> <td style="text-align: center;">(5)</td> </tr> </table>						70	<60>	(85)	385	<375>	(295)	225	<215>	(225)	5	<5>	(5)		
70	<60>	(85)																	
385	<375>	(295)																	
225	<215>	(225)																	
5	<5>	(5)																	
<b>Arm 1 Tsing Yi Hong Wan Road</b>																			
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">135</td> <td style="text-align: center;">&lt;135&gt;</td> <td style="text-align: center;">(180)</td> </tr> <tr> <td style="text-align: center;">435</td> <td style="text-align: center;">&lt;400&gt;</td> <td style="text-align: center;">(470)</td> </tr> <tr> <td style="text-align: center;">315</td> <td style="text-align: center;">&lt;310&gt;</td> <td style="text-align: center;">(330)</td> </tr> <tr> <td style="text-align: center;">65</td> <td style="text-align: center;">&lt;65&gt;</td> <td style="text-align: center;">(45)</td> </tr> </table>						135	<135>	(180)	435	<400>	(470)	315	<310>	(330)	65	<65>	(45)		
135	<135>	(180)																	
435	<400>	(470)																	
315	<310>	(330)																	
65	<65>	(45)																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 3 Tsing Sha Highway</b></td> </tr> <tr> <td style="text-align: center;">1385</td> <td style="text-align: center;">&lt;1395&gt;</td> <td style="text-align: center;">(1490)</td> </tr> </table>						<b>Arm 3 Tsing Sha Highway</b>		1385	<1395>	(1490)									
<b>Arm 3 Tsing Sha Highway</b>																			
1385	<1395>	(1490)																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">280</td> <td style="text-align: center;">690</td> <td style="text-align: center;">85</td> <td style="text-align: center;">40</td> </tr> <tr> <td style="text-align: center;">&lt;275&gt;</td> <td style="text-align: center;">&lt;720&gt;</td> <td style="text-align: center;">&lt;85&gt;</td> <td style="text-align: center;">&lt;55&gt;</td> </tr> <tr> <td style="text-align: center;">(245)</td> <td style="text-align: center;">(725)</td> <td style="text-align: center;">(65)</td> <td style="text-align: center;">(45)</td> </tr> </table>						280	690	85	40	<275>	<720>	<85>	<55>	(245)	(725)	(65)	(45)		
280	690	85	40																
<275>	<720>	<85>	<55>																
(245)	(725)	(65)	(45)																
<b>Arm 2 Tsing Yi Road NB</b>																			
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">1050</td> <td style="text-align: center;">&lt;975&gt;</td> <td style="text-align: center;">(1495)</td> </tr> </table>						1050	<975>	(1495)											
1050	<975>	(1495)																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">AM</td> <td style="text-align: center;">[Logistic]</td> <td style="text-align: center;">(PM)</td> </tr> <tr> <td style="text-align: center;">[Logistic]</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">(PM)</td> <td></td> <td></td> </tr> </table>						AM	[Logistic]	(PM)	[Logistic]			(PM)							
AM	[Logistic]	(PM)																	
[Logistic]																			
(PM)																			
<b>Input Parameters</b>		Arm 1	Arm 2	Arm 3	Arm 4														
V	= Approach half width (m)	7.3	7.1	7.3	7.3														
E	= Entry width (m)	13.5	12	9.5	10														
L	= Effective length of flare (m)	30	15	30	15														
R	= Entry radius	45	97	52	34														
D	= Inscribed circle diameter (m)	100	100	100	100														
A	= Entry angle (degree)	29	32	31	46														
Q	= Entry flow (pcu/hr)	AM 950 Logistic 910 PM 1025	1095 1135 1080	685 655 610	815 675 510														
Qc	= Circulating flow across entry (pcu/hr)	AM 1085 Logistic 950 PM 785	1050 975 1495	1385 1395 1490	875 870 815														
<b>Output Parameters</b>		Arm 1	Arm 2	Arm 3	Arm 4														
S	= Sharpness of flare = 1.6*(E-V)/L	0.33	0.52	0.12	0.29														
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	1.03	1.03	1.03	0.96														
X2	= V+((E-V)/(1+2*S))	11.03	9.50	9.08	9.01														
M	= Exp((D-60)/10)	54.60	54.60	54.60	54.60														
F	= 303*X2	3343	2877	2752	2731														
Td	= 1+(0.5/(1+M))	1.01	1.01	1.01	1.01														
Fc	= 0.21*Td*(1+0.2*X2)	0.68	0.61	0.60	0.59														
Qe	= Capacity = K*(F-Fc*Qc)	AM 2685 Logistic 2780 PM 2895	2303 2351 2021	1977 1970 1912	2133 2136 2168														
DFC	= Entry Flow/Capacity = Q/Qe	AM 0.35 Logistic 0.33 PM 0.35	0.48 0.48 0.53	0.35 0.33 0.32	0.38 0.32 0.24														
<b>DFC of Critical Approach</b>	=	AM 0.48 Logistic 0.48 PM 0.53																	

# Roundabout Junction Calculation

Junction : (RA3) Tsing Yi Hong Wan Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow (With Planned New Road)

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	= Approach half width (m)		7	7.3	7.3
E	= Entry width (m)		14	10	12
L	= Effective length of flare (m)		20	5	2
R	= Entry radius		65	40	75
D	= Inscribed circle diameter (m)		68	68	68
A	= Entry angle (degree)		53	46	46
Q	= Entry flow (pcu/hr)		750	1090	1090
		AM	750	1090	1090
		Logistic	780	900	900
		PM	975	940	940
Qc	= Circulating flow across entry (pcu/hr)		195	0	80
		AM	195	0	80
		Logistic	170	80	80
		PM	945	80	95

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	= Sharpness of flare = $1.6*(E-V)/L$		0.56	0.86	3.76
K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$		0.95	0.97	0.98
X2	= $V+((E-V)/(1+2*S))$		10.30	8.29	7.85
M	= $Exp((D-60)/10)$		2.23	2.23	2.23
F	= $303*X2$		3121	2512	2379
Td	= $1+(0.5/(1+M))$		1.16	1.16	1.16
Fc	= $0.21*Td*(1+0.2*X2)$		0.74	0.64	0.62
Qe	= Capacity = $K*(F-Fc*Qc)$		2840	2434	2283
		AM	2840	2434	2283
		Logistic	2858	2384	2283
		PM	2309	2384	2274
DFC	= Entry Flow/Capacity = $Q/Qe$		0.26	0.45	0.48
		AM	0.26	0.45	0.48
		Logistic	0.27	0.38	0.39
		PM	0.42	0.39	0.41

DFC of Critical Approach	=	AM	0.48
		Logistic	0.39
		PM	0.42


# Roundabout Junction Calculation

Junction : <u>(RA4) Tsing Yi Hong Wan Road / Tsing Ko Road</u>		Job No.: <u>24001HK</u>																																																													
Scenario : <u>2029 Design Traffic Flow</u>																																																															
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 4 Tsing Yi Hong Wan Road SB</b></td> <td></td> <td></td> </tr> <tr> <td>475</td> <td></td> <td>255</td> <td>190</td> </tr> <tr> <td>&lt;385&gt;</td> <td></td> <td>&lt;240&gt;</td> <td>&lt;165&gt;</td> </tr> <tr> <td>(365)</td> <td></td> <td>(210)</td> <td>(265)</td> </tr> <tr> <td colspan="2" style="text-align: center;"><b>Arm 1 Tsing Yi Hong Wan Road</b></td> <td></td> <td></td> </tr> <tr> <td>745</td> <td>&lt;1160&gt;</td> <td colspan="2">(1125)</td> </tr> <tr> <td colspan="2" style="text-align: center;"><b>Arm 3 Tsing Ko Road</b></td> <td></td> <td></td> </tr> <tr> <td>330</td> <td>&lt;165&gt;</td> <td colspan="2">(265)</td> </tr> <tr> <td>10</td> <td>&lt;5&gt;</td> <td colspan="2">(20)</td> </tr> <tr> <td>5</td> <td>&lt;385&gt;</td> <td colspan="2">(365)</td> </tr> <tr> <td colspan="2" style="text-align: center;"><b>Arm 2 Tsing Yi Hong Wan Road NB</b></td> <td></td> <td></td> </tr> <tr> <td>590</td> <td>&lt;675&gt;</td> <td colspan="2">(695)</td> </tr> <tr> <td>25</td> <td>115</td> <td></td> <td>0</td> </tr> <tr> <td>&lt;25&gt;</td> <td>&lt;145&gt;</td> <td></td> <td>&lt;145&gt;</td> </tr> <tr> <td>(20)</td> <td>(165)</td> <td></td> <td>(165)</td> </tr> </table>				<b>Arm 4 Tsing Yi Hong Wan Road SB</b>				475		255	190	<385>		<240>	<165>	(365)		(210)	(265)	<b>Arm 1 Tsing Yi Hong Wan Road</b>				745	<1160>	(1125)		<b>Arm 3 Tsing Ko Road</b>				330	<165>	(265)		10	<5>	(20)		5	<385>	(365)		<b>Arm 2 Tsing Yi Hong Wan Road NB</b>				590	<675>	(695)		25	115		0	<25>	<145>		<145>	(20)	(165)		(165)
<b>Arm 4 Tsing Yi Hong Wan Road SB</b>																																																															
475		255	190																																																												
<385>		<240>	<165>																																																												
(365)		(210)	(265)																																																												
<b>Arm 1 Tsing Yi Hong Wan Road</b>																																																															
745	<1160>	(1125)																																																													
<b>Arm 3 Tsing Ko Road</b>																																																															
330	<165>	(265)																																																													
10	<5>	(20)																																																													
5	<385>	(365)																																																													
<b>Arm 2 Tsing Yi Hong Wan Road NB</b>																																																															
590	<675>	(695)																																																													
25	115		0																																																												
<25>	<145>		<145>																																																												
(20)	(165)		(165)																																																												
		AM	[Logistic]	(PM)																																																											
		[Logistic]																																																													
		(PM)																																																													
<b>Input Parameters</b>																																																															
		Arm 1	Arm 2	Arm 3	Arm 4																																																										
V	=	Approach half width (m)	6.7	6.3	7.3																																																										
E	=	Entry width (m)	13.5	12.5	15																																																										
L	=	Effective length of flare (m)	18	30	30																																																										
R	=	Entry radius	47	100	75																																																										
D	=	Inscribed circle diameter (m)	68	68	68																																																										
A	=	Entry angle (degree)	41	22	46																																																										
Q	=	Entry flow (pcu/hr)																																																													
		AM	140	345	920																																																										
		Logistic	315	555	790																																																										
		PM	350	650	840																																																										
Qc	=	Circulating flow across entry (pcu/hr)																																																													
		AM	480	590	15																																																										
		Logistic	770	675	535																																																										
		PM	940	695	550																																																										
<b>Output Parameters</b>																																																															
		Arm 1	Arm 2	Arm 3	Arm 4																																																										
S	=	Sharpness of flare = 1.6*(E-V)/L	0.60	0.33	0.41																																																										
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	0.99	1.07	0.98																																																										
X2	=	V+((E-V)/(1+2*S))	9.78	10.03	11.53																																																										
M	=	Exp((D-60)/10)	2.23	2.23	2.23																																																										
F	=	303*X2	2963	3040	3493																																																										
Td	=	1+(0.5/(1+M))	1.16	1.16	1.16																																																										
Fc	=	0.21*Td*(1+0.2*X2)	0.72	0.73	0.80																																																										
Qe	=	Capacity = K*(F-Fc*Qc)																																																													
		AM	2592	2784	3412																																																										
		Logistic	2387	2718	3004																																																										
		PM	2266	2702	2992																																																										
DFC	=	Entry Flow/Capacity = Q/Qe																																																													
		AM	0.05	0.12	0.27																																																										
		Logistic	0.13	0.20	0.26																																																										
		PM	0.15	0.24	0.28																																																										
<b>DFC of Critical Approach =</b>																																																															
		AM	0.27																																																												
		Logistic	0.26																																																												
		PM	0.28																																																												

# Roundabout Junction Calculation

Junction : (RA5) Tam Kon Shan Interchange Job No.: 24001HK

Scenario : 2029 Design Traffic Flow



Input Parameters			Arm 1	Arm 2	Arm 3	Arm 4	Arm 5
V	=	Approach half width (m)	7	7.3	5.5	7.3	7
E	=	Entry width (m)	9	13.5	7.5	13.5	11
L	=	Effective length of flare (m)	9	9	11	9	10
R	=	Entry radius	100	45	45	25	45
D	=	Inscribed circle diameter (m)	100	100	100	100	100
A	=	Entry angle (degree)	30	25	25	30	45
Q	=	Entry flow (pcu/hr)					
		AM	715	1715	405	1125	470
		Logistic	625	1755	305	1075	420
		PM	650	1925	375	1110	490
Qc	=	Circulating flow across entry (pcu/hr)					
		AM	1300	1310	2525	2355	2080
		Logistic	1195	1130	2440	2205	2015
		PM	1355	1225	2710	2505	2145

Output Parameters			Arm 1	Arm 2	Arm 3	Arm 4	Arm 5
S	=	Sharpness of flare = 1.6*(E-V)/L	0.36	1.10	0.29	1.10	0.64
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	1.04	1.04	1.04	1.01	0.98
X2	=	V+((E-V)/(1+2*S))	8.17	9.23	6.76	9.23	8.75
M	=	Exp((D-60)/10)	54.60	54.60	54.60	54.60	54.60
F	=	303*X2	2475	2798	2050	2798	2653
Td	=	1+(0.5/(1+M))	1.01	1.01	1.01	1.01	1.01
Fc	=	0.21*Td*(1+0.2*X2)	0.56	0.60	0.50	0.60	0.58
Qe	=	Capacity = K*(F-Fc*Qc)					
		AM	1818	2097	826	1391	1404
		Logistic	1879	2211	870	1482	1441
		PM	1786	2151	730	1300	1367
DFC	=	Entry Flow/Capacity = Q/Qe					
		AM	0.39	0.82	0.49	0.81	0.33
		Logistic	0.33	0.79	0.35	0.73	0.29
		PM	0.36	0.89	0.51	0.85	0.36

DFC of Critical Approach = AM 0.82  
Logistic 0.79  
PM 0.89

# Roundabout Junction Calculation

Junction : (RA6) Tsing King Road / Fung Shue Wo Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

**Arm 4 Tsing King Road**

25	5	600	100
<25>	<5>	<400>	<80>
(25)	(15)	(450)	(65)

**Arm 1 Fung Shue Wo Road WB**

0	<0>	(0)
25	<30>	(25)
80	<55>	(65)
220	<170>	(210)

**Arm 3 Fung Shue Wo Road EB**

980	<850>	(750)
-----	-------	-------

**Arm 2 Tsing Yi Heung Sze Wui Road**

395	305	115	510
<340>	<240>	<110>	<445>
(455)	(310)	(100)	(290)

Central Circulating Flow: 1200, <1020>, (950)

Signal Timing Table:

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4	
V	=	Approach half width (m)	6.7	7.3	7.3	6.9
E	=	Entry width (m)	9.7	10	9.2	8.9
L	=	Effective length of flare (m)	16	20	14	16
R	=	Entry radius	55	71	60	62
D	=	Inscribed circle diameter (m)	100	100	100	100
A	=	Entry angle (degree)	36	30	18	25
Q	=	Entry flow (pcu/hr)				
		AM	325	1325	590	730
		Logistic	255	1135	485	510
		PM	300	1155	565	555
Qc	=	Circulating flow across entry (pcu/hr)				
		AM	1670	135	980	1200
		Logistic	1315	115	850	1020
		PM	1275	580	750	950

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4	
S	=	Sharpness of flare = 1.6*(E-V)/L	0.30	0.22	0.22	0.20
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	1.01	1.04	1.07	1.05
X2	=	V+((E-V)/(1+2*S))	8.58	9.19	8.62	8.33
M	=	Exp((D-60)/10)	54.60	54.60	54.60	54.60
F	=	303*X2	2598	2783	2613	2524
Td	=	1+(0.5/(1+M))	1.01	1.01	1.01	1.01
Fc	=	0.21*Td*(1+0.2*X2)	0.58	0.60	0.58	0.56
Qe	=	Capacity = K*(F-Fc*Qc)				
		AM	1654	2797	2199	1939
		Logistic	1861	2809	2280	2046
		PM	1884	2520	2342	2087
DFC	=	Entry Flow/Capacity = Q/Qe				
		AM	0.20	0.47	0.27	0.38
		Logistic	0.14	0.40	0.21	0.25
		PM	0.16	0.46	0.24	0.27

**DFC of Critical Approach =**

AM	0.47
Logistic	0.40
PM	0.46

**CTA Consultants Ltd.**



# Roundabout Junction Calculation

Junction : <u>(RA7) Tsing Yi Hong Wan Road / Tsing Sheung Road</u>		Job No.: <u>24001HK</u>																																																																																					
Scenario : <u>2029 Design Traffic Flow</u>																																																																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 4 Tsing Sheung Road</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">75</td> <td style="text-align: center;">&lt;120&gt;</td> <td style="text-align: center;">95</td> <td style="text-align: center;">40</td> </tr> <tr> <td style="text-align: center;">(115)</td> <td style="text-align: center;">(150)</td> <td style="text-align: center;">(25)</td> <td style="text-align: center;">(25)</td> </tr> </tbody> </table>				Arm 4 Tsing Sheung Road				75	<120>	95	40	(115)	(150)	(25)	(25)																																																																								
Arm 4 Tsing Sheung Road																																																																																							
75	<120>	95	40																																																																																				
(115)	(150)	(25)	(25)																																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 1</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">175</td> <td style="text-align: center;">&lt;220&gt;</td> <td style="text-align: center;">(280)</td> <td style="text-align: center;">(280)</td> </tr> <tr> <td style="text-align: center;">75</td> <td style="text-align: center;">&lt;125&gt;</td> <td style="text-align: center;">(275)</td> <td style="text-align: center;">(275)</td> </tr> </tbody> </table>				Arm 1				175	<220>	(280)	(280)	75	<125>	(275)	(275)																																																																								
Arm 1																																																																																							
175	<220>	(280)	(280)																																																																																				
75	<125>	(275)	(275)																																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 3 Tsing Yi Hong Wan Road</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">25</td> <td style="text-align: center;">&lt;20&gt;</td> <td style="text-align: center;">(60)</td> <td style="text-align: center;">(60)</td> </tr> <tr> <td style="text-align: center;">10</td> <td style="text-align: center;">&lt;5&gt;</td> <td style="text-align: center;">(10)</td> <td style="text-align: center;">(10)</td> </tr> <tr> <td style="text-align: center;">0</td> <td style="text-align: center;">&lt;5&gt;</td> <td style="text-align: center;">(10)</td> <td style="text-align: center;">(10)</td> </tr> </tbody> </table>				Arm 3 Tsing Yi Hong Wan Road				25	<20>	(60)	(60)	10	<5>	(10)	(10)	0	<5>	(10)	(10)																																																																				
Arm 3 Tsing Yi Hong Wan Road																																																																																							
25	<20>	(60)	(60)																																																																																				
10	<5>	(10)	(10)																																																																																				
0	<5>	(10)	(10)																																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 2 Tsing Sheung Road</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">140</td> <td style="text-align: center;">&lt;150&gt;</td> <td style="text-align: center;">(170)</td> <td style="text-align: center;">(170)</td> </tr> <tr> <td style="text-align: center;">5</td> <td style="text-align: center;">&lt;5&gt;</td> <td style="text-align: center;">55</td> <td style="text-align: center;">5</td> </tr> <tr> <td style="text-align: center;">(10)</td> <td style="text-align: center;">(40)</td> <td style="text-align: center;">(40)</td> <td style="text-align: center;">(5)</td> </tr> </tbody> </table>				Arm 2 Tsing Sheung Road				140	<150>	(170)	(170)	5	<5>	55	5	(10)	(40)	(40)	(5)																																																																				
Arm 2 Tsing Sheung Road																																																																																							
140	<150>	(170)	(170)																																																																																				
5	<5>	55	5																																																																																				
(10)	(40)	(40)	(5)																																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>AM</th> <th>[Logistic]</th> <th>(PM)</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>					AM	[Logistic]	(PM)																																																																																
	AM	[Logistic]	(PM)																																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: left;">Input Parameters</th> <th>Arm 1</th> <th>Arm 2</th> <th>Arm 3</th> <th>Arm 4</th> </tr> </thead> <tbody> <tr> <td>V</td> <td>= Approach half width (m)</td> <td></td> <td style="text-align: center;">5.2</td> <td style="text-align: center;">3</td> <td style="text-align: center;">6.7</td> </tr> <tr> <td>E</td> <td>= Entry width (m)</td> <td></td> <td style="text-align: center;">9</td> <td style="text-align: center;">8.4</td> <td style="text-align: center;">12</td> </tr> <tr> <td>L</td> <td>= Effective length of flare (m)</td> <td></td> <td style="text-align: center;">25</td> <td style="text-align: center;">15</td> <td style="text-align: center;">23</td> </tr> <tr> <td>R</td> <td>= Entry radius</td> <td></td> <td style="text-align: center;">63</td> <td style="text-align: center;">55</td> <td style="text-align: center;">11.6</td> </tr> <tr> <td>D</td> <td>= Inscribed circle diameter (m)</td> <td></td> <td style="text-align: center;">53</td> <td style="text-align: center;">53</td> <td style="text-align: center;">53</td> </tr> <tr> <td>A</td> <td>= Entry angle (degree)</td> <td></td> <td style="text-align: center;">33</td> <td style="text-align: center;">48</td> <td style="text-align: center;">38</td> </tr> <tr> <td>Q</td> <td>= Entry flow (pcu/hr)</td> <td>AM</td> <td style="text-align: center;">65</td> <td style="text-align: center;">35</td> <td style="text-align: center;">210</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td style="text-align: center;">30</td> <td style="text-align: center;">30</td> <td style="text-align: center;">245</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td style="text-align: center;">55</td> <td style="text-align: center;">80</td> <td style="text-align: center;">290</td> </tr> <tr> <td>Qc</td> <td>= Circulating flow across entry (pcu/hr)</td> <td>AM</td> <td style="text-align: center;">75</td> <td style="text-align: center;">140</td> <td style="text-align: center;">70</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td style="text-align: center;">125</td> <td style="text-align: center;">150</td> <td style="text-align: center;">35</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td style="text-align: center;">275</td> <td style="text-align: center;">170</td> <td style="text-align: center;">65</td> </tr> </tbody> </table>				Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4	V	= Approach half width (m)		5.2	3	6.7	E	= Entry width (m)		9	8.4	12	L	= Effective length of flare (m)		25	15	23	R	= Entry radius		63	55	11.6	D	= Inscribed circle diameter (m)		53	53	53	A	= Entry angle (degree)		33	48	38	Q	= Entry flow (pcu/hr)	AM	65	35	210			Logistic	30	30	245			PM	55	80	290	Qc	= Circulating flow across entry (pcu/hr)	AM	75	140	70			Logistic	125	150	35			PM	275	170	65						
Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4																																																																																		
V	= Approach half width (m)		5.2	3	6.7																																																																																		
E	= Entry width (m)		9	8.4	12																																																																																		
L	= Effective length of flare (m)		25	15	23																																																																																		
R	= Entry radius		63	55	11.6																																																																																		
D	= Inscribed circle diameter (m)		53	53	53																																																																																		
A	= Entry angle (degree)		33	48	38																																																																																		
Q	= Entry flow (pcu/hr)	AM	65	35	210																																																																																		
		Logistic	30	30	245																																																																																		
		PM	55	80	290																																																																																		
Qc	= Circulating flow across entry (pcu/hr)	AM	75	140	70																																																																																		
		Logistic	125	150	35																																																																																		
		PM	275	170	65																																																																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: left;">Output Parameters</th> <th>Arm 1</th> <th>Arm 2</th> <th>Arm 3</th> <th>Arm 4</th> </tr> </thead> <tbody> <tr> <td>S</td> <td>= Sharpness of flare = 1.6*(E-V)/L</td> <td></td> <td style="text-align: center;">0.24</td> <td style="text-align: center;">0.58</td> <td style="text-align: center;">0.37</td> </tr> <tr> <td>K</td> <td>= 1-0.00347*(A-30)-0.978*(1/R-0.05)</td> <td></td> <td style="text-align: center;">1.02</td> <td style="text-align: center;">0.97</td> <td style="text-align: center;">0.94</td> </tr> <tr> <td>X2</td> <td>= V+((E-V)/(1+2*S))</td> <td></td> <td style="text-align: center;">7.76</td> <td style="text-align: center;">5.51</td> <td style="text-align: center;">9.75</td> </tr> <tr> <td>M</td> <td>= Exp((D-60)/10)</td> <td></td> <td style="text-align: center;">0.50</td> <td style="text-align: center;">0.50</td> <td style="text-align: center;">0.50</td> </tr> <tr> <td>F</td> <td>= 303*X2</td> <td></td> <td style="text-align: center;">2350</td> <td style="text-align: center;">1669</td> <td style="text-align: center;">2954</td> </tr> <tr> <td>Td</td> <td>= 1+(0.5/(1+M))</td> <td></td> <td style="text-align: center;">1.33</td> <td style="text-align: center;">1.33</td> <td style="text-align: center;">1.33</td> </tr> <tr> <td>Fc</td> <td>= 0.21*Td*(1+0.2*X2)</td> <td></td> <td style="text-align: center;">0.71</td> <td style="text-align: center;">0.59</td> <td style="text-align: center;">0.83</td> </tr> <tr> <td>Qe</td> <td>= Capacity = K*(F-Fc*Qc)</td> <td>AM</td> <td style="text-align: center;">2349</td> <td style="text-align: center;">1537</td> <td style="text-align: center;">2714</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td style="text-align: center;">2313</td> <td style="text-align: center;">1531</td> <td style="text-align: center;">2741</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td style="text-align: center;">2203</td> <td style="text-align: center;">1520</td> <td style="text-align: center;">2717</td> </tr> <tr> <td>DFC</td> <td>= Entry Flow/Capacity = Q/Qe</td> <td>AM</td> <td style="text-align: center;">0.03</td> <td style="text-align: center;">0.02</td> <td style="text-align: center;">0.08</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td style="text-align: center;">0.01</td> <td style="text-align: center;">0.02</td> <td style="text-align: center;">0.09</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td style="text-align: center;">0.02</td> <td style="text-align: center;">0.05</td> <td style="text-align: center;">0.11</td> </tr> </tbody> </table>				Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4	S	= Sharpness of flare = 1.6*(E-V)/L		0.24	0.58	0.37	K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)		1.02	0.97	0.94	X2	= V+((E-V)/(1+2*S))		7.76	5.51	9.75	M	= Exp((D-60)/10)		0.50	0.50	0.50	F	= 303*X2		2350	1669	2954	Td	= 1+(0.5/(1+M))		1.33	1.33	1.33	Fc	= 0.21*Td*(1+0.2*X2)		0.71	0.59	0.83	Qe	= Capacity = K*(F-Fc*Qc)	AM	2349	1537	2714			Logistic	2313	1531	2741			PM	2203	1520	2717	DFC	= Entry Flow/Capacity = Q/Qe	AM	0.03	0.02	0.08			Logistic	0.01	0.02	0.09			PM	0.02	0.05	0.11
Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4																																																																																		
S	= Sharpness of flare = 1.6*(E-V)/L		0.24	0.58	0.37																																																																																		
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)		1.02	0.97	0.94																																																																																		
X2	= V+((E-V)/(1+2*S))		7.76	5.51	9.75																																																																																		
M	= Exp((D-60)/10)		0.50	0.50	0.50																																																																																		
F	= 303*X2		2350	1669	2954																																																																																		
Td	= 1+(0.5/(1+M))		1.33	1.33	1.33																																																																																		
Fc	= 0.21*Td*(1+0.2*X2)		0.71	0.59	0.83																																																																																		
Qe	= Capacity = K*(F-Fc*Qc)	AM	2349	1537	2714																																																																																		
		Logistic	2313	1531	2741																																																																																		
		PM	2203	1520	2717																																																																																		
DFC	= Entry Flow/Capacity = Q/Qe	AM	0.03	0.02	0.08																																																																																		
		Logistic	0.01	0.02	0.09																																																																																		
		PM	0.02	0.05	0.11																																																																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td>DFC of Critical Approach</td> <td>=</td> <td>AM</td> <td style="text-align: center;">0.08</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td style="text-align: center;">0.09</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td style="text-align: center;">0.11</td> </tr> </tbody> </table>				DFC of Critical Approach	=	AM	0.08			Logistic	0.09			PM	0.11																																																																								
DFC of Critical Approach	=	AM	0.08																																																																																				
		Logistic	0.09																																																																																				
		PM	0.11																																																																																				
CTA Consultants Ltd.																																																																																							

# Roundabout Junction Calculation

Junction : <u>(RA8) Tsing Yi Road / Ching Hong Road</u>		Job No.: <u>24001HK</u>																	
Scenario : <u>2029 Design Traffic Flow</u>																			
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 4 Tsing Yi Road SB</th> </tr> </thead> <tbody> <tr> <td>230</td> <td>410</td> <td>375</td> <td></td> </tr> <tr> <td>&lt;180&gt;</td> <td>&lt;505&gt;</td> <td>&lt;325&gt;</td> <td></td> </tr> <tr> <td>(220)</td> <td>(475)</td> <td>(315)</td> <td></td> </tr> </tbody> </table>				Arm 4 Tsing Yi Road SB				230	410	375		<180>	<505>	<325>		(220)	(475)	(315)	
Arm 4 Tsing Yi Road SB																			
230	410	375																	
<180>	<505>	<325>																	
(220)	(475)	(315)																	
<table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td>465</td> <td>&lt;485&gt;</td> <td>(485)</td> <td></td> </tr> </tbody> </table>				465	<485>	(485)													
465	<485>	(485)																	
<table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td>685</td> <td>&lt;635&gt;</td> <td>(630)</td> <td></td> </tr> <tr> <td>75</td> <td>&lt;105&gt;</td> <td>(115)</td> <td></td> </tr> <tr> <td>65</td> <td>&lt;90&gt;</td> <td>(70)</td> <td></td> </tr> </tbody> </table>				685	<635>	(630)		75	<105>	(115)		65	<90>	(70)					
685	<635>	(630)																	
75	<105>	(115)																	
65	<90>	(70)																	
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 3 Ching Hong Road</th> </tr> </thead> <tbody> <tr> <td>555</td> <td>&lt;470&gt;</td> <td>(520)</td> <td></td> </tr> </tbody> </table>				Arm 3 Ching Hong Road				555	<470>	(520)									
Arm 3 Ching Hong Road																			
555	<470>	(520)																	
<table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td>85</td> <td></td> <td>325</td> <td>0</td> </tr> <tr> <td>&lt;120&gt;</td> <td></td> <td>&lt;265&gt;</td> <td>&lt;25&gt;</td> </tr> <tr> <td>(105)</td> <td></td> <td>(300)</td> <td>(0)</td> </tr> </tbody> </table>				85		325	0	<120>		<265>	<25>	(105)		(300)	(0)				
85		325	0																
<120>		<265>	<25>																
(105)		(300)	(0)																
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4" style="text-align: center;">Arm 2 Tsing Yi Road NB</th> </tr> </thead> <tbody> <tr> <td>705</td> <td>&lt;775&gt;</td> <td>(1080)</td> <td></td> </tr> </tbody> </table>				Arm 2 Tsing Yi Road NB				705	<775>	(1080)									
Arm 2 Tsing Yi Road NB																			
705	<775>	(1080)																	
<table border="1" style="width:100%; border-collapse: collapse;"> <tbody> <tr> <td>AM</td> <td>[Logistic]</td> <td>(PM)</td> <td></td> </tr> <tr> <td>[Logistic]</td> <td></td> <td></td> <td></td> </tr> <tr> <td>(PM)</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>				AM	[Logistic]	(PM)		[Logistic]				(PM)							
AM	[Logistic]	(PM)																	
[Logistic]																			
(PM)																			
<b>Input Parameters</b>																			
		Arm 1	Arm 2	Arm 3	Arm 4														
V	=	Approach half width (m)	4.5	7.3	7														
E	=	Entry width (m)	9	8.5	8.5														
L	=	Effective length of flare (m)	25	4	16														
R	=	Entry radius	24.5	30	100														
D	=	Inscribed circle diameter (m)	30	30	30														
A	=	Entry angle (degree)	44	40	27														
Q	=	Entry flow (pcu/hr)	AM	410	825	1015													
			Logistic	410	830	1010													
			PM	405	815	1010													
Qc	=	Circulating flow across entry (pcu/hr)	AM	705	555	465													
			Logistic	775	470	485													
			PM	1080	520	485													
<b>Output Parameters</b>																			
		Arm 1	Arm 2	Arm 3	Arm 4														
S	=	Sharpness of flare = 1.6*(E-V)/L	0.29	0.48	0.15														
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	0.96	0.98	1.05														
X2	=	V+((E-V)/(1+2*S))	7.36	7.91	8.15														
M	=	Exp((D-60)/10)	0.05	0.05	0.05														
F	=	303*X2	2229	2397	2471														
Td	=	1+(0.5/(1+M))	1.48	1.48	1.48														
Fc	=	0.21*Td*(1+0.2*X2)	0.77	0.80	0.82														
Qe	=	Capacity = K*(F-Fc*Qc)	AM	1622	1917	2195													
			Logistic	1570	1984	2178													
			PM	1346	1945	2178													
DFC	=	Entry Flow/Capacity = Q/Qe	AM	0.25	0.43	0.46													
			Logistic	0.26	0.42	0.46													
			PM	0.30	0.42	0.46													
<b>DFC of Critical Approach</b>																			
	=	AM	0.46																
		Logistic	0.46																
		PM	0.46																

# Roundabout Junction Calculation

Junction : (RA9) Tam Kon Shan Road Job No.: 24001HK  
 Scenario : 2029 Design Traffic Flow

**Arm 4 Development Access**

0	0	0
<0>	<0>	<5>
(0)	(0)	(5)

**Arm 1 Tam Kon Shan Road**

15	<5>	(15)
0	<5>	(0)
25	<35>	(10)

**Arm 3 Tam Kon Shan Road**

0	<0>	(0)
45	<60>	(40)
5	<0>	(5)

**Arm 2 Tsing Yi North Coastal Road**

25	10	60	
<30>	<0>	<90>	
(40)	(10)	(70)	

**Approach Data**

125	<155>	(130)
-----	-------	-------

**Time Periods**

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

**Input Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4	
V	=	Approach half width (m)	3.3	4	3.4	4.2
E	=	Entry width (m)	6.7	4.9	5.8	5.4
L	=	Effective length of flare (m)	10	10	10	10
R	=	Entry radius	32	97	52	34
D	=	Inscribed circle diameter (m)	30	30	30	30
A	=	Entry angle (degree)	34	32	31	46
Q	=	Entry flow (pcu/hr)	AM: 40, Logistic: 45, PM: 25	95	50	0
Qc	=	Circulating flow across entry (pcu/hr)	AM: 5, Logistic: 0, PM: 5	45	85	125

**Output Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4	
S	=	Sharpness of flare = 1.6*(E-V)/L	0.54	0.14	0.38	0.19
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	1.00	1.03	1.03	0.96
X2	=	V+((E-V)/(1+2*S))	4.93	4.70	4.76	5.07
M	=	Exp((D-60)/10)	0.05	0.05	0.05	0.05
F	=	303*X2	1493	1424	1442	1535
Td	=	1+(0.5/(1+M))	1.48	1.48	1.48	1.48
Fc	=	0.21*Td*(1+0.2*X2)	0.62	0.60	0.61	0.62
Qe	=	Capacity = K*(F-Fc*Qc)	AM: 1497, Logistic: 1500, PM: 1497	1441	1427	1406
DFC	=	Entry Flow/Capacity = Q/Qe	AM: 0.03, Logistic: 0.03, PM: 0.02	0.07	0.04	0.00

**DFC of Critical Approach =**

AM	0.07
Logistic	0.08
PM	0.08

# Roundabout Junction Calculation

Junction : (RA10) Tsing Sheung Road / Tsing Ko Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

Arm 4 Tsing Ko Road			
10	205		5
<45>	<170>		<20>
(5)	(145)		(15)

Arm 1 Tsing Sheung Road WB		
5	<0>	(15)
55	<60>	(90)
120	<120>	(165)

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	= Approach half width (m)	6.6		5.6	6.4
E	= Entry width (m)	12.9		5.1	11.6
L	= Effective length of flare (m)	18		30	30
R	= Entry radius	47		67.3	75
D	= Inscribed circle diameter (m)	50		50	50
A	= Entry angle (degree)	41		22	46
Q	= Entry flow (pcu/hr)	AM	180	445	220
		Logistic	180	420	235
		PM	270	310	165
Qc	= Circulating flow across entry (pcu/hr)	AM	240	70	120
		Logistic	255	105	105
		PM	180	110	85

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	= Sharpness of flare = $1.6*(E-V)/L$	0.56		-0.03	0.28
K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$	0.99		1.06	0.98
X2	= $V+((E-V)/(1+2*S))$	9.57		5.07	9.74
M	= $Exp((D-60)/10)$	0.37		0.37	0.37
F	= $303*X2$	2900		1537	2953
Td	= $1+(0.5/(1+M))$	1.37		1.37	1.37
Fc	= $0.21*Td*(1+0.2*X2)$	0.84		0.58	0.85
Qe	= Capacity = $K*(F-Fc*Qc)$	AM	2672	1589	2795
		Logistic	2660	1568	2808
		PM	2722	1565	2824
DFC	= Entry Flow/Capacity = $Q/Qe$	AM	0.07	0.28	0.08
		Logistic	0.07	0.27	0.08
		PM	0.10	0.20	0.06


  

<b>DFC of Critical Approach</b>	<b>=</b>	<b>AM</b>	<b>0.28</b>
		<b>Logistic</b>	<b>0.27</b>
		<b>PM</b>	<b>0.20</b>

Junction: (J1) Tsing Yi Road West / Cheung Tsing Highway																																																				
Description: 2029 Design Traffic Flow																																																				
Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		A.M. Peak			P.M. Peak																															
						Left	Right			A.M.	P.M.			A.M.	P.M.	A.M.	P.M.	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y																													
Tsing Yi Road West	S	↓	2	A	3.5	0	0	0	1	0%	0%	1965	6135	1965	1965	5900	5825	218	0.111	0.111	160	0.081	0.083																													
	S	↔	2	A	3.3	0	20	0	0	46%	100%	2085	0	2015	1940	0	0	224	0.111		161	0.083																														
	S	↔	2	A	3.3	0	17.5	0	0	100%	100%	2085	0	1920	1920	0	0	213	0.111		159	0.083																														
Cheung Tsing Highway	E	↑	3	A,B	3.4	20	0	0	1	100%	100%	1955	1955	1820	1820	1820	1820	545	0.299		420	0.231																														
	E	↔	4	B	3.5	0	30	0	0	100%	100%	2105	4210	2005	2005	3990	3990	244	0.122		161	0.080																														
	E	↓	4	B	3.5	0	25	0	0	100%	100%	2105	0	1985	1985	0	0	241	0.122	0.122	159	0.080	0.080																													
Tsing Yi Road West	N	↔	1	C	3.6	20	0	6.5	1	100%	100%	1702	3544	1585	1585	3425	3425	440	0.278	0.278	365	0.230	0.230																													
	N	↑	1	C	3.6	0	0	6.5	0	0%	0%	1842	0	1840	1840	0	0	325	0.177		290	0.158																														
*																																																				
Pedestrian crossing			↔	5P	C	Min. Green time = 5GM + 10FG = 15s																																														
			↕	6P	C	Min. Green time = 5GM + 6FG = 11s																																														
			↔	7P	A,B	Min. Green time = 5GM + 9FG = 14s																																														
			↕	8P	B	Min. Green time = 5GM + 10FG = 15s																																														
Notes:												Traffic Flow (pcu / hr)				A.M. Check Phase				P.M. Check Phase																																
																<table border="1"> <tr><td>ey</td><td>0.510</td><td>0.577</td></tr> <tr><td>L (sec)</td><td>13</td><td>9</td></tr> <tr><td>C (sec)</td><td>100</td><td>100</td></tr> <tr><td>y pract.</td><td>0.783</td><td>0.819</td></tr> <tr><td>R.C. (%)</td><td><b>53%</b></td><td><b>42%</b></td></tr> </table>				ey	0.510	0.577	L (sec)	13	9	C (sec)	100	100	y pract.	0.783	0.819	R.C. (%)	<b>53%</b>	<b>42%</b>	<table border="1"> <tr><td>ey</td><td>0.393</td><td>0.461</td></tr> <tr><td>L (sec)</td><td>13</td><td>9</td></tr> <tr><td>C (sec)</td><td>105</td><td>105</td></tr> <tr><td>y pract.</td><td>0.789</td><td>0.823</td></tr> <tr><td>R.C. (%)</td><td><b>100%</b></td><td><b>78%</b></td></tr> </table>			ey	0.393	0.461	L (sec)	13	9	C (sec)	105	105	y pract.	0.789	0.823	R.C. (%)	<b>100%</b>	<b>78%</b>
ey	0.510	0.577																																																		
L (sec)	13	9																																																		
C (sec)	100	100																																																		
y pract.	0.783	0.819																																																		
R.C. (%)	<b>53%</b>	<b>42%</b>																																																		
ey	0.393	0.461																																																		
L (sec)	13	9																																																		
C (sec)	105	105																																																		
y pract.	0.789	0.823																																																		
R.C. (%)	<b>100%</b>	<b>78%</b>																																																		
Stage / Phase Diagrams																																																				
I/G = 5							I/G = 5							I/G = 6																																						

Junction: (J2) Tsing Hung Road / Tsing Yi Road																								
Description: 2029 Design Traffic Flow																								
Approach	Direction	Movement notation	Phase	Stage	Width (m)			Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
					Left	Right		Left	Right		AM	PM			AM	PM	AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Tsing Yi Road	S	↓	1	A	3.5	0.0	0	0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	381	0.194		282	0.144	
	S	↓	1	A	3.5	0.0	0	0	0	0	0%	0%	2105	0	2105	2105	0	0	409	0.194		303	0.144	
	S	←	1	A	3.6	0.0	18	0	100%	100%	2115	2115	1950	1950	1950	1950	370	0.190		380	0.195	0.195		
Tsing Yi Road	N	↑	4	C	4.0	30.0	0	1	100%	100%	2015	2015	1920	1920	1920	1920	1920	1920	60	0.031		55	0.029	
	N	↑	4	C	3.5	0.0	0	0	0%	0%	2105	4210	2105	2105	4210	4210	4210	4210	330	0.157	0.157	278	0.132	
	N	↑	4	C	3.5	0.0	0	0	0%	0%	2105	0	2105	2105	0	0	0	0	330	0.157		278	0.132	0.132
Tsing Hung Road	E	→	2	A,B	3.3	25.0	0	1	100%	100%	1945	1945	1835	1835	1835	1835	1835	1835	525	0.286	0.286	340	0.185	
	E	→	3	B	4.0	0.0	22	0	100%	100%	2155	2155	2015	2015	2015	2015	2015	2015	45	0.022		30	0.015	
Pedestrian Crossing		↔	5P	D	Min. Green time = 5GM + 7FG = 12s																			
		↔	6P	A,B,D	Min. Green time = 5GM + 5FG = 10s																			
		↔	7P	C,D	Min. Green time = 5GM + 10FG = 15s																			
		↔	8P	C,D	Min. Green time = 5GM + 5FG = 10s																			

Notes:	Traffic Flow (pcu / hr)		Weekday AM Peak		AM Peak Check Phase		PM Peak Check Phase	
	A,B,C,D	AB,C,D	A,B,C,D	AB,C,D	ey	ey	ey	ey
	525(340)	45(30)	370(380)	790(585)	0.373	0.443	0.327	0.317
					33	22	33	22
					120	120	100	100
					0.653	0.735	0.603	0.702
					75%	66%	85%	121%



I/G = 2	I/G = 6 + Min. G 5	I/G = 5	I/G = 5 + 12		
I/G = 2	I/G = 6 + Min. G 5	I/G = 5	I/G = 5 + 12		

Junction: ( J4 ) Sai Tso Wan Road / Tsing Yi Road West / Tsing Yi Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% ) uphill Gradient	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		A.M. Peak			P.M. Peak		
					Left	Right	A.M.	P.M.			A.M.	P.M.			Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Tsing Yi Road	NE	↖	1	A	4.5	15	0	6.5	1	100%	100%	1792	1792	1630	1630	275	0.169	0.169	245	0.150	0.150	
	NE	↗	1	A	3.4	0	0	6.5	0	0%	0%	1822	1822	1820	1820	230	0.126		220	0.121		
Sai Tso Wan Road	NW	↖	3	C,D	3.8	15	0	0	1	100%	100%	1995	1995	1815	1815	530	0.292		440	0.242		
	NW	↗	4	D	3.8	0	25	0	0	100%	100%	2135	2135	2015	2015	225	0.112	0.112	205	0.102	0.102	
Tsing Yi Road West	SE	↘	2	B,C	3.4	0	0	0	1	0%	0%	1955	1955	1955	1955	235	0.120		145	0.074		
	SE	↙	2	B,C	3.7	0	25	0	0	100%	100%	2125	2125	2005	2005	580	0.289	0.289	285	0.142	0.142	
Pedestrian crossing		↑ ↓ ← →	5p 6p 7p 8p	A,B D B,C A,D	Min. Green time = 5GM + 8FG = 13s Min. Green time = 5GM + 10FG = 15s Min. Green time = 5GM + 9FG = 14s Min. Green time = 5GM + 7FG = 12s																	

Notes:	<p>Traffic Flow (pcu / hr)</p>	<p>A.M. Check Phase</p> <p>Ey 0.570 L (sec) 19 C (sec) 120 y pract. 0.758 R.C. (%) 33%</p>	<p>P.M. Check Phase</p> <p>Ey 0.394 L (sec) 19 C (sec) 110 y pract. 0.745 R.C. (%) 89%</p>
--------	--------------------------------	--	--

Stage / Phase Diagrams			
<p><b>A</b></p>	<p><b>B</b></p>	<p><b>C</b></p>	<p><b>D</b></p>
I/G = 7	I/G = 10		I/G = 5


TRAFFIC SIGNALS CALCULATION

Job No: 24001HK

Junction: **(J5) Sai Tso Wan Road Near VEC**  
 Description: **2029 Design Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak			
						Left	Right		AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y	
Sai Tso Wan Road	EB	→	3	A	4.0	0.0	0	1	0%	0%	2015	2015	2015	2015	2015	2015	640	0.318	0.318	535	0.266		
Sai Tso Wan Road	WB	←	1	A,B	4.0	0.0	0	1	0%	0%	2015	2015	2015	2015	2015	2015	600	0.298		720	0.357	0.357	
Sai Tso Wan Road	WB	↖	2	B,C	4.0	0.0	10	0	100%	100%	2155	2155	1875	1875	1875	1875	150	0.080	0.080	35	0.019		

Notes: (None)	Traffic Flow (pcu / hr)	AM (PM) Peak	A,BC		AB,C		A,BC		AB,C	
			AM Peak Check Phase		PM Peak Check Phase					
		640(535) →	εy	0.398	0.298	εy	0.284	0.357		
		↖ 150(35)	L (sec)	11	18	L (sec)	11	18		
		← 600(720)	C (sec)	91	91	C (sec)	91	91		
			y pract.	0.791	0.722	y pract.	0.791	0.722		
			R.C. (%)	99%	142%	R.C. (%)	178%	102%		




I/G = 6      I/G = 7



Junction: (J8) Tsing Yi Road West / Ching Hong Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)			Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak					
					Left	Right	0.0	0.0	0			0	0			0	AM	PM	AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Tsing Yi Road West	S	↓	1	A	3.0	0.0	0	5.5	0	0	0%	0%	1824	3698	1824	1824	3698	3698	190	0.104	0.207	126	0.069	0.128				
	S	↓	1	A	3.5	0.0	0	5.5	0	0	0%	0%	1874	0	1874	1874	0	0	195	0.104		129	0.069					
	S	↘	1	A	3.7	10.0	0	5.5	1	100%	100%	1754	1754	1525	1525	1525	1525	315	0.207		195	0.128						
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	188	0.096		210	0.107						
	N	↑	2	A,B	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	202	0.096		225	0.107						
	N	↗	3	B	3.3	0.0	18	0	0	100%	100%	2085	2085	1925	1925	1925	1925	380	0.197	0.197	315	0.164	0.164					
Ching Hong Road	W	←	4	C	3.4	18.0	20	0	0	18% / 82%	17% / 83%	2095	0	1945	1945	0	0	298	0.153	0.153	264	0.136	0.136					
	W	↓	4	C	3.4	15.0	0	0	1	100%	100%	1955	4050	1775	1775	3720	3720	272	0.153		241	0.136						
Pedestrian crossing		↕	5P	A,B			Min. Green time = 11s (G) + 8s (FS) = 19s																					
		↕	6P	C			Min. Green time = 5s (G) + 12s (FS) = 17s																					
Pedestrian Crossing																												

Notes:	Traffic Flow (pcu/hr)	Weekday AM Peak		AM Peak Check Phase		PM Peak Check Phase	
		390(435)	380(315)	385(255)	315(195)	Ey	0.557
				L (sec)	14	L (sec)	14
				C (sec)	100	C (sec)	100
				y pract.	0.774	y pract.	0.774
				R.C. (%)	39%	R.C. (%)	81%



Junction: (J9) Tsing Yi Road West / Liu To Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
						Tsing Yi Road West	S			↓	2			A,B	3.3	0.0	0	5	1	0%	0%	1735	3610
	S	↓	2	A,B	3.3	0.0	0	5	0	0%	0%	1875	0	1875	1875	0	0	229	0.122		195	0.104	
	S	↙	3	B	3.3	0.0	22	5	0	100%	100%	1875	1875	1755	1755	1755	1755	310	0.177	0.177	335	0.191	0.191
Tsing Yi Road West	N	↕	1	A	3.2	10.0	0	0	1	50%	38%	1935	4100	1800	1830	3965	3995	288	0.160	0.160	300	0.164	0.164
	N	↑	1	A	4.1	0.0	0	0	0	0%	0%	2165	0	2165	2165	0	0	347	0.160		355	0.164	
Liu To Road	E	↗	5	B,C	3.2	10.0	0	0	1	100%	100%	1935	1935	1685	1685	1685	1685	410	0.243		295	0.175	
	E	↘	4	C	4.1	0.0	18	0	0	100%	100%	2165	2165	2000	2000	2000	2000	250	0.125	0.125	80	0.040	0.040
Pedestrian crossing		↕	6P	A,D																			
		↕	7P	C,D																			
		↔	8P	D																			
Pedestrian Crossing																							

A,B,C,D A,B,C,D A,B,C,D A,B,C,D


Notes:	Traffic Flow (pcu / hr) Weekday AM Peak	AM Peak Check Phase	PM Peak Check Phase
		e <sub>y</sub> 0.404 0.462 L (sec) 34 38 C (sec) 130 130 y pract. 0.665 0.637 R.C. (%) 65% 38%	e <sub>y</sub> 0.339 0.395 L (sec) 34 38 C (sec) 110 110 y pract. 0.622 0.589 R.C. (%) 83% 49%

Stage / Phase Diagrams			
L/G = 5	L/G = 7	L/G = 5	L/G = 11 + Ped 13

Junction: (J10) Tsing Yi Road West / Fung Shue Wo Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Site Factor	Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM				AM	PM	AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Fung Shue Wo Road (To Tsing Yi Road West)	S	↓	1	A,D	4.1	0.0	0	3	0	0%	0%	1	2039	4058	2039	2039	4058	4058	304	0.149	0.292	279	0.137	0.240
	S	↓	1	A,D	3.9	0.0	0	3	0	0%	0%	1	2019	0	2019	2019	0	0	301	0.149		276	0.137	
Fung Shue Wo Road (To Fung Shue Wo Road)	S	↓	1	A,D	4.0	0.0	0	3	1	0%	0%	1	1889	2294.8	1889	1889	2294.8	2294.8	552	0.292		453	0.240	
	S	↓	1	A,D	4.0	0.0	0	3	0	0%	0%	0.2	405.8	0	405.8	405.8	0	0	118	0.292		97	0.240	
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%	0%	1	1965	2491.3	1965	1965	2491.25	2491.25	540	0.275		544	0.277	
	N	↑	2	A,B	3.5	0.0	0	0	0	0%	0%	0.25	526.25	0	526.25	526.25	0	0	145	0.275		146	0.277	
	N	↗	3	B	3.6	0.0	18	0	0	100%	100%	1	2115	2115	1950	1950	1950	1950	220	0.113	0.113	145	0.074	0.074
Fung Shue Wo Road	N	↖	4	C	3.8	35.0	0	3	1	100%	100%	1	1869	2193.6	1790	1790	2100	2100	128	0.071		124	0.069	
	N	↖	4	C	4.0	38.0	0	3	0	100%	100%	0.16	324.64	0	310	310	0	0	22	0.071		21	0.069	
Fung Shue Wo Road	N	↗	4	C	3.6	0.0	43	3	0	100%	100%	0.23	457.47	2446.5	440	440	2355	2355	121	0.274	0.274	103	0.234	0.234
	N	↗	4	C	3.6	0.0	40	3	0	100%	100%	1	1989	0	1915	1915	0	0	524	0.274		447	0.234	
Pedestrian crossing		↔	5p	D																				
		↔	6P	B,C																				
		↕	7P	A,C,D																				
		↕	8P	A,B,D																				

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak		AM Peak Check Phase		PM Peak Check Phase	
		605(555)	670(550)	εy 0.679	0.548	εy 0.679	0.548
		↑	↗	L (sec) 12	12	L (sec) 12	12
		↖	↘	C (sec) 100	100	C (sec) 100	100
		↖	↘	y pract. 0.792	0.792	y pract. 0.792	0.792
		685(690)	220(145)	R.C. (%) 17%	17%	R.C. (%) 45%	45%



Junction: (J11) Tsing Yi Heung Sze Wui Road / Cheung Wan Street  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Tsing Yi Heung Sze Wui Road	N	↑	2	A,B	3.5	0.0	0	0	1	0%	0%	1965	4070	1965	1965	4070	4070	702	0.357		611	0.311	0.311
	N	↑	2	A,B	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	753	0.357		654	0.311	
Cheung Wan Street	W	↙	3	C	3.5	18.0	20	0	0	31% / 69%	47% / 53%	2105	0	1955	1950	0	0	428	0.219	0.219	360	0.185	0.185
	W	↘	3	C	3.5	15.0	0	0	1	100%	100%	1965	4070	1785	1785	3740	3735	392	0.219		330	0.185	
Tsing Yi Heung Sze Wui Road	S	↘	1	A,D	3.5	10.0	0	0	1	100%	100%	1965	6175	1710	1710	5920	5920	695	0.406	0.406	495	0.289	
	S	↓	1	A,D	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	555	0.264		428	0.203	
	S	↓	1	A,D	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	555	0.264		428	0.203	
Pedestrian crossing		↑ ↓	4P	B																			Min. Green time = 8GM + 11FG = 19s
		← →	5P	D																			Min. Green time = 5GM + 10FG = 15s
		← →	6P	C																			Min. Green time = 5GM + 8FG = 13s

AB,C,D AD,B,C AB,C,D AD,B,C


Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak		AM Peak Check Phase		PM Peak Check Phase		
		1455(1265)	1110(855)	695(495)	Ey 0.577	0.626	Ey 0.496	0.474
			↓	↘	L (sec) 32	33	L (sec) 32	33
					C (sec) 114	114	C (sec) 100	100
					y pract. 0.647	0.639	y pract. 0.612	0.603
					R.C. (%) 12%	2%	R.C. (%) 23%	27%

Stage / Phase Diagrams			
I/G = 2	I/G = 8 + Ped 19	I/G = 3 I/G = 5	I/G = 5 I/G = 12 + Ped 15

Junction: (J12) Tsing Yi Heung Sze Wui Road / Chung Mei Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Chung Mei Road	E	↗	5	B,C	3.3	10.0	0	0	1	100%	100%	1945	1945	1690	1690	1690	1690	260	0.154		280	0.166	
	E	↘	6	C	3.3	0.0	18	0	0	100%	100%	2085	2085	1925	1925	1925	1925	315	0.164	0.164	235	0.122	0.122
Tsing Yi Heung Sze Wui Road	N	↖	2	A,C	3.3	25.0	0	0	1	100%	100%	1945	1945	1835	1835	1835	1835	290	0.158		355	0.193	
	N	↑	3	A	3.5	0.0	0	0	0	0%	0%	2105	4210	2105	2105	4210	4210	545	0.259	0.259	478	0.227	0.227
	N	↑	3	A	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	545	0.259		478	0.227	
Tsing Yi Heung Sze Wui Road	S	↘	1	A,B	3.5	0.0	0	3	1	0%	0%	1839	3818	1839	1839	3818	3818	621	0.338		486	0.265	
	S	↙	1	A,B	3.5	0.0	0	3	0	0%	0%	1979	0	1979	1979	0	0	669	0.338		524	0.265	
	S	↖	4	B	3.5	0.0	22	3	0	100%	100%	1979	1979	1855	1855	1855	1855	370	0.199	0.199	290	0.156	0.156

Notes:	Traffic Flow (pcu / hr)    Weekday AM Peak 260(280)    ↗    ↘    ↖    ↙    ↘    ↙ 315(235)    ↘    ↙    ↖    ↙    ↘    ↙ 290(355)    1090(955)	AM Peak Check Phase E <sub>y</sub> 0.622 L (sec)    15 C (sec)    114 y pract.    0.782 R.C. (%)    26%	PM Peak Check Phase E <sub>y</sub> 0.505 L (sec)    15 C (sec)    100 y pract.    0.765 R.C. (%)    51%



Junction: (J14) Tsing Yi Road / Planned New Road  
 Description: 2029 Design Traffic Flow (With Planned New Road)

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		AM Peak			PM Peak		
						Left	Right			AM	PM			AM	PM	AM	PM	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Tsing Yi Road	N	↑	A	1	3.5	0.0	0	0	1	0%	0%	1965	4070	1965	1965	4065	4065	554	0.282	0.282	546	0.278	0.278
	N	↗	A	1	3.5	0.0	40	0	0	8%	9%	2105	0	2100	2100	0	0	591	0.282		584	0.278	
Planned New Road	W	↖	C	3	3.5	0.0	18	0	0	100%	100%	2105	2105	1945	1945	1945	1945	50	0.026		50	0.026	
	W	↘	C	3	3.5	10.0	0	0	1	100%	100%	1965	1965	1710	1710	1710	1710	50	0.029	0.029	50	0.029	0.029
Tsing Yi Road	S	↘	B	2	3.5	10.0	0	0	1	10%	13%	1965	4070	1935	1925	4040	4030	496	0.256	0.256	373	0.194	0.194
	S	↓	B	2	3.5	0.0	0	0	0	0%	0%	2105	0	2105	2105	0	0	539	0.256		407	0.193	
Pedestrian crossing		↔	Dp	1		Min. Green time = 5GM + 7FG = 12s																	
		↑	EP	1,2		Min. Green time = 5GM + 7FG = 12s																	
		↔	Fp	2,3		Min. Green time = 5GM + 7FG = 12s																	
		↓	Gp	3		Min. Green time = 5GM + 7FG = 12s																	
		↔	Hp	1,3		Min. Green time = 5GM + 7FG = 12s																	
		↔	Ip	2		Min. Green time = 5GM + 7FG = 12s																	

Notes:	Traffic Flow (pcu / hr)    Weekday AM Peak 1095(1080)    50(50)    985(730)    50(50)	AM Peak Check Phase Ey    0.311 L (sec)    18 C (sec)    120 y pract.    0.765 R.C. (%) <b>146%</b>	PM Peak Check Phase Ey    0.307 L (sec)    18 C (sec)    120 y pract.    0.765 R.C. (%) <b>149%</b>
--------	--	--	--

Stage / Phase Diagrams			
<p>1. I/G = 5</p>	<p>2. I/G = 10</p>	<p>3. I/G = 6</p>	

Junction: (J1) Cheung Tsing Highway / Tsing Yi Road West  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Neb-side 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak				
					Left	Right	Left	Right			Left	Right			Logistic Peak	Logistic Peak	Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y	
Tsing Yi Road West	S	↓	2	A	3.5	0	0	0	0	1	0%		1965	6135	1965	5895	158	0.081	0.081				
	S	↙	2	A	3.3	0	20	0	0	0	50%		2085	0	2010	0	162	0.081					
	S	↘	2	A	3.3	0	17.5	0	0	0	100%		2085	0	1920	0	155	0.081					
Cheung Tsing Highway	E	↗	3	A,B	3.4	20	0	0	1	100%		1955	1955	1820	1820	405	0.223						
	E	↘	4	B	3.5	0	30	0	0	100%		2105	4070	2005	3860	280	0.140						
	E	↙	4	B	3.5	0	25	0	1	100%		1965	0	1855	0	260	0.140	0.140					
Tsing Yi Road West	N	↙	1	C	3.6	20	0	6.5	1	100%		1702	3544	1585	3425	525	0.331	0.331					
	N	↘	1	C	3.6	0	0	6.5	0	0%		1842	0	1840	0	325	0.177						
Pedestrian crossing		↕	5P	C	Min. Green time = 5GM + 10FG = 15s																		
		↕	6P	C	Min. Green time = 5GM + 6FG = 11s																		
		↕	7P	A,B	Min. Green time = 5GM + 9FG = 14s																		
		↕	8P	B	Min. Green time = 5GM + 10FG = 15s																		

Notes:	Traffic Flow (pcu / hr)		Logistic Peak Check Phase	
			A,B,C    AB,C Ey    0.552    0.554 L (sec)    13    9 C (sec)    100    100 y pract.    0.783    0.819 R.C. (%)    42%    48%	




I/G = 5      I/G = 5      I/G = 6





Junction: (J2) Tsing Hung Road / Tsing Yi Road																									
Description: 2029 Design Traffic Flow																									
Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)			Logistic Peak							
						Left	Right		Logistic Peak				Logistic Peak		Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y			
Tsing Yi Road	S	↓	1	A	3.5	0.0	0	1	0%		1965	4070	1965		4070	338	0.172								
	S	↓	1	A	3.5	0.0	0	0	0%		2105	0	2105		0	362	0.172								
	S	←	1	A	3.6	0.0	18	0	100%		2115	2115	1950		1950	320	0.164	0.172							
Tsing Yi Road	N	↑	4	C	4.0	30.0	0	1	100%		2015	2015	1920		1920	60	0.031								
	N	↑	4	C	3.5	0.0	0	0	0%		2105	4210	2105		4210	350	0.166								
	N	↑	4	C	3.5	0.0	0	0	0%		2105	0	2105		0	350	0.166	0.166							
Tsing Hung Road	E	→	2	A,B	3.3	25.0	0	1	100%		1945	1945	1835		1835	315	0.172								
	E	→	3	B	4.0	0.0	22	0	100%		2155	2155	2015		2015	45	0.022								
Pedestrian Crossing		↔	5P	D																					
		↔	6P	A,B,D																					
		↔	7P	C,D																					
		↔	8P	C,D																					
											A,B,C,D		A,B,C,D												
Notes:											Traffic Flow (pcu / hr) Weekday AM Peak					Logistic Peak Check Phase									
																Ey 0.338 0.338 L (sec) 33 22 C (sec) 100 100 y pract. 0.603 0.702 R.C. (%) <b>78%</b> <b>108%</b>									
Stage / Phase Diagrams																									
I/G = 2				I/G = 6 + Min. G 5				I/G = 5				I/G = 5 + 12													



Junction: (J4) Sai Tso Wan Road / Tsing Yi Road West / Tsing Yi Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Logistic Peak			
					Left	Right	Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)
Tsing Yi Road	NE	↖	1	A	4.5	15	0	6.5	1	100%		1792	1792	1630	275	0.169	0.169			
	NE	↗	1	A	3.4	0	0	6.5	0	0%		1822	1822	1820	265	0.146				
Sai Tso Wan Road	NW	↖	3	C,D	3.8	15	0	0	1	100%		1995	1995	1815	635	0.350				
	NW	↗	4	D	3.8	0	25	0	0	100%		2135	2135	2015	320	0.159	0.159			
Tsing Yi Road West	SE	↘	2	B,C	3.4	0	0	0	1	0%		1955	1955	1955	215	0.110				
	SE	↙	2	B,C	3.7	0	25	0	0	100%		2125	2125	2005	550	0.274	0.274			
Pedestrian crossing		↑ ↓ ↔	5p 6p 7p 8p	A,B D B,C A,D	Min. Green time = 5GM + 8FG = 13s Min. Green time = 5GM + 10FG = 15s Min. Green time = 5GM + 9FG = 14s Min. Green time = 5GM + 7FG = 12s															

Notes:	Traffic Flow (pcu / hr) 	Logistic Peak Check Phase E <sub>y</sub> 0.602 L (sec) 19 C (sec) 110 y pract. 0.745 R.C. (%) 24%
--------	---	--

Stage / Phase Diagrams			
<b>A</b> 	<b>B</b> 	<b>C</b> 	<b>D</b> 
I/G = 5	I/G = 5	I/G = 2	I/G = 5
I/G = 5	I/G = 8+12		

Junction: (J5) Sai Tso Wan Road Near VEC


Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak					
						Left	Right		Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y		
Sai Tso Wan Road	EB	→	3	A	4.0	0.0	0	1	0%		2015	2015	2015		2015		825	0.409	0.409			
Sai Tso Wan Road	WB	←	1	A,B	4.0	0.0	0	1	0%		2015	2015	2015		2015		625	0.310				
Sai Tso Wan Road	WB	↶	2	B,C	4.0	0.0	10	0	100%		2155	2155	1875		1875		130	0.069	0.069			

Pedestrian Crossing 4P C Min. green time = 6Gm + 5 FGm = 11s

Notes: (None)	Traffic Flow (pcu / hr)	AM (PM) Peak		Logistic Peak Check Phase						
		825	→	130	↶	625	←	εy	0.479	0.310
						L (sec)	11	18		
						C (sec)	91	91		
						y pract.	0.791	0.722		
						R.C. (%)	65%	133%		



I/G = 6	I/G = 7		
I/G = 3	I/G = 7	I/G = 5 + P11s	



Junction: **J9 - Tsing Yi Road West / Liu To Road**  
 Description: **2029 Design Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient	Nearside O/I	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak		
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value
Tsing Yi Road West	S	↓	2	A,B	3.3	0.0	0	5	1	0%		1735	3610	1735	3610	207	0.119			
	S	↓	2	A,B	3.3	0.0	0	5	0	0%		1875	0	1875	0	223	0.119			
	S	↙	3	B	3.3	0.0	22	5	0	100%		1875	1875	1755	1755	355	0.202	0.202		
Tsing Yi Road West	N	↑	1	A	3.2	10.0	0	0	1	47%		1935	4100	1805	3970	284	0.157	0.157		
	N	↑	1	A	4.1	0.0	0	0	0	0%		2165	0	2165	0	341	0.157			
Liu To Road	E	↗	5	B,C	3.2	10.0	0	0	1	100%		1935	1935	1685	1685	320	0.190			
	E	↘	4	C	4.1	0.0	18	0	0	100%		2165	2165	2000	2000	70	0.035	0.035		
Pedestrian crossing		↑ ↓ ← →	6P 7P 8P	A,D C,D D																

A,B,C,D A,B,C,D


Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	Logistic Peak Check Phase
	320 70		Day 0.347 0.395 L (sec) 34 38 C (sec) 130 130 y pract. 0.665 0.637 R.C. (%) <b>91%</b> <b>61%</b>

Stage / Phase Diagrams			
L/G = 5	L/G = 7	L/G = 5	L/G = 11 + Ped 13

Junction: **J10 - Tsing Yi Road West / Fung Shue Wo Road**  
 Description: **2029 Design Traffic Flow**

Approach	Direction	Movement notation	Phase	Stage	Width (m)		Radius (m)		(% uphill Gradient)	Nearside O/I	Pro. Turning (%)		Site Factor	Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
					Left	Right	Logistic Peak				Logistic Peak					Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Fung Shue Wo Road	S	↓	1	A,D	4.1	0.0	0	3	0	0%			1	2039	4058	2039	4058	329	0.161	0.229			
(To Tsing Yi Road West)	S	↓	1	A,D	3.9	0.0	0	3	0	0%			1	2019	0	2019	0	326	0.161				
Fung Shue Wo Road	S	↓	1	A,D	4.0	0.0	0	3	1	0%			1	1889	2294.8	1889	2294.8	432	0.229				
(To Fung Shue Wo Road)	S	↓	1	A,D	4.0	0.0	0	3	0	0%			0.2	405.8	0	405.8	0	93	0.229				
Tsing Yi Road West	N	↑	2	A,B	3.5	0.0	0	0	1	0%			1	1965	2491.3	1965	2491.25	505	0.257				
	N	↑	2	A,B	3.5	0.0	0	0	0	0%			0.25	526.25	0	526.25	0	135	0.257				
	N	↗	3	B	3.6	0.0	18	0	0	100%			1	2115	2115	1950	1950	165	0.085	0.085			
Fung Shue Wo Road	N	↖	4	C	3.8	35.0	0	3	1	100%			1	1869	2193.6	1790	2100	111	0.062				
	N	↖	4	C	4.0	38.0	0	3	0	100%			0.16	324.64	0	310	0	19	0.062				
Fung Shue Wo Road	N	↗	4	C	3.6	0.0	43	3	0	100%			0.23	457.47	2446.5	440	2355	101	0.229	0.229			
	N	↗	4	C	3.6	0.0	40	3	0	100%			1	1989	0	1915	0	439	0.229				
Pedestrian crossing		←---→	5p	D																			
		←---→	6P	B,C																			
		↑	7P	A,C,D																			
		↓	8P	A,B,D																			

Notes:	Traffic Flow (pcu / hr)	Weekday AM Peak	Logistic Peak Check Phase
			Ey 0.543 L (sec) 12 C (sec) 90 y pract. 0.780 R.C. (%) <b>44%</b>




I/G = 5      I/G = 5      I/G = 5



Junction: (J12) Tsing Yi Heung Sze Wui Road / Chung Mei Road  
 Description: 2029 Design Traffic Flow

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak		
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value
Chung Mei Road	E	↗	5	B,C	3.3	10.0	0	0	1	100%		1945	1945	1690	1690	280	0.166			
	E	↘	6	C	3.3	0.0	18	0	0	100%		2085	2085	1925	1925	255	0.132	0.132		
Tsing Yi Heung Sze Wui Road	N	↖	2	A,C	3.3	25.0	0	0	1	100%		1945	1945	1835	1835	285	0.155			
	N	↑	3	A	3.5	0.0	0	0	0	0%		2105	4210	2105	4210	390	0.185	0.185		
	N	↑	3	A	3.5	0.0	0	0	0	0%		2105	0	2105	0	390	0.185			
Tsing Yi Heung Sze Wui Road	S	↘	1	A,B	3.5	0.0	0	3	1	0%		1839	3818	1839	3818	446	0.242			
	S	↙	1	A,B	3.5	0.0	0	3	0	0%		1979	0	1979	0	479	0.242			
	S	↖	4	B	3.5	0.0	22	3	0	100%		1979	1979	1855	1855	365	0.197	0.197		
Pedestrian crossing																				

Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 280 ↗ 255 ↘ 365 ↖ 925.00 ↓ 285 ↖ 780 ↑	Logistic Peak Check Phase g <sub>y</sub> 0.515 L (sec) 15 C (sec) 114 y <sub>pract.</sub> 0.782 R.C. (%) 52%
--------	--	---



Junction: (J14) Tsing Yi Road / Planned New Road  
 Description: 2029 Design Traffic Flow (With Planned New Road)

Approach	Direction	Movement notation	Phase	Stage	Width (m)	Radius (m)		(% uphill Gradient)	Nearside 0/1	Pro. Turning (%)		Saturation Flow (pcu/hr)	Total Saturation Flow (pcu/hr)	Revised Saturation Flow (pcu/hr)		Total Revised Saturation Flow (pcu/hr)		Logistic Peak			
						Left	Right			Logistic Peak				Logistic Peak		Flow (pcu/hr)	y Value	Critical y	Flow (pcu/hr)	y Value	Critical y
Tsing Yi Road	N	↑	A	1	3.5	0.0	0	0	1	0%		1965	4070	1965		4065		573	0.292	0.292	
	N	↗	A	1	3.5	0.0	40	0	0	8%		2105	0	2100	0			612	0.291		
Planned New Road	W	↖	C	3	3.5	0.0	18	0	0	100%		2105	2105	1945		1945		50	0.026		
	W	↘	C	3	3.5	10.0	0	0	1	100%		1965	1965	1710		1710		50	0.029	0.029	
Tsing Yi Road	S	↓	B	2	3.5	10.0	0	0	1	11%		1965	4070	1935		4040		448	0.231	0.232	
	S	↙	B	2	3.5	0.0	0	0	0	0%		2105	0	2105	0			487	0.232		
Pedestrian crossing		↔	Dp	1		Min. Green time = 5GM + 7FG = 12s															
		↑	EP	1,2		Min. Green time = 5GM + 7FG = 12s															
		↔	Fp	2,3		Min. Green time = 5GM + 7FG = 12s															
		↓	Gp	3		Min. Green time = 5GM + 7FG = 12s															
		↔	Hp	1,3		Min. Green time = 5GM + 7FG = 12s															
		↔	Ip	2		Min. Green time = 5GM + 7FG = 12s															


Notes:	Traffic Flow (pcu / hr) Weekday AM Peak 1095(1080) 50(50) 985(730) 50(50) 	AM Peak Check Phase Ey 0.321 L (sec) 18 C (sec) 120 y pract. 0.765 R.C. (%) 138%
--------	--	---

Stage / Phase Diagrams		
1.	2.	3.
I/G = 5	I/G = 10	I/G = 6



# Priority Junction Calculation

Junction : ( J3 ) Tsing Yi Road / Tsing Sheung Road Job No.: 24001HK  
 Scenario : 2029 Design Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

- Y = 1 - 0.0345W
- q-AB, etc = the design flow of movement AB, etc
- W = major road width
- W-CR = central reserve width
- w-BA, etc = lane width to vehicle
- v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc
- v-IBA = visibility to the left for waiting vehicles in stream BA, etc

Geometry :	Input	Calculated
W	14	D 0.933
W-CR	0	E 1.012
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	F 0.616
Minor Road Share LT&RT? (Yes: 1, No: 0)	0	Y 0.517
V-rBA	30	
V-IBA	50	
V-rBC	50	
V-rCB	50	
w-BA	4.5	
w-BC	4.5	
w-CB	0	

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM
	pcu/hr				pcu/hr			
	q-CA	435	555	395	Q-BA	400	390	423
	q-CB	120	90	105	Q-BC	638	633	654
	q-AB	235	240	220	Q-CB	372	368	383
	q-AC	515	540	435	Q-CA	N/A	N/A	N/A
	q-BA	215	175	190	Q-BAC	N/A	N/A	N/A
	q-BC	145	140	135				
	f	0.403	0.444	0.415				


(If C-B blocked C- (If Minor Road Share LT&RT))

Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
	B-A	0.54	0.45	0.45
	B-C	0.23	0.22	0.21
	C-B	0.32	0.24	0.27
	C-A	N/A	N/A	N/A
	B-AC	N/A	N/A	N/A

**Critical DFC** **0.54** **0.45** **0.45**

# Priority Junction Calculation

Junction : ( J6 ) Sai Tso Wan Road / Tsing Tim Street Job No.: 24001HK  
 Scenario : 2029 Design Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

$$Y = 1 - 0.0345W$$

q-AB, etc = the design flow of movement AB, etc

W = major road width

W-CR = central reserve width

w-BA, etc = lane width to vehicle

v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc

v-IBA = visibility to the left for waiting vehicles in stream BA, etc


Geometry :	Input	Calculated
W	7	D 0.877
W-CR	0	E 0.933
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	F 0.616
Minor Road Share LT&RT? (Yes: 1, No: 0)	1	Y 0.759

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM	
	pcu/hr				pcu/hr				
	q-CA	425	425	335	Q-BA	350	360	423	
	q-CB	35	30	10	Q-BC	564	573	618	
	q-AB	125	105	70	Q-CB	359	368	401	
	q-AC	460	430	270	Q-CA	N/A	N/A	N/A	(If C-B blocked C-
	q-BA	115	95	95	Q-BAC	379	385	430	(If Minor Road Share
	q-BC	30	20	5					LT&RT)
	f	0.207	0.174	0.050					

Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
	B-A	N/A	N/A	N/A
	B-C	N/A	N/A	N/A
	C-B	0.10	0.08	0.02
	C-A	N/A	N/A	N/A
	B-AC	0.38	0.30	0.23
	<b>Critical DFC</b>	<b>0.38</b>	<b>0.30</b>	<b>0.23</b>

# Priority Junction Calculation

Junction : ( J13 ) Tsing Yi Road / Tsing Keung Street Job No.: 24001HK  
 Scenario : 2029 Design Traffic Flow



The predictive equations of capacity of movement are:

$$Q-BA = D(627 + 14W-CR - Y(0.364q-AC + 0.144q-AB + 0.229q-CA + 0.52q-CB))$$

$$Q-BC = E(745 - Y(0.364q-AC + 0.144q-AB))$$

$$Q-CB = F(745 - 0.364Y(q-AC + q-AB))$$

The geometric parameters represented by D, E, F are:

$$D = (1 + 0.094(w-BA - 3.65))(1 + 0.0009(V-rBA - 120))(1 + 0.0006(V-IBA - 150))$$

$$E = (1 + 0.094(w-BC - 3.65))(1 + 0.0009(V-rBC - 120))$$

$$F = (1 + 0.094(w-CB - 3.65))(1 + 0.0009(V-rCB - 120))$$

where

- Y = 1 - 0.0345W
- q-AB, etc = the design flow of movement AB, etc
- W = major road width
- W-CR = central reserve width
- w-BA, etc = lane width to vehicle
- v-rBA, etc = visibility to the right for waiting vehicles in stream BA, etc
- v-IBA = visibility to the left for waiting vehicles in stream BA, etc

Geometry :	Input			Calculated			
W	15	V-rBA	50	w-BA	4	D	0.910
W-CR	0	V-IBA	50	w-BC	4	E	0.968
C-B blocked C-A, residual width <2.5m? (Yes: 1, No: 0)	0	V-rBC	50	w-CB	4.7	F	1.029
Minor Road Share LT&RT? (Yes: 1, No: 0)	0	V-rCB	50			Y	0.483

Analysis :	Traffic Flow	AM	Logistic	PM	Capacity	AM	Logistic	PM	
	pcu/hr				pcu/hr				
q-CA	385	420	345	Q-BA	443	436	460		
q-CB	65	90	25	Q-BC	643	644	646		
q-AB	130	130	65	Q-CB	669	671	680		
q-AC	410	400	415	Q-CA	N/A	N/A	N/A	(If C-B blocked C-	
q-BA	70	115	65	Q-BAC	N/A	N/A	N/A	(If Minor Road Share	
q-BC	115	100	65					LT&RT)	
f	0.622	0.465	0.500						

Results :	Ratio of Flow-to-Capacity	AM	Logistic	PM
B-A		0.16	0.26	0.14
B-C		0.18	0.16	0.10
C-B		0.10	0.13	0.04
C-A		N/A	N/A	N/A
B-AC		N/A	N/A	N/A

**Critical DFC** **0.18    0.26    0.14**

# Roundabout Junction Calculation

Junction : (RA1) Tsing Yi Interchange (North) Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	= Approach half width (m)		6		6
E	= Entry width (m)		7		7
L	= Effective length of flare (m)		5		5
R	= Entry radius		62		41
D	= Inscribed circle diameter (m)		60		60
A	= Entry angle (degree)		27		60
Q	= Entry flow (pcu/hr)		1590		420
		AM	1590		420
		Logistic	1325		315
		PM	835		320
Qc	= Circulating flow across entry (pcu/hr)		0		1225
		AM	0		1225
		Logistic	0		995
		PM	0		600

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	= Sharpness of flare = $1.6*(E-V)/L$		0.32		0.32
K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$		1.04		0.92
X2	= $V+((E-V)/(1+2*S))$		6.61		6.61
M	= $Exp((D-60)/10)$		1.00		1.00
F	= $303*X2$		2003		2003
Td	= $1+(0.5/(1+M))$		1.25		1.25
Fc	= $0.21*Td*(1+0.2*X2)$		0.61		0.61
Qe	= Capacity = $K*(F-Fc*Qc)$		2090		1157
		AM	2090		1157
		Logistic	2090		1286
		PM	2090		1508
DFC	= Entry Flow/Capacity = $Q/Qe$		0.76		0.36
		AM	0.76		0.36
		Logistic	0.63		0.24
		PM	0.40		0.21

DFC of Critical Approach	=	AM	0.76
		Logistic	0.63
		PM	0.40

# Roundabout Junction Calculation

Junction : (RA1) Tsing Yi Interchange (South) Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

645	<515>	(420)
385	<300>	(285)
30	<20>	(35)
0	<0>	(0)

0	610	0
<0>	<635>	<0>
(0)	(685)	(0)

640	<655>	(720)
0	<0>	(0)
245	<265>	(375)
505	<430>	(270)

1385	<1125>	(1350)
910	230	0
<665>	<195>	<0>
(875)	(100)	(0)

245	<265>	(1060)
-----	-------	--------

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	= Approach half width (m)	7	6.8	7	6
E	= Entry width (m)	7.2	7	7.3	6.3
L	= Effective length of flare (m)	5	5	5	5
R	= Entry radius	23	25	24	44
D	= Inscribed circle diameter (m)	60	60	60	60
A	= Entry angle (degree)	43	54	27	23
Q	= Entry flow (pcu/hr)	750	1140	415	610
	AM	750	1140	415	610
	Logistic	695	860	320	635
	PM	645	975	320	685
Qc	= Circulating flow across entry (pcu/hr)	640	245	1385	645
	AM	640	245	1385	645
	Logistic	655	265	1125	515
	PM	720	1060	1350	420

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	= Sharpness of flare = 1.6*(E-V)/L	0.06	0.06	0.10	0.10
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	0.96	0.93	1.02	1.05
X2	= V+((E-V)/(1+2*S))	7.18	6.98	7.25	6.25
M	= Exp((D-60)/10)	1.00	1.00	1.00	1.00
F	= 303*X2	2175	2114	2197	1894
Td	= 1+(0.5/(1+M))	1.25	1.25	1.25	1.25
Fc	= 0.21*Td*(1+0.2*X2)	0.64	0.63	0.64	0.59
Qe	= Capacity = K*(F-Fc*Qc)	1697	1816	1331	1590
	AM	1697	1816	1331	1590
	Logistic	1688	1804	1501	1671
	PM	1648	1341	1354	1730
DFC	= Entry Flow/Capacity = Q/Qe	0.44	0.63	0.31	0.38
	AM	0.44	0.63	0.31	0.38
	Logistic	0.41	0.48	0.21	0.38
	PM	0.39	0.73	0.24	0.40

DFC of Critical Approach	=	AM	0.63
		Logistic	0.48
		PM	0.73

# Roundabout Junction Calculation

Junction :		(RA2) Tsing Yi Road / Tsing Yi Hong Wan Road / Tsing Sha Hig Job No.: 24001HK																																																																																							
Scenario :		2029 Design Traffic Flow																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 4 Tsing Yi Road SB</b></td> </tr> <tr> <td style="text-align: center;">0</td> <td style="text-align: center;">160</td> <td style="text-align: center;">655</td> <td style="text-align: center;">0</td> </tr> <tr> <td style="text-align: center;">&lt;0&gt;</td> <td style="text-align: center;">&lt;125&gt;</td> <td style="text-align: center;">&lt;550&gt;</td> <td style="text-align: center;">&lt;0&gt;</td> </tr> <tr> <td style="text-align: center;">(5)</td> <td style="text-align: center;">(90)</td> <td style="text-align: center;">(415)</td> <td style="text-align: center;">(0)</td> </tr> </table>						<b>Arm 4 Tsing Yi Road SB</b>		0	160	655	0	<0>	<125>	<550>	<0>	(5)	(90)	(415)	(0)																																																																						
<b>Arm 4 Tsing Yi Road SB</b>																																																																																									
0	160	655	0																																																																																						
<0>	<125>	<550>	<0>																																																																																						
(5)	(90)	(415)	(0)																																																																																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">875</td> <td style="text-align: center;">&lt;870&gt;</td> <td style="text-align: center;">(815)</td> </tr> </table>						875	<870>	(815)																																																																																	
875	<870>	(815)																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">70</td> <td style="text-align: center;">&lt;60&gt;</td> <td style="text-align: center;">(85)</td> </tr> <tr> <td style="text-align: center;">385</td> <td style="text-align: center;">&lt;375&gt;</td> <td style="text-align: center;">(295)</td> </tr> <tr> <td style="text-align: center;">225</td> <td style="text-align: center;">&lt;215&gt;</td> <td style="text-align: center;">(225)</td> </tr> <tr> <td style="text-align: center;">5</td> <td style="text-align: center;">&lt;5&gt;</td> <td style="text-align: center;">(5)</td> </tr> </table>						70	<60>	(85)	385	<375>	(295)	225	<215>	(225)	5	<5>	(5)																																																																								
70	<60>	(85)																																																																																							
385	<375>	(295)																																																																																							
225	<215>	(225)																																																																																							
5	<5>	(5)																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 3 Tsing Sha Highway</b></td> </tr> <tr> <td style="text-align: center;">1385</td> <td style="text-align: center;">&lt;1395&gt;</td> <td style="text-align: center;">(1490)</td> </tr> </table>						<b>Arm 3 Tsing Sha Highway</b>		1385	<1395>	(1490)																																																																															
<b>Arm 3 Tsing Sha Highway</b>																																																																																									
1385	<1395>	(1490)																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">280</td> <td style="text-align: center;">690</td> <td style="text-align: center;">85</td> <td style="text-align: center;">40</td> </tr> <tr> <td style="text-align: center;">&lt;275&gt;</td> <td style="text-align: center;">&lt;720&gt;</td> <td style="text-align: center;">&lt;85&gt;</td> <td style="text-align: center;">&lt;55&gt;</td> </tr> <tr> <td style="text-align: center;">(245)</td> <td style="text-align: center;">(725)</td> <td style="text-align: center;">(65)</td> <td style="text-align: center;">(45)</td> </tr> </table>						280	690	85	40	<275>	<720>	<85>	<55>	(245)	(725)	(65)	(45)																																																																								
280	690	85	40																																																																																						
<275>	<720>	<85>	<55>																																																																																						
(245)	(725)	(65)	(45)																																																																																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 2 Tsing Yi Road NB</b></td> </tr> <tr> <td style="text-align: center;">1050</td> <td style="text-align: center;">&lt;975&gt;</td> <td style="text-align: center;">(1495)</td> </tr> </table>						<b>Arm 2 Tsing Yi Road NB</b>		1050	<975>	(1495)																																																																															
<b>Arm 2 Tsing Yi Road NB</b>																																																																																									
1050	<975>	(1495)																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;"><b>Arm 1 Tsing Yi Hong Wan Road</b></td> </tr> <tr> <td style="text-align: center;">135</td> <td style="text-align: center;">&lt;135&gt;</td> <td style="text-align: center;">(180)</td> </tr> <tr> <td style="text-align: center;">435</td> <td style="text-align: center;">&lt;400&gt;</td> <td style="text-align: center;">(470)</td> </tr> <tr> <td style="text-align: center;">315</td> <td style="text-align: center;">&lt;310&gt;</td> <td style="text-align: center;">(330)</td> </tr> <tr> <td style="text-align: center;">65</td> <td style="text-align: center;">&lt;65&gt;</td> <td style="text-align: center;">(45)</td> </tr> </table>						<b>Arm 1 Tsing Yi Hong Wan Road</b>		135	<135>	(180)	435	<400>	(470)	315	<310>	(330)	65	<65>	(45)																																																																						
<b>Arm 1 Tsing Yi Hong Wan Road</b>																																																																																									
135	<135>	(180)																																																																																							
435	<400>	(470)																																																																																							
315	<310>	(330)																																																																																							
65	<65>	(45)																																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">AM</td> <td style="text-align: center;">[Logistic]</td> <td style="text-align: center;">(PM)</td> </tr> <tr> <td style="text-align: center;">[Logistic]</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">(PM)</td> <td></td> <td></td> </tr> </table>						AM	[Logistic]	(PM)	[Logistic]			(PM)																																																																													
AM	[Logistic]	(PM)																																																																																							
[Logistic]																																																																																									
(PM)																																																																																									
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2"><u>Input Parameters</u></td> <td style="text-align: center;">Arm 1</td> <td style="text-align: center;">Arm 2</td> <td style="text-align: center;">Arm 3</td> <td style="text-align: center;">Arm 4</td> </tr> <tr> <td>V</td> <td>= Approach half width (m)</td> <td style="text-align: center;">7.3</td> <td style="text-align: center;">7.1</td> <td style="text-align: center;">7.3</td> <td style="text-align: center;">7.3</td> </tr> <tr> <td>E</td> <td>= Entry width (m)</td> <td style="text-align: center;">13.5</td> <td style="text-align: center;">12</td> <td style="text-align: center;">9.5</td> <td style="text-align: center;">10</td> </tr> <tr> <td>L</td> <td>= Effective length of flare (m)</td> <td style="text-align: center;">30</td> <td style="text-align: center;">15</td> <td style="text-align: center;">30</td> <td style="text-align: center;">15</td> </tr> <tr> <td>R</td> <td>= Entry radius</td> <td style="text-align: center;">45</td> <td style="text-align: center;">97</td> <td style="text-align: center;">52</td> <td style="text-align: center;">34</td> </tr> <tr> <td>D</td> <td>= Inscribed circle diameter (m)</td> <td style="text-align: center;">100</td> <td style="text-align: center;">100</td> <td style="text-align: center;">100</td> <td style="text-align: center;">100</td> </tr> <tr> <td>A</td> <td>= Entry angle (degree)</td> <td style="text-align: center;">29</td> <td style="text-align: center;">32</td> <td style="text-align: center;">31</td> <td style="text-align: center;">46</td> </tr> <tr> <td>Q</td> <td>= Entry flow (pcu/hr)</td> <td style="text-align: center;">950</td> <td style="text-align: center;">1095</td> <td style="text-align: center;">685</td> <td style="text-align: center;">815</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">Logistic</td> <td style="text-align: center;">910</td> <td style="text-align: center;">1135</td> <td style="text-align: center;">655</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">PM</td> <td style="text-align: center;">1025</td> <td style="text-align: center;">1080</td> <td style="text-align: center;">610</td> </tr> <tr> <td>Qc</td> <td>= Circulating flow across entry (pcu/hr)</td> <td style="text-align: center;">1085</td> <td style="text-align: center;">1050</td> <td style="text-align: center;">1385</td> <td style="text-align: center;">875</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">Logistic</td> <td style="text-align: center;">950</td> <td style="text-align: center;">975</td> <td style="text-align: center;">1395</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">PM</td> <td style="text-align: center;">785</td> <td style="text-align: center;">1495</td> <td style="text-align: center;">1490</td> </tr> </table>						<u>Input Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4	V	= Approach half width (m)	7.3	7.1	7.3	7.3	E	= Entry width (m)	13.5	12	9.5	10	L	= Effective length of flare (m)	30	15	30	15	R	= Entry radius	45	97	52	34	D	= Inscribed circle diameter (m)	100	100	100	100	A	= Entry angle (degree)	29	32	31	46	Q	= Entry flow (pcu/hr)	950	1095	685	815			Logistic	910	1135	655			PM	1025	1080	610	Qc	= Circulating flow across entry (pcu/hr)	1085	1050	1385	875			Logistic	950	975	1395			PM	785	1495	1490						
<u>Input Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4																																																																																				
V	= Approach half width (m)	7.3	7.1	7.3	7.3																																																																																				
E	= Entry width (m)	13.5	12	9.5	10																																																																																				
L	= Effective length of flare (m)	30	15	30	15																																																																																				
R	= Entry radius	45	97	52	34																																																																																				
D	= Inscribed circle diameter (m)	100	100	100	100																																																																																				
A	= Entry angle (degree)	29	32	31	46																																																																																				
Q	= Entry flow (pcu/hr)	950	1095	685	815																																																																																				
		Logistic	910	1135	655																																																																																				
		PM	1025	1080	610																																																																																				
Qc	= Circulating flow across entry (pcu/hr)	1085	1050	1385	875																																																																																				
		Logistic	950	975	1395																																																																																				
		PM	785	1495	1490																																																																																				
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2"><u>Output Parameters</u></td> <td style="text-align: center;">Arm 1</td> <td style="text-align: center;">Arm 2</td> <td style="text-align: center;">Arm 3</td> <td style="text-align: center;">Arm 4</td> </tr> <tr> <td>S</td> <td>= Sharpness of flare = 1.6*(E-V)/L</td> <td style="text-align: center;">0.33</td> <td style="text-align: center;">0.52</td> <td style="text-align: center;">0.12</td> <td style="text-align: center;">0.29</td> </tr> <tr> <td>K</td> <td>= 1-0.00347*(A-30)-0.978*(1/R-0.05)</td> <td style="text-align: center;">1.03</td> <td style="text-align: center;">1.03</td> <td style="text-align: center;">1.03</td> <td style="text-align: center;">0.96</td> </tr> <tr> <td>X2</td> <td>= V+((E-V)/(1+2*S))</td> <td style="text-align: center;">11.03</td> <td style="text-align: center;">9.50</td> <td style="text-align: center;">9.08</td> <td style="text-align: center;">9.01</td> </tr> <tr> <td>M</td> <td>= Exp((D-60)/10)</td> <td style="text-align: center;">54.60</td> <td style="text-align: center;">54.60</td> <td style="text-align: center;">54.60</td> <td style="text-align: center;">54.60</td> </tr> <tr> <td>F</td> <td>= 303*X2</td> <td style="text-align: center;">3343</td> <td style="text-align: center;">2877</td> <td style="text-align: center;">2752</td> <td style="text-align: center;">2731</td> </tr> <tr> <td>Td</td> <td>= 1+(0.5/(1+M))</td> <td style="text-align: center;">1.01</td> <td style="text-align: center;">1.01</td> <td style="text-align: center;">1.01</td> <td style="text-align: center;">1.01</td> </tr> <tr> <td>Fc</td> <td>= 0.21*Td*(1+0.2*X2)</td> <td style="text-align: center;">0.68</td> <td style="text-align: center;">0.61</td> <td style="text-align: center;">0.60</td> <td style="text-align: center;">0.59</td> </tr> <tr> <td>Qe</td> <td>= Capacity = K*(F-Fc*Qc)</td> <td style="text-align: center;">2685</td> <td style="text-align: center;">2303</td> <td style="text-align: center;">1977</td> <td style="text-align: center;">2133</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">Logistic</td> <td style="text-align: center;">2780</td> <td style="text-align: center;">2351</td> <td style="text-align: center;">1970</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">PM</td> <td style="text-align: center;">2895</td> <td style="text-align: center;">2021</td> <td style="text-align: center;">1912</td> </tr> <tr> <td>DFC</td> <td>= Entry Flow/Capacity = Q/Qe</td> <td style="text-align: center;">0.35</td> <td style="text-align: center;">0.48</td> <td style="text-align: center;">0.35</td> <td style="text-align: center;">0.38</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">Logistic</td> <td style="text-align: center;">0.33</td> <td style="text-align: center;">0.48</td> <td style="text-align: center;">0.33</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">PM</td> <td style="text-align: center;">0.35</td> <td style="text-align: center;">0.53</td> <td style="text-align: center;">0.24</td> </tr> </table>						<u>Output Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4	S	= Sharpness of flare = 1.6*(E-V)/L	0.33	0.52	0.12	0.29	K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	1.03	1.03	1.03	0.96	X2	= V+((E-V)/(1+2*S))	11.03	9.50	9.08	9.01	M	= Exp((D-60)/10)	54.60	54.60	54.60	54.60	F	= 303*X2	3343	2877	2752	2731	Td	= 1+(0.5/(1+M))	1.01	1.01	1.01	1.01	Fc	= 0.21*Td*(1+0.2*X2)	0.68	0.61	0.60	0.59	Qe	= Capacity = K*(F-Fc*Qc)	2685	2303	1977	2133			Logistic	2780	2351	1970			PM	2895	2021	1912	DFC	= Entry Flow/Capacity = Q/Qe	0.35	0.48	0.35	0.38			Logistic	0.33	0.48	0.33			PM	0.35	0.53	0.24
<u>Output Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4																																																																																				
S	= Sharpness of flare = 1.6*(E-V)/L	0.33	0.52	0.12	0.29																																																																																				
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	1.03	1.03	1.03	0.96																																																																																				
X2	= V+((E-V)/(1+2*S))	11.03	9.50	9.08	9.01																																																																																				
M	= Exp((D-60)/10)	54.60	54.60	54.60	54.60																																																																																				
F	= 303*X2	3343	2877	2752	2731																																																																																				
Td	= 1+(0.5/(1+M))	1.01	1.01	1.01	1.01																																																																																				
Fc	= 0.21*Td*(1+0.2*X2)	0.68	0.61	0.60	0.59																																																																																				
Qe	= Capacity = K*(F-Fc*Qc)	2685	2303	1977	2133																																																																																				
		Logistic	2780	2351	1970																																																																																				
		PM	2895	2021	1912																																																																																				
DFC	= Entry Flow/Capacity = Q/Qe	0.35	0.48	0.35	0.38																																																																																				
		Logistic	0.33	0.48	0.33																																																																																				
		PM	0.35	0.53	0.24																																																																																				
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td><b>DFC of Critical Approach</b></td> <td>=</td> <td style="text-align: center;"><b>AM</b></td> <td style="text-align: center;"><b>0.48</b></td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;"><b>Logistic</b></td> <td style="text-align: center;"><b>0.48</b></td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;"><b>PM</b></td> <td style="text-align: center;"><b>0.53</b></td> </tr> </table>						<b>DFC of Critical Approach</b>	=	<b>AM</b>	<b>0.48</b>			<b>Logistic</b>	<b>0.48</b>			<b>PM</b>	<b>0.53</b>																																																																								
<b>DFC of Critical Approach</b>	=	<b>AM</b>	<b>0.48</b>																																																																																						
		<b>Logistic</b>	<b>0.48</b>																																																																																						
		<b>PM</b>	<b>0.53</b>																																																																																						
CTA Consultants Ltd.																																																																																									

# Roundabout Junction Calculation

Junction : (RA3) Tsing Yi Hong Wan Road Job No.: 24001HK  
 Scenario : 2029 Design Traffic Flow

**Arm 4 Tsing Yi Hong Wan Road SB**

190		900	
<165>		<735>	
(185)		(755)	

**Arm 1**

1115	<925>	(980)	

**Arm 3**

25	<25>	(40)	

**Arm 2 Tsing Yi Hong Wan Road NB**

940	<945>	(1160)	

190	<165>	(940)	

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

**Input Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4
V	=	Approach half width (m)	7		7.3
E	=	Entry width (m)	14		12
L	=	Effective length of flare (m)	20		2
R	=	Entry radius	65		75
D	=	Inscribed circle diameter (m)	68		68
A	=	Entry angle (degree)	53		46
Q	=	Entry flow (pcu/hr)	750		1090
		AM	750		1090
		Logistic	780		900
		PM	975		940
Qc	=	Circulating flow across entry (pcu/hr)	190		25
		AM	190		25
		Logistic	165		25
		PM	940		40

**Output Parameters**

		Arm 1	Arm 2	Arm 3	Arm 4
S	=	Sharpness of flare = $1.6*(E-V)/L$	0.56		3.76
K	=	$1-0.00347*(A-30)-0.978*(1/R-0.05)$	0.95		0.98
X2	=	$V+((E-V)/(1+2*S))$	10.30		7.85
M	=	$Exp((D-60)/10)$	2.23		2.23
F	=	$303*X2$	3121		2379
Td	=	$1+(0.5/(1+M))$	1.16		1.16
Fc	=	$0.21*Td*(1+0.2*X2)$	0.74		0.62
Qe	=	Capacity = $K*(F-Fc*Qc)$	2843		2317
		AM	2843		2317
		Logistic	2861		2317
		PM	2312		2308
DFC	=	Entry Flow/Capacity = $Q/Qe$	0.26		0.47
		AM	0.26		0.47
		Logistic	0.27		0.39
		PM	0.42		0.41

**DFC of Critical Approach**

	=	AM	0.47
		Logistic	0.39
		PM	0.42

# Roundabout Junction Calculation


Junction : <u>(RA4) Tsing Yi Hong Wan Road / Tsing Ko Road</u>		Job No.: <u>24001HK</u>																																																																																					
Scenario : <u>2029 Design Traffic Flow</u>																																																																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td colspan="4" style="text-align: center;"><b>Arm 4 Tsing Yi Hong Wan Road SB</b></td> </tr> <tr> <td>475</td> <td></td> <td>255</td> <td>190</td> </tr> <tr> <td>&lt;385&gt;</td> <td></td> <td>&lt;240&gt;</td> <td>&lt;165&gt;</td> </tr> <tr> <td>(365)</td> <td></td> <td>(210)</td> <td>(265)</td> </tr> <tr> <td colspan="4" style="text-align: center;"><b>Arm 1 Tsing Yi Hong Wan Road</b></td> </tr> <tr> <td>745</td> <td>&lt;1160&gt;</td> <td colspan="2">(1125)</td> </tr> <tr> <td colspan="4" style="text-align: center;"><b>Arm 3 Tsing Ko Road</b></td> </tr> <tr> <td>330</td> <td>&lt;165&gt;</td> <td colspan="2">(265)</td> </tr> <tr> <td>10</td> <td>&lt;5&gt;</td> <td colspan="2">(20)</td> </tr> <tr> <td>5</td> <td>&lt;385&gt;</td> <td colspan="2">(365)</td> </tr> <tr> <td colspan="4" style="text-align: center;"><b>Arm 2 Tsing Yi Hong Wan Road NB</b></td> </tr> <tr> <td>590</td> <td>&lt;675&gt;</td> <td colspan="2">(695)</td> </tr> <tr> <td>25</td> <td>115</td> <td></td> <td>0</td> </tr> <tr> <td>&lt;25&gt;</td> <td>&lt;145&gt;</td> <td></td> <td>&lt;145&gt;</td> </tr> <tr> <td>(20)</td> <td>(165)</td> <td></td> <td>(165)</td> </tr> </table>				<b>Arm 4 Tsing Yi Hong Wan Road SB</b>				475		255	190	<385>		<240>	<165>	(365)		(210)	(265)	<b>Arm 1 Tsing Yi Hong Wan Road</b>				745	<1160>	(1125)		<b>Arm 3 Tsing Ko Road</b>				330	<165>	(265)		10	<5>	(20)		5	<385>	(365)		<b>Arm 2 Tsing Yi Hong Wan Road NB</b>				590	<675>	(695)		25	115		0	<25>	<145>		<145>	(20)	(165)		(165)																								
<b>Arm 4 Tsing Yi Hong Wan Road SB</b>																																																																																							
475		255	190																																																																																				
<385>		<240>	<165>																																																																																				
(365)		(210)	(265)																																																																																				
<b>Arm 1 Tsing Yi Hong Wan Road</b>																																																																																							
745	<1160>	(1125)																																																																																					
<b>Arm 3 Tsing Ko Road</b>																																																																																							
330	<165>	(265)																																																																																					
10	<5>	(20)																																																																																					
5	<385>	(365)																																																																																					
<b>Arm 2 Tsing Yi Hong Wan Road NB</b>																																																																																							
590	<675>	(695)																																																																																					
25	115		0																																																																																				
<25>	<145>		<145>																																																																																				
(20)	(165)		(165)																																																																																				
<table border="1" style="width:50%; border-collapse: collapse;"> <tr> <td>AM</td> <td>[Logistic]</td> <td>(PM)</td> </tr> <tr> <td>[Logistic]</td> <td></td> <td></td> </tr> <tr> <td>(PM)</td> <td></td> <td></td> </tr> </table>				AM	[Logistic]	(PM)	[Logistic]			(PM)																																																																													
AM	[Logistic]	(PM)																																																																																					
[Logistic]																																																																																							
(PM)																																																																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: left;"><u>Input Parameters</u></th> <th>Arm 1</th> <th>Arm 2</th> <th>Arm 3</th> <th>Arm 4</th> </tr> </thead> <tbody> <tr> <td>V</td> <td>= Approach half width (m)</td> <td></td> <td>6.7</td> <td>6.3</td> <td>7.3</td> </tr> <tr> <td>E</td> <td>= Entry width (m)</td> <td></td> <td>13.5</td> <td>12.5</td> <td>15</td> </tr> <tr> <td>L</td> <td>= Effective length of flare (m)</td> <td></td> <td>18</td> <td>30</td> <td>30</td> </tr> <tr> <td>R</td> <td>= Entry radius</td> <td></td> <td>47</td> <td>100</td> <td>75</td> </tr> <tr> <td>D</td> <td>= Inscribed circle diameter (m)</td> <td></td> <td>68</td> <td>68</td> <td>68</td> </tr> <tr> <td>A</td> <td>= Entry angle (degree)</td> <td></td> <td>41</td> <td>22</td> <td>46</td> </tr> <tr> <td>Q</td> <td>= Entry flow (pcu/hr)</td> <td>AM</td> <td>140</td> <td>345</td> <td>920</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td>315</td> <td>555</td> <td>790</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td>350</td> <td>650</td> <td>840</td> </tr> <tr> <td>Qc</td> <td>= Circulating flow across entry (pcu/hr)</td> <td>AM</td> <td>480</td> <td>590</td> <td>15</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td>770</td> <td>675</td> <td>535</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td>940</td> <td>695</td> <td>550</td> </tr> </tbody> </table>				<u>Input Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4	V	= Approach half width (m)		6.7	6.3	7.3	E	= Entry width (m)		13.5	12.5	15	L	= Effective length of flare (m)		18	30	30	R	= Entry radius		47	100	75	D	= Inscribed circle diameter (m)		68	68	68	A	= Entry angle (degree)		41	22	46	Q	= Entry flow (pcu/hr)	AM	140	345	920			Logistic	315	555	790			PM	350	650	840	Qc	= Circulating flow across entry (pcu/hr)	AM	480	590	15			Logistic	770	675	535			PM	940	695	550						
<u>Input Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4																																																																																		
V	= Approach half width (m)		6.7	6.3	7.3																																																																																		
E	= Entry width (m)		13.5	12.5	15																																																																																		
L	= Effective length of flare (m)		18	30	30																																																																																		
R	= Entry radius		47	100	75																																																																																		
D	= Inscribed circle diameter (m)		68	68	68																																																																																		
A	= Entry angle (degree)		41	22	46																																																																																		
Q	= Entry flow (pcu/hr)	AM	140	345	920																																																																																		
		Logistic	315	555	790																																																																																		
		PM	350	650	840																																																																																		
Qc	= Circulating flow across entry (pcu/hr)	AM	480	590	15																																																																																		
		Logistic	770	675	535																																																																																		
		PM	940	695	550																																																																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: left;"><u>Output Parameters</u></th> <th>Arm 1</th> <th>Arm 2</th> <th>Arm 3</th> <th>Arm 4</th> </tr> </thead> <tbody> <tr> <td>S</td> <td>= Sharpness of flare = <math>1.6*(E-V)/L</math></td> <td></td> <td>0.60</td> <td>0.33</td> <td>0.41</td> </tr> <tr> <td>K</td> <td>= <math>1-0.00347*(A-30)-0.978*(1/R-0.05)</math></td> <td></td> <td>0.99</td> <td>1.07</td> <td>0.98</td> </tr> <tr> <td>X2</td> <td>= <math>V+((E-V)/(1+2*S))</math></td> <td></td> <td>9.78</td> <td>10.03</td> <td>11.53</td> </tr> <tr> <td>M</td> <td>= <math>Exp((D-60)/10)</math></td> <td></td> <td>2.23</td> <td>2.23</td> <td>2.23</td> </tr> <tr> <td>F</td> <td>= <math>303*X2</math></td> <td></td> <td>2963</td> <td>3040</td> <td>3493</td> </tr> <tr> <td>Td</td> <td>= <math>1+(0.5/(1+M))</math></td> <td></td> <td>1.16</td> <td>1.16</td> <td>1.16</td> </tr> <tr> <td>Fc</td> <td>= <math>0.21*Td*(1+0.2*X2)</math></td> <td></td> <td>0.72</td> <td>0.73</td> <td>0.80</td> </tr> <tr> <td>Qe</td> <td>= Capacity = <math>K*(F-Fc*Qc)</math></td> <td>AM</td> <td>2592</td> <td>2784</td> <td>3412</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td>2387</td> <td>2718</td> <td>3004</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td>2266</td> <td>2702</td> <td>2992</td> </tr> <tr> <td>DFC</td> <td>= Entry Flow/Capacity = <math>Q/Qe</math></td> <td>AM</td> <td>0.05</td> <td>0.12</td> <td>0.27</td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td>0.13</td> <td>0.20</td> <td>0.26</td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td>0.15</td> <td>0.24</td> <td>0.28</td> </tr> </tbody> </table>				<u>Output Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4	S	= Sharpness of flare = $1.6*(E-V)/L$		0.60	0.33	0.41	K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$		0.99	1.07	0.98	X2	= $V+((E-V)/(1+2*S))$		9.78	10.03	11.53	M	= $Exp((D-60)/10)$		2.23	2.23	2.23	F	= $303*X2$		2963	3040	3493	Td	= $1+(0.5/(1+M))$		1.16	1.16	1.16	Fc	= $0.21*Td*(1+0.2*X2)$		0.72	0.73	0.80	Qe	= Capacity = $K*(F-Fc*Qc)$	AM	2592	2784	3412			Logistic	2387	2718	3004			PM	2266	2702	2992	DFC	= Entry Flow/Capacity = $Q/Qe$	AM	0.05	0.12	0.27			Logistic	0.13	0.20	0.26			PM	0.15	0.24	0.28
<u>Output Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4																																																																																		
S	= Sharpness of flare = $1.6*(E-V)/L$		0.60	0.33	0.41																																																																																		
K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$		0.99	1.07	0.98																																																																																		
X2	= $V+((E-V)/(1+2*S))$		9.78	10.03	11.53																																																																																		
M	= $Exp((D-60)/10)$		2.23	2.23	2.23																																																																																		
F	= $303*X2$		2963	3040	3493																																																																																		
Td	= $1+(0.5/(1+M))$		1.16	1.16	1.16																																																																																		
Fc	= $0.21*Td*(1+0.2*X2)$		0.72	0.73	0.80																																																																																		
Qe	= Capacity = $K*(F-Fc*Qc)$	AM	2592	2784	3412																																																																																		
		Logistic	2387	2718	3004																																																																																		
		PM	2266	2702	2992																																																																																		
DFC	= Entry Flow/Capacity = $Q/Qe$	AM	0.05	0.12	0.27																																																																																		
		Logistic	0.13	0.20	0.26																																																																																		
		PM	0.15	0.24	0.28																																																																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td><b>DFC of Critical Approach</b></td> <td>=</td> <td>AM</td> <td><b>0.27</b></td> </tr> <tr> <td></td> <td></td> <td>Logistic</td> <td><b>0.26</b></td> </tr> <tr> <td></td> <td></td> <td>PM</td> <td><b>0.28</b></td> </tr> </table>				<b>DFC of Critical Approach</b>	=	AM	<b>0.27</b>			Logistic	<b>0.26</b>			PM	<b>0.28</b>																																																																								
<b>DFC of Critical Approach</b>	=	AM	<b>0.27</b>																																																																																				
		Logistic	<b>0.26</b>																																																																																				
		PM	<b>0.28</b>																																																																																				



# Roundabout Junction Calculation

Junction : (RA5) Tam Kon Shan Interchange Job No.: 24001HK

Scenario : 2029 Design Traffic Flow



Input Parameters			Arm 1	Arm 2	Arm 3	Arm 4	Arm 5
V	=	Approach half width (m)	7	7.3	5.5	7.3	7
E	=	Entry width (m)	9	13.5	7.5	13.5	11
L	=	Effective length of flare (m)	9	9	11	9	10
R	=	Entry radius	100	45	45	25	45
D	=	Inscribed circle diameter (m)	100	100	100	100	100
A	=	Entry angle (degree)	30	25	25	30	45
Q	=	Entry flow (pcu/hr)					
		AM	715	1715	405	1125	470
		Logistic	625	1755	305	1075	420
		PM	650	1925	375	1110	490
Qc	=	Circulating flow across entry (pcu/hr)					
		AM	1300	1310	2525	2355	2080
		Logistic	1195	1130	2440	2205	2015
		PM	1355	1225	2710	2505	2145

Output Parameters			Arm 1	Arm 2	Arm 3	Arm 4	Arm 5
S	=	Sharpness of flare = 1.6*(E-V)/L	0.36	1.10	0.29	1.10	0.64
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	1.04	1.04	1.04	1.01	0.98
X2	=	V+((E-V)/(1+2*S))	8.17	9.23	6.76	9.23	8.75
M	=	Exp((D-60)/10)	54.60	54.60	54.60	54.60	54.60
F	=	303*X2	2475	2798	2050	2798	2653
Td	=	1+(0.5/(1+M))	1.01	1.01	1.01	1.01	1.01
Fc	=	0.21*Td*(1+0.2*X2)	0.56	0.60	0.50	0.60	0.58
Qe	=	Capacity = K*(F-Fc*Qc)					
		AM	1818	2097	826	1391	1404
		Logistic	1879	2211	870	1482	1441
		PM	1786	2151	730	1300	1367
DFC	=	Entry Flow/Capacity = Q/Qe					
		AM	0.39	0.82	0.49	0.81	0.33
		Logistic	0.33	0.79	0.35	0.73	0.29
		PM	0.36	0.89	0.51	0.85	0.36

DFC of Critical Approach = AM 0.82  
Logistic 0.79  
PM 0.89

# Roundabout Junction Calculation

Junction : (RA6) Tsing King Road / Fung Shue Wo Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

1200	<1020>	(950)
------	--------	-------

15	<20>	(5)
45	<25>	(65)
530	<440>	(495)
0	<0>	(0)

25	5	600	100
<25>	<5>	<400>	<80>
(25)	(15)	(450)	(65)

1670	<1315>	(1275)
------	--------	--------

0	<0>	(0)
25	<30>	(25)
80	<55>	(65)
220	<170>	(210)

135	<115>	(580)
-----	-------	-------

395	305	115	510
<340>	<240>	<110>	<445>
(455)	(310)	(100)	(290)

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4	
V	= Approach half width (m)	6.7	7.3	7.3	6.9	
E	= Entry width (m)	9.7	10	9.2	8.9	
L	= Effective length of flare (m)	16	20	14	16	
R	= Entry radius	55	71	60	62	
D	= Inscribed circle diameter (m)	100	100	100	100	
A	= Entry angle (degree)	36	30	18	25	
Q	= Entry flow (pcu/hr)	325	1325	590	730	
		Logistic	255	1135	485	510
		PM	300	1155	565	555
Qc	= Circulating flow across entry (pcu/hr)	1670	135	980	1200	
		Logistic	1315	115	850	1020
		PM	1275	580	750	950

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4	
S	= Sharpness of flare = 1.6*(E-V)/L	0.30	0.22	0.22	0.20	
K	= 1-0.00347*(A-30)-0.978*(1/R-0.05)	1.01	1.04	1.07	1.05	
X2	= V+((E-V)/(1+2*S))	8.58	9.19	8.62	8.33	
M	= Exp((D-60)/10)	54.60	54.60	54.60	54.60	
F	= 303*X2	2598	2783	2613	2524	
Td	= 1+(0.5/(1+M))	1.01	1.01	1.01	1.01	
Fc	= 0.21*Td*(1+0.2*X2)	0.58	0.60	0.58	0.56	
Qe	= Capacity = K*(F-Fc*Qc)	1654	2797	2199	1939	
		Logistic	1861	2809	2280	2046
		PM	1884	2520	2342	2087
DFC	= Entry Flow/Capacity = Q/Qe	0.20	0.47	0.27	0.38	
		Logistic	0.14	0.40	0.21	0.25
		PM	0.16	0.46	0.24	0.27

DFC of Critical Approach	=	AM	0.47
		Logistic	0.40
		PM	0.46

# Roundabout Junction Calculation

Junction : <u>(RA7) Tsing Yi Hong Wan Road / Tsing Sheung Road</u>		Job No.: <u>24001HK</u>																
Scenario : <u>2029 Design Traffic Flow</u>																		
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2"></th> <th>AM</th> <th>[Logistic]</th> <th>(PM)</th> </tr> </thead> <tbody> <tr> <td colspan="2"></td> <td>[Logistic]</td> <td></td> <td></td> </tr> <tr> <td colspan="2"></td> <td>(PM)</td> <td></td> <td></td> </tr> </tbody> </table>						AM	[Logistic]	(PM)			[Logistic]					(PM)		
		AM	[Logistic]	(PM)														
		[Logistic]																
		(PM)																
<u>Input Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4													
V	= Approach half width (m)		5.2	3	6.7													
E	= Entry width (m)		9	8.4	12													
L	= Effective length of flare (m)		25	15	23													
R	= Entry radius		63	55	11.6													
D	= Inscribed circle diameter (m)		53	53	53													
A	= Entry angle (degree)		33	48	38													
Q	= Entry flow (pcu/hr)	AM	65	35	210													
		Logistic	30	30	245													
		PM	55	80	290													
Qc	= Circulating flow across entry (pcu/hr)	AM	75	140	70													
		Logistic	125	150	35													
		PM	275	170	65													
<u>Output Parameters</u>		Arm 1	Arm 2	Arm 3	Arm 4													
S	= Sharpness of flare = $1.6*(E-V)/L$		0.24	0.58	0.37													
K	= $1-0.00347*(A-30)-0.978*(1/R-0.05)$		1.02	0.97	0.94													
X2	= $V+((E-V)/(1+2*S))$		7.76	5.51	9.75													
M	= $Exp((D-60)/10)$		0.50	0.50	0.50													
F	= $303*X2$		2350	1669	2954													
Td	= $1+(0.5/(1+M))$		1.33	1.33	1.33													
Fc	= $0.21*Td*(1+0.2*X2)$		0.71	0.59	0.83													
Qe	= Capacity = $K*(F-Fc*Qc)$	AM	2349	1537	2714													
		Logistic	2313	1531	2741													
		PM	2203	1520	2717													
DFC	= Entry Flow/Capacity = $Q/Qe$	AM	0.03	0.02	0.08													
		Logistic	0.01	0.02	0.09													
		PM	0.02	0.05	0.11													
<b>DFC of Critical Approach</b>		<b>AM</b>	<b>0.08</b>															
		<b>Logistic</b>	<b>0.09</b>															
		<b>PM</b>	<b>0.11</b>															

# Roundabout Junction Calculation

Junction : <u>(RA8) Tsing Yi Road / Ching Hong Road</u>		Job No.: <u>24001HK</u>																	
Scenario : <u>2029 Design Traffic Flow</u>																			
<table border="1" style="margin: auto;"> <tr> <td colspan="4"><b>Arm 4 Tsing Yi Road SB</b></td> </tr> <tr> <td>230</td><td>410</td><td>375</td><td></td> </tr> <tr> <td>&lt;180&gt;</td><td>&lt;505&gt;</td><td>&lt;325&gt;</td><td></td> </tr> <tr> <td>(220)</td><td>(475)</td><td>(315)</td><td></td> </tr> </table>				<b>Arm 4 Tsing Yi Road SB</b>				230	410	375		<180>	<505>	<325>		(220)	(475)	(315)	
<b>Arm 4 Tsing Yi Road SB</b>																			
230	410	375																	
<180>	<505>	<325>																	
(220)	(475)	(315)																	
<table border="1" style="margin: auto;"> <tr> <td>465</td><td>&lt;485&gt;</td><td>(485)</td><td></td> </tr> </table>				465	<485>	(485)													
465	<485>	(485)																	
<table border="1" style="margin: auto;"> <tr> <td>685</td><td>&lt;635&gt;</td><td>(630)</td><td></td> </tr> <tr> <td>75</td><td>&lt;105&gt;</td><td>(115)</td><td></td> </tr> <tr> <td>65</td><td>&lt;90&gt;</td><td>(70)</td><td></td> </tr> </table>				685	<635>	(630)		75	<105>	(115)		65	<90>	(70)					
685	<635>	(630)																	
75	<105>	(115)																	
65	<90>	(70)																	
<table border="1" style="margin: auto;"> <tr> <td colspan="4"><b>Arm 3 Ching Hong Road</b></td> </tr> <tr> <td>555</td><td>&lt;470&gt;</td><td>(520)</td><td></td> </tr> </table>				<b>Arm 3 Ching Hong Road</b>				555	<470>	(520)									
<b>Arm 3 Ching Hong Road</b>																			
555	<470>	(520)																	
<table border="1" style="margin: auto;"> <tr> <td>85</td><td></td><td>325</td><td>0</td> </tr> <tr> <td>&lt;120&gt;</td><td></td><td>&lt;265&gt;</td><td>&lt;25&gt;</td> </tr> <tr> <td>(105)</td><td></td><td>(300)</td><td>(0)</td> </tr> </table>				85		325	0	<120>		<265>	<25>	(105)		(300)	(0)				
85		325	0																
<120>		<265>	<25>																
(105)		(300)	(0)																
<table border="1" style="margin: auto;"> <tr> <td colspan="4"><b>Arm 2 Tsing Yi Road NB</b></td> </tr> <tr> <td>705</td><td>&lt;775&gt;</td><td>(1080)</td><td></td> </tr> </table>				<b>Arm 2 Tsing Yi Road NB</b>				705	<775>	(1080)									
<b>Arm 2 Tsing Yi Road NB</b>																			
705	<775>	(1080)																	
<table border="1" style="margin: auto;"> <tr> <td>AM</td><td>[Logistic]</td><td>(PM)</td><td></td> </tr> <tr> <td>[Logistic]</td><td></td><td></td><td></td> </tr> <tr> <td>(PM)</td><td></td><td></td><td></td> </tr> </table>				AM	[Logistic]	(PM)		[Logistic]				(PM)							
AM	[Logistic]	(PM)																	
[Logistic]																			
(PM)																			
<b>Input Parameters</b>		Arm 1	Arm 2	Arm 3	Arm 4														
V	=	Approach half width (m)	4.5	7.3	7														
E	=	Entry width (m)	9	8.5	8.5														
L	=	Effective length of flare (m)	25	4	16														
R	=	Entry radius	24.5	30	100														
D	=	Inscribed circle diameter (m)	30	30	30														
A	=	Entry angle (degree)	44	40	27														
Q	=	Entry flow (pcu/hr)	AM	410	825	1015													
			Logistic	410	830	1010													
			PM	405	815	1010													
Qc	=	Circulating flow across entry (pcu/hr)	AM	705	555	465													
			Logistic	775	470	485													
			PM	1080	520	485													
<b>Output Parameters</b>		Arm 1	Arm 2	Arm 3	Arm 4														
S	=	Sharpness of flare = 1.6*(E-V)/L	0.29	0.48	0.15														
K	=	1-0.00347*(A-30)-0.978*(1/R-0.05)	0.96	0.98	1.05														
X2	=	V+((E-V)/(1+2*S))	7.36	7.91	8.15														
M	=	Exp((D-60)/10)	0.05	0.05	0.05														
F	=	303*X2	2229	2397	2471														
Td	=	1+(0.5/(1+M))	1.48	1.48	1.48														
Fc	=	0.21*Td*(1+0.2*X2)	0.77	0.80	0.82														
Qe	=	Capacity = K*(F-Fc*Qc)	AM	1622	1917	2195													
			Logistic	1570	1984	2178													
			PM	1346	1945	2178													
DFC	=	Entry Flow/Capacity = Q/Qe	AM	0.25	0.43	0.46													
			Logistic	0.26	0.42	0.46													
			PM	0.30	0.42	0.46													
<b>DFC of Critical Approach</b>		=	AM	0.46															
			Logistic	0.46															
			PM	0.46															

# Roundabout Junction Calculation

Junction : (RA9) Tam Kon Shan Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

**Arm 4 Development Access**

0	0	0
<0>	<0>	<5>
(0)	(0)	(5)

**Arm 1 Tam Kon Shan Road**

15	<5>	(15)
0	<5>	(0)
25	<35>	(10)

**Arm 3 Tam Kon Shan Road**

0	<0>	(0)
45	<60>	(40)
5	<0>	(5)

**Arm 2 Tsing Yi North Coastal Road**

25	10	60	
<30>	<0>	<90>	
(40)	(10)	(70)	

**Approach Data**

125	<155>	(130)
-----	-------	-------

5	<0>	(5)
---	-----	-----

85	<100>	(95)
----	-------	------

45	<45>	(30)
----	------	------

**Time Periods**

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

**Input Parameters**

	Arm 1	Arm 2	Arm 3	Arm 4
V = Approach half width (m)	3.3	4	3.4	4.2
E = Entry width (m)	6.7	4.9	5.8	5.4
L = Effective length of flare (m)	10	10	10	10
R = Entry radius	32	97	52	34
D = Inscribed circle diameter (m)	30	30	30	30
A = Entry angle (degree)	34	32	31	46
Q = Entry flow (pcu/hr)	AM: 40, Logistic: 45, PM: 25	95, 120, 120	50, 60, 45	0, 5, 5
Qc = Circulating flow across entry (pcu/hr)	AM: 5, Logistic: 0, PM: 5	45, 45, 30	85, 100, 95	125, 155, 130

**Output Parameters**

	Arm 1	Arm 2	Arm 3	Arm 4
S = Sharpness of flare = 1.6*(E-V)/L	0.54	0.14	0.38	0.19
K = 1-0.00347*(A-30)-0.978*(1/R-0.05)	1.00	1.03	1.03	0.96
X2 = V+((E-V)/(1+2*S))	4.93	4.70	4.76	5.07
M = Exp((D-60)/10)	0.05	0.05	0.05	0.05
F = 303*X2	1493	1424	1442	1535
Td = 1+(0.5/(1+M))	1.48	1.48	1.48	1.48
Fc = 0.21*Td*(1+0.2*X2)	0.62	0.60	0.61	0.62
Qe = Capacity = K*(F-Fc*Qc)	AM: 1497, Logistic: 1500, PM: 1497	1441, 1441, 1450	1427, 1418, 1421	1406, 1388, 1403
DFC = Entry Flow/Capacity = Q/Qe	AM: 0.03, Logistic: 0.03, PM: 0.02	0.07, 0.08, 0.08	0.04, 0.04, 0.03	0.00, 0.00, 0.00

**DFC of Critical Approach =**

AM	0.07
Logistic	0.08
PM	0.08

# Roundabout Junction Calculation

Junction : (RA10) Tsing Sheung Road / Tsing Ko Road Job No.: 24001HK

Scenario : 2029 Design Traffic Flow

**Arm 4 Tsing Ko Road**

10	205		5
<45>	<170>		<20>
(5)	(145)		(15)

**Arm 1 Tsing Sheung Road WB**

5	<0>	(15)
55	<60>	(90)
120	<120>	(165)

**Arm 3 Tsing Sheung Road EB**

330	<315>	(240)
90	<65>	(40)
25	<40>	(30)

**Arm 2**

70	<105>	(110)
----	-------	-------

**Approach Data**

120	<105>	(85)
-----	-------	------

240	<255>	(180)
-----	-------	-------

395	<395>	(420)
-----	-------	-------

AM	[Logistic]	(PM)
[Logistic]		
(PM)		

Input Parameters		Arm 1	Arm 2	Arm 3	Arm 4
V	=	Approach half width (m)	6.6	5.6	6.4
E	=	Entry width (m)	12.9	5.1	11.6
L	=	Effective length of flare (m)	18	30	30
R	=	Entry radius	47	67.3	75
D	=	Inscribed circle diameter (m)	50	50	50
A	=	Entry angle (degree)	41	22	46
Q	=	Entry flow (pcu/hr)	AM 180	445	220
			Logistic 180	420	235
			PM 270	310	165
Qc	=	Circulating flow across entry (pcu/hr)	AM 240	70	120
			Logistic 255	105	105
			PM 180	110	85

Output Parameters		Arm 1	Arm 2	Arm 3	Arm 4
S	=	Sharpness of flare = $1.6*(E-V)/L$	0.56	-0.03	0.28
K	=	$1-0.00347*(A-30)-0.978*(1/R-0.05)$	0.99	1.06	0.98
X2	=	$V+((E-V)/(1+2*S))$	9.57	5.07	9.74
M	=	$Exp((D-60)/10)$	0.37	0.37	0.37
F	=	$303*X2$	2900	1537	2953
Td	=	$1+(0.5/(1+M))$	1.37	1.37	1.37
Fc	=	$0.21*Td*(1+0.2*X2)$	0.84	0.58	0.85
Qe	=	Capacity = $K*(F-Fc*Qc)$	AM 2672	1589	2795
			Logistic 2660	1568	2808
			PM 2722	1565	2824
DFC	=	Entry Flow/Capacity = $Q/Qe$	AM 0.07	0.28	0.08
			Logistic 0.07	0.27	0.08
			PM 0.10	0.20	0.06

**DFC of Critical Approach** = AM **0.28**  
Logistic **0.27**  
PM **0.20**