

SITE AREA : 51,073 sqm
 PLOT RATIO : 0.4
 GFA : RESIDENTIAL: 20,427 sqm
 CLUBHOUSE: 1021 sqm
 (5% of total GFA and to be exempted)

TYPE OF UNIT	GFA / UNIT (sqm)	GFA / UNIT (sqft)	NUMBER OF UNITS	GFA (sqm)
A-UPPER	229	2,465	6	1,374
A-LOWER	246	2,648	6	1,476
B	334	3,595	24	8,016
C	196	2,110	25	4,900
D	184	1,981	2	368
E	159	1,711	27	4,293
TOTAL : 90				20,427

WETLAND AREA (PHASE I DEVELOPMENT) : 24,702 sqm (48.37% OF SITE AREA)

COMMON GREENERY AREA BREAKDOWN

UNCOVERED HORIZONTAL PA	: 3,060 sqm
REED ZONE	: 8,990 sqm
GRASS PAVER	: 5,458 x 0.5 = 2,729 sqm
VERTICAL GREENERY (ASSUME HEIGHT OF 2.5M)	: 992m x 2.5m = 2,480 sqm
TOTAL :	17,259 sqm (33.79% OF SITE AREA)

- 2.5M TALL WOODEN TRELLIS ABOVE 2.5 M TALL FENCE WALL
- 2.5M TALL WOODEN TRELLIS
- TREE PIT AT PRIVATE GARDEN
- ▨ EVA


LIST OF HOUSING UNITS

A# (DUPLEX)	B	C	D	E & Ea*
Includes A-UPPER & A-LOWER				*Units with fixed clear glazing for bird-hide purpose
4 STOREYS + BASEMENT (BLDG HEIGHT: 14.5M ABOVE GROUND)	3 STOREYS + BASEMENT (BLDG HEIGHT: 13.5M ABOVE GROUND)	3 STOREYS (BLDG HEIGHT: 12.5 M ABOVE GROUND)	2 STOREYS + BASEMENT (BLDG HEIGHT: 9M ABOVE GROUND)	2 STOREYS + BASEMENT (BLDG HEIGHT: 9M ABOVE GROUND)
PHASE IV DEVELOPMENT	PHASE III & IV DEVELOPMENT	PHASE II DEVELOPMENT	PHASE IV DEVELOPMENT	PHASE III & IV DEVELOPMENT



Figure 11b

3 VISITOR
ACCESSIBLE CAR
PARKING SPACES



BASEMENT CARPARK
STAIRCASE

UNEXCAVATED
AREA

WETLAND OUTLINE ABOVE

7 VISITOR CAR
PARKING SPACES

RSMRC

SPS 250 m²

NUMBER OF PRIVATE CAR PARKING SPACES = 153 (BASEMENT) + 50 (G/F)
NUMBER OF VISITOR CAR PARKING SPACES = 7 + 3 (ACCESSIBLE PARKING)

DEVELOPMENT SCHEDULE	INTERNAL TRANSPORT FACILITIES	USE	HKPSG / LEASE REQUIREMENT	
			MIN.	MAX.
RESIDENTIAL - TOTAL GFA : 20,427 M ² - ACTUAL PLOT RATIO : 0.40 - TOTAL NO. OF UNITS : 90 (i) FLAT SIZE BETWEEN 130 160 M ² : 27 NOS. (ii) FLAT SIZE OVER 160 M ² : 63 NOS. - NO. OF HOUSES : 90 ASSUMING ONE HOUSE FOR EVERY FLAT	PRIVATE CAR PARKING SPACES	PRIVATE HOUSING		
		(i) RESIDENTIAL UNITS FLAT SIZE BETWEEN 130-160 M ²	28	49
		(ii) RESIDENTIAL UNITS FLAT SIZE OVER 160 M ²	82	144
		SUB-TOTAL	110	193
		REQUIRED ACCESSIBLE CAR PARKING SPACES	2	3
		VISITOR HOUSES		
			0	
		SUB-TOTAL	0	
		TOTAL	110	193
		MOTORCYCLE PARKING SPACES	TOTAL	1
LOADING / UNLOADING BAY	TOTAL		2	


NUMBER OF PRIVATE CAR PARKING SPACES ON G/F: 50

- WETLAND AREA ABOVE
- UNEXCAVATED AREA

Figure 22b

- LEGEND:
- SITE BOUNDARY
 - EXISTING TREE TO BE RETAINED (OUTSIDE APPLICATION SITE BOUNDARY)
 - PROPOSED HEAVY STANDARD TREE
 - PROPOSED LAWN
 - PROPOSED SHRUBS/GROUNDCOVER
 - PROPOSED GRASS PAVER
 - PROPOSED REEDBED
 - PROPOSED ISLANDS
 - WATER AREA
 - PROPOSED LEVEL
 - VERTICAL GREEN WALL (2.5m H) ON FENCE WALL/NOISE BARRIERS REFER TO DWG NO.LD103
 - PARTITION WALL (5.0m H) (2.5m H SOLID WALL + 2.5m H WOODEN TRELLIS) REFER TO DWG NO.LD105
 - PARTITION WALL (2.5m H) (2.5m H WOODEN TRELLIS) REFER TO DWG NO.LD106
 - BOUNDARY OF WETLAND RESTORATION AREA (WRA)
 - PROPOSED PAVING
 - MAJOR VEHICULAR AND PEDESTRIAN ACCESS

- ① Main Entrance
- ② Secondary Entrance
- ③ Club House
- ④ Footpath/EVA (Grass Pavers)
- ⑤ Roof Top Garden "A"
- ⑥ Roof Top Garden "B"
- ⑦ Sitting Courtyard "C"
- ⑧ Sitting Courtyard "D"
- ⑨ Existing Fish Pond



Noise Barriers composed of 2.5m H Solid Wall at base and Transparent Panels on top to minimize the visual intrusion of the Wall. Ornamental Trees, Shrubs, and Vertical Green Walls to provide Smooth Transition Between the Development and the Surrounding

Grass Paver with Sufficient Loading Capacity to enhance the Local Greenery at EVA

Riparian Planting to Enhance the Wetland Biodiversity and also Act as the Visual and Physical Buffer between Human Activities and Wildlife

PROJECT :
 PLANNING APPLICATION FOR PROPOSED COMPREHENSIVE DEVELOPMENT SCHEME TO INCLUDE WETLAND RESTORATION PROPOSED IN "OU(CDWRA)" ZONE AT NORTH OF KAM POK ROAD EAST, POK WAI, YUEN LONG, NEW TERRITORIES

DRAWING TITLE :
 LANDSCAPE MASTER PLAN (OVERALL)

PROJECT No. C1920

DRAWING No. LMP01

SCALE : 1:1200

DATE OF ISSUE : NOV 2022

CAD FILENAME : C1920-LMP01

Figure 28b

REV	DESCRIPTION	DATE
C	GENERAL AMENDMENT	07/12/23
B	GENERAL AMENDMENT	14/07/23
A	GENERAL AMENDMENT	09/05/23

DESIGN BY :	TEL
DRAWN BY :	CAD
CHECKED BY :	TEL
APPROVED BY :	TEL

- NOTES :
1. DO NOT SCALE DRAWING. FIGURED DIMENSIONS ARE TO BE FOLLOWED.
 2. COPYRIGHT OF THE DRAWING IS RETAINED BY THE AUTHORIZED PERSON.
 3. ALL DIMENSIONS ARE TO BE CHECKED AT SITE BY THE MAIN CONTRACTOR.
 4. READ THIS DWG. IN CONNECTION WITH GEN. ARCH. PLANS, STRUCT. PLANS, AND OTHER RELATED DWGS.

LanDes

LANDES LIMITED
 景藝設計有限公司

FLAT A-17/F,
 SHUN PONT COMMERCIAL BUILDING,
 5-11 THOMSON ROAD, HONG KONG
 TEL: 2868 0980 FAX: 2868 2203
 香港灣仔譚臣道5-11號
 信邦商業大廈17樓A室
 電話: 2868 0980
 傳真: 2868 2203