

Yuba Company Limited

Proposed Amendment to the Approved Wan Chai Outline Zoning Plan No. S/H5/31 from Comprehensive Development Area", "Residential (Group C)", "Open Space" and "Government, Institution or Community" zones and Areas shown as "Road" to "Other Specified Uses (Residential Development with Historic Building Conserved)" and "Other Specified Uses (Elevated Walkway)" at Nos. 1, 1A, 2 and 3 Hill Side Terrace, No. 55 Ship Street (a.k.a. Nam Koo Terrace), Nos. 1-5 Schooner Street, No. 53 Ship Street, No. 18 Sau Wa Fong, Inland Lot No. 9048 and adjoining Government Land, Wan Chai

Geotechnical Planning Review Report

August 2024

Report no: EA1425/G/R33/07

Contents

1	Introduction	1
2	The Site	1
2.1	Site Description	1
2.2	Ground Condition	2
2.3	Groundwater Condition	2
2.4	Existing Geotechnical Features.....	3
2.5	Existing Structures	6
2.6	General Description of the Proposed Works	8
2.7	Construction Methods and Sequence of Works	10
2.8	Discussion on Potential Natural Terrain Hazards.....	10
3	Geotechnical Review on Proposed Works	10
3.1	Proposed Ground Investigation Works.....	10
3.2	Effect on Existing GEO Registered Features	11
3.3	Indicative Development Scheme	12
4	Conclusion.....	13

Table

Table	Subject
Table 1	Summary Table of Measured Groundwater Levels (updated to 31 August 2021)
Table 2	Status of Registered Features in the vicinity of the Site
Table 3	Effect on Geotechnical Features due to proposed development

Figures

Figure	Subject
Figure 1	Site Location Plan
Figure 2	Existing Ground Investigations Plan
Figure 3	Geological Section
Figure 4	Location Plan of Existing Registered Slopes / Retaining Walls
Figure 5	Layout of the Existing Geotechnical Feautre

Appendices

Appendix	Subject
Appendix A	Records of Existing and Proposed Ground Investigation Works
Appendix B	Summary of Existing Registered Features
Appendix C	Architectural Drawing of Indicative Development Scheme
Appendix D	Layout of Piezometre P3a and P4
Appendix E	Record Plan of St. Francis' Canossian College
Appendix F	Record Plan of Nam Koo Terrace
Appendix G	Record Plan of Dragon Villa
Appendix H	Schematic Sections

1 Introduction

We are instructed by the Applicant, Yuba Company Limited to prepare this **Geotechnical Planning Review Report (GPRR)** in support of the Proposed Amendments to the Approved Wan Chai Outline Zoning Plan No. S/H5/31 from Comprehensive Development Area", "Residential (Group C)", "Open Space" and "Government, Institution or Community" zones and Areas shown as "Road" to "Other Specified Uses (Residential Development with Historic Building Conserved)" and "Other Specified Uses (Elevated Walkway)" at Nos. 1, 1A, 2 and 3 Hill Side Terrace, No. 55 Ship Street (a.k.a. Nam Koo Terrace), Nos. 1-5 Schooner Street, No. 53 Ship Street, No. 18 Sau Wa Fong, Inland Lot No. 9048 and adjoining Government Land, Wan Chai (collectively referred to as the "**Rezoning Site**" / the "**Site**").

The geotechnical feasibility of the Indicative Development Scheme in relation to the stability of man-made slopes/retaining walls and to address any potential natural terrain landslide hazards that may affect or be affected by the Site is assessed in the report. Please refer to Appendix 1 of supplementary planning statement for the architectural plans.

2 The Site

2.1 Site Description

The Rezoning Site is located at southwestern part of Wan Chai. It is bounded by Schooner Street and Greenland House to the north, Ship Street to the east, St. Francis' Canossian College to the south and St. Francis' Canossian School to the west.

Majority of the Site is vacant except for NKT and No. 18 Sau Wa Fong. NKT is a vacant two-storey historic building built between 1915 and 1921 as a residential house which is listed by the Antiquities Advisory Board ("AAB") as a Grade I Historic Building. The Rezoning Site also includes the adjoining Government Land at the southwest and northwest edges of the Site comprising

slopes and steps. The total site area of the Rezoning Site is 3157.6 m² in which the development site area is 3140.7 m² after excluding the elevated walkway above Ship Street staircase.

Areas surrounding the Rezoning Site are characterised by a mix of land uses including residential, education, open space, commercial and retail uses.

The location of the Site is presented in Figure 1.

2.2 Ground Condition

According to the Hong Kong Geological Map, Series HGM20, Sheet No. 11 (Scale 1: 20,000), Solid and Superficial Geology of Hong Kong & Kowloon published by the Geotechnical Control Office (GCO 1986), the area of the Site is underlain by Jurassic-cretaceous medium-grained granite.

According to the existing Ground Investigation (GI) reports retrieved from the Geotechnical Engineering Office (GEO), the previous GI works were carried out in the vicinity between 1981 and 2000. The existing and proposed GI records reveal that the Site generally comprises a layer of fill of various thickness and decomposed granite. The bedrock level varies between +11.4mPD and 45.08 mPD and is dipping in a direction of south to north across the Site.

The location of existing and proposed GI is presented in Figure 2. The geological section illustrating the typical ground condition of the Site is presented in Figure 3. The records of existing and proposed GI are attached in Appendix A.

2.3 Groundwater Condition

Groundwater monitoring has been carried out at piezometers P3a and P4 within the site since April 2014 for the proposed Hopewell Centre II development. The recent groundwater monitoring records around the Ship Street Stair site are presented as in **Table 1**, below.

Piezometer	Ground Level (mPD)	Piezometer Tip Level (mPD)	Lowest Groundwater Level (mPD)	Highest Groundwater Level (mPD)
P3a	+43.65	+26.99	+21.941	+35.998
P4	+12.335	+5.235	+7.448	+12.308

Table 1: Summary Table of Measured Groundwater Levels (updated to 31 August 2021)

The groundwater contour plan approved under Site Formation Design submission for Main Site based on the groundwater monitoring readings showed that the groundwater level across the Ship Street Stair site dipping from +42 mPD in the south to +12 mPD in the north.

The layout out of the P3a and P4 indicates in Appendix D.

In borehole B1 installed in 1981, the highest measured groundwater level was at +9.47mPD.

2.4 Existing Geotechnical Features

There are ten numbers of GEO registered features in the vicinity of the Site. Three of the registered features are situated within the Site. The locations of these features are shown in Figure 4.

Desk study on previous stability assessment on these eight registered features has been carried out. The results revealed that among the 10 registered features, 4 registered features were assessed by GEO and 3 of which have been served with Dangerous Hillside Orders. A summary of the status of the registered features is presented below:

Feature No.	Status
11SW-B/CR252	GEO Stage 2 Study carried out in 2004. Advisory letter was issued to lot owner in 2004.
11SW-B/CR253	No previous study.
11SW-B/CR235	Slope upgrading works were implemented by the responsible owner, and GEO advised BD on

	28/9/2011 of no geotechnical objection to the acknowledgement of Form BA14.
11SW-B/CR349 (Wall Portion of Sub-division No. 1)	DH0035/HK/11/C served on lot owner on 3/2011. Remedial works proposal approved by BD on 11/3/2013. The remedial works are completed in 11/2017.
11SW-B/C353	No previous study.
11SW-B/R616	GEO Stage 2 Study carried out in 1995; feature found to be up to current geotechnical standards.
11SW-B/R617	GEO Stage 2 Study carried out in 1988; feature found to be up to current geotechnical standards. GEO Stage 2 Study carried out in 2014. DH0038/HK/15/C served on lot owner on 6/6/2015. DH0005/HK/21/C served on lot owner on 10/3/2021.
11SW-B/R629	DH0035/HK/11/C served on lot owner in 3/2011. Remedial works proposal approved by BD on 11/3/2013. The remedial works are completed in 11/2017. The latest remedial works approval drawings were attached in Appendix E for reference.
11SW-B/R963	No previous study.
11SW-B/R1023	New registration of Slope Feature, approved on 13 January 2024. Acknowledged on 28 June 2023. (Under BD 6/3027/20(RD)).

Table 2: Status of Registered Features in the vicinity of the Site

The layout of the Existing Geotechnical Feature is shown on figure 5. And The findings of the desk study are summarised in Appendix B.

Feature No.	Existing Conditions	Anticipated Affected Extent of Features
11SW-B/CR252	About 5m high 90° Concrete wall.	The feature is to be maintained. The retaining wall will modify to proposed development. Adequate shoring system will be provided for the excavation that it requested monitoring to control the ground settlement, thus the effect on the features will be minimal.
11SW-B/CR235	About 5.5m high 90° Concrete wall.	The retaining wall will modify to Indicative Development Scheme . Adequate shoring system will be provided for the excavation that it requested monitoring to control the ground settlement, thus the effect on the features will be minimal.
11SW-B/CR253	About 2m high 88° Masonry wall.	The retaining wall will modify to Indicative Development Scheme . Adequate shoring system will be provided for the excavation that it requested monitoring to control the ground settlement, thus the effect on the features will be minimal.
11SW-B/CR349 (Wall Portion of Sub-division No. 1)	About 8m high 80° masonry wall.	The retaining wall will modify to Indicative Development Scheme . Adequate shoring system will be provided for the excavation that it requested monitoring to control the ground settlement, thus the effect on the features will be minimal.
11SW-B/R963	About 5.5m high 85° Wall	The retaining wall will modify to Indicative Development Scheme . Adequate shoring system will be provided for the excavation that it requested monitoring to control the ground settlement, thus the effect on the features will be minimal.
11SW-B/R616	About 8.3m high 83° masonry wall.	The feature is to be maintained. No adverse effect will be induced.

Feature No.	Existing Conditions	Anticipated Affected Extent of Features
11SW-B/R629	About 10m high 85° masonry wall.	The feature is to be maintained. Since the Indicative Development Scheme case will be slightly filled up at the passive side of the masonry wall only, no adverse effect will be induced.
11SW-B/R616	About 8.3m high 83° masonry wall.	feature is to be maintained. Since the Indicative Development Scheme case will be slightly filled up at the passive side of the masonry wall only, no adverse effect will be induced.
11SW-B/R617	About 11.8m high 85° masonry wall.	The feature would need to be demolished to facilitate the construction of the proposed residential building.
11SW-B/C353	About 4m high slope	The feature would need to be demolished to facilitate the construction of the proposed residential building.
11SW-B/R1023	5.6 m High Concrete Retaining Wall	The feature is to be maintained. No adverse effect will be induced.

Table 3 Effect on Geotechnical Features due to proposed development

Stability of the existing geotechnical features will affect or be affected by the proposed works will be investigated in the detailed design stage. If necessary, upgrading works will be carried out first for the features which cannot meet the current safety standard. All the man-made features are proposed to be maintained as far as possible.

2.5 Existing Structures

2.5.1 St. Francis' Canossian College comprise of a 3-storey low-rise building structure which was built in 1957 and a new 6-storey low-rise building structure

which was built in 2012 at No. 9-13 Kennedy Road. The new 6-storey building, founded on socket H-pile, is located adjacent to the proposed external staircase. The platform level of the building is generally +52.20mPD. The level difference between the platform and existing staircase is retained by a mass concrete retaining wall. Record plans are retrieved from BD and attached in Appendix E for reference.

2.5.2 Nam Koo Terrace is located at Lot No. I.L. 2140, No. 55 Ship Street. The property comprises two independent buildings, the main building and an annex. The main building and the annex are 2 storeys high, located at 7m from the proposed Park. The rear of the main building is a courtyard. DH order no. DH161/HK/98/C regarding the feature 11SW-B/R629 was issued by BD on 10 August 1998. Wall remedial works submission was approved on 19 Nov 2001. Three amendments were submitted and approved on 10 Jun 03, 25 Aug 05 and 19 April 11 respectively. The Indicative Development Scheme is located along the west to north east side of the building. In addition, the historical building will be preserved and revitalised as part of the Indicative Development Scheme. Record plans and latest remedial works approval drawings were attached in Appendix F for reference.

2.5.3 St. Luke College and Miu Kang Terrace are demolished. The proposed shop and building is located the those lot for development. Hill Side Terrace is founded on pad footing. The site is located at the northeast of the captioned building. There is an existing stone retaining wall with maximum 4m retaining height located between the Hill Side Terrace and the Site. Additional ground investigation works will be proposed to verify the configuration. Stability will be checked in detail design stage. Effect on the existing foundation due to the proposed socket H-pile foundation works for the Indicative Development Scheme should be minimal. Record plans are retrieved from BD and attached in Appendix I for reference. Miu Keng Terrace was a 6-storey building is situated at Lot No. I.L. 2903 RP, No. 53 Ship Street, was located at the southeast of the Site. According to the as-built foundation record plans (BD ref. 3/3196/72), the building structure is founded on pad footings with founding levels of +17.5mPD or 1.5m below the Ship Street step levels.

2.5.4 I.L. 199 RP (No. 18 Sau Wa Fong) was occupied by a 6 storeys residential building. An open space will be constructed in this lot. Additional ground investigation works will be proposed to verify the configuration. Stability will be checked in detailed design stage. Effect on the existing foundation due to the proposed socket H-pile foundation works for the Indicative Development Scheme should be minimal.

2.5.6 Dragon Villa located 8 Sik On Street

Dragon Villa is located at No. 2-8 Sik On Street. The captioned building was founded on 13no. of caisson piles rested on bedrock. The indicative development scheme is located at the southeast of the captioned building. Since the site is located 10m from the Site, effect on the existing foundation due to the proposed socket H-pile foundation works for the Indicative Development Scheme should be minimal. Record plans are retrieved from BD and attached in Appendix G for reference.

2.6 General Description of the Proposed Works

As the Indicative Development Scheme is designed to encroach into the existing slope, the following geotechnical works will be participated and should be considered extremely carefully so that no adverse impact will be induced on adjacent properties. The geotechnical works related to the Indicative Development Scheme within the lot boundary will be basically listed, considered and discussed as follows.

Foundation

In view of a total of 28-storeys reinforced concrete building, loadings such as dead load, wind load and live load from the proposed superstructure are expected to be not substantial. Therefore, rock socket H-piles should be appropriate and the effect on the adjacent properties should be minimal.

In accordance with available ground investigation works, the bedrock is about 12m to 18m below existing ground. In order to take lateral loads due to soils and wind on the proposed building, piles are required to be designed socketted into rock to provide a better friction capacity for vertical as well as lateral loadings.

Detailed design calculation with assessment should be carried out and submitted for approval in order to ensure no adverse impact induced on the adjacent slopes, foundation, etc.

Excavation for construction of pilecaps and retaining wall

Since the building load is just catered for 28-storeys, pilecap is expected to be about 1.5m thick. By taking into account of 1m deep allowances for the proposed drainage system, maximum excavation height will be involved for about 2.5m deep from the proposed ground floor level.

For the level difference between the Site and adjacent ground, L-shaped retaining wall with maximum 5m retaining height is proposed.

As considered the limitation of working space, sheet pile/pipe pile, with strutting if necessary, is considered necessary for construction of the pilecap and retaining wall. The maximum retaining height is about 5m. Since the underside of the pilecap is 3m to 5m from ground level, it is likely that dewatering is not necessary. However, the method of dewatering will be considered in details and designed so as to ensure no adverse impact on the adjacent properties. For the level difference between the Site and adjacent ground, L-shaped retaining wall with maximum 5m retaining height is proposed.

During excavation, close monitoring on the adjacent properties and groundwater level will be implemented. Detailed design with assessment will be carried out and submitted for approval in order to ensure no adverse impact induced on the adjacent properties, etc.

Schematic drawings for the captioned site formation works are attached in Appendix E. All existing features affecting or being affected by the development will be investigated and, if necessary, upgrading works will be proposed and carried out. Relevant details will be designed and submitted to the Buildings Department for approval.

2.7 Construction Methods and Sequence of Works

Excavation will be generally shoring system around the Site. The stability of the proposed shoring system will be checked. The Site will be flatted for construction of the socket H-pile. Platform will be considered if piling works are carried out prior to the excavation works. Upon completion of the ELS and piling works, the proposed pile caps and retaining wall will be constructed. Upon completion of the substructures, backfilling will be carried out up to the proposed finish level. Schematic sections of the proposed ELS works and superstructure works are attached at Appendix H.

2.8 Discussion on Potential Natural Terrain Hazards

The Indicative Development Scheme is surrounded by building structures and no natural terrain is located in the vicinity of the Site. Hence, no natural terrain hazards are anticipated for the Indicative Development Scheme .

3 Geotechnical Review on Proposed Works

Majority of the Rezoning Site is vacant except Nam Koo Terrace (a Grade 1 Historic Building) and No. 18 Sau Wa Fong. The Indicative Development Scheme comprises of a 24 storey residential tower over a 3 storey podium with NKT preserved in-situ and an Open Space. Layout and cross-sections of the Indicative Development Scheme are attached at Appendix C.

The geotechnical aspects of the proposed works are presented below.

3.1 Proposed Ground Investigation Works

Site-specific ground investigation works will be proposed at the Site in order to obtain information on the subsurface profile and material characteristics, groundwater regimes and foundations of the existing building. The proposed ground investigation works will comprise the following:-

- Vertical drillholes (with piezometer/standpipe);
- Trial pits;
- Horizontal/inclined coreholes;
- Field tests;
- Laboratory tests.

The proposed ground investigation works will be carried out in compliance with the current geotechnical standards and the site supervision requirements as stipulated in the “Code of Practice for Site Supervision 2009” published by the Buildings Department (BD).

3.2 Effect on Existing GEO Registered Features

Six registered features, namely Feature Nos. 11SW-B/CR252, 11SW-B/CR253, 11SW-B/CR349, 11SW-B/R629, 11SW-B/C353 and 11SW-B/R1023 are located within the boundary of the Site. Three other registered features, namely Feature Nos. 11SW-B/R617, 11SW-B/CR235 and 11SW-B/R963, are located outside the boundary of the Site.

The Indicative Development Scheme is at close proximity to the crest of Feature Nos. 11SW-B/CR235, 11SW-BC353, 11SW-B/R617, 11SW-B/R629 and 11SW-B/R963 and hence the impact on these existing slopes due to the additional loading from the Indicative Development Scheme and its foundation system shall be investigated and stabilization works shall be proposed if found necessary. Whereas, Feature Nos. 11SW-B/CR252, 11SW-B/CR253 and 11SW-B/CR349 are located along the southern uphill side of the Indicative Development Scheme. And No. 11SW-B/R1023 was the new register feature for the level difference of Ship Street Staircase. Considering the founding levels of the foundation will be rationally well below the toe levels of these features, no adverse impact is likely to be induced to these features. These features will be modified to form the open space. A proposal for modifying or upgrading the features will be presented in the ELS plan or site formation plan to be submitted separately to the BD for approval.

Moreover, Dangerous Hillside Orders have been served on Feature Nos. 11SW-B/CR349 (Sub-division 1) and 11SW-B/R629 by the BD. The remedial works proposals, comprising buttressing works at 11SW-B/CR349

(Sub-division 1) and soil nailing works at Feature No. 11SW-B/R629, have been submitted and approved by the BD in June 2011. The remedial works are completed in November 2017. The impact on these two features due to the proposed works should be investigated. In particular, the impact on Feature No. 11SW-B/R629 due to the loading from the foundation of the Indicative Development Scheme will be reviewed and further upgrading works will be proposed if found necessary. Design amendments to the remedial works proposals incorporating the assessment of the impact to the features due to the development shall be submitted to the BD for approval.

The upgrading works comprising installation of soil nails and construction of reinforced concrete retaining walls or mass concrete walls are considered feasible subject to the actual site constraints for individual features.

3.3 Indicative Development Scheme

The Indicative Development Scheme within the Site consists of a 24 storeys over a 3 storey podium with NKT preserved in-situ and an Open Space from +19.76 mPD to +118.80 mPD (at Main Roof Level). The residential tower will be built at the same level as Nam Koo Terrace at +33.6 mPD. Layout and cross-sections of the Indicative Development Scheme are attached at Appendix C.

The existing ground level within the Site is at +19.76 mPD (Schooner Street), which is about the proposed G/F for shops and 2/F and 3/F for E/M. In designing the Proposed Comprehensive Development, consideration have been given to the type of foundation and the rockhead levels in the vicinity of the Site. Therefore, the new building is proposed to be supported by a combination of footing and pile foundations. In addition, as the Indicative Development Scheme will be built adjacent to Nam Koo Terrace, the impact of the proposed foundation on the existing foundation of Nam Koo Terrace will be investigated and preventive measures, such as sleeving will be provided. Also, Feature No. 11SW-B/R629 (served with a Dangerous Hillside Order by the Buildings Department) supporting the building platform of Nam Koo Terrace was upgraded by soil nails in November 2017. Nonetheless,

the building and ground movement of Nam Koo Terrace will be closely monitored during implementation of the proposed construction works.

Local excavation will be proposed to facilitate the construction of footing foundation or pile caps. Open excavation and ELS system are feasible options for the local excavation works.

In conclusion, no geotechnical difficulty is anticipated arising from the required excavation and foundation works of the Indicative Development Scheme .

4 Conclusion

The purpose of this report is to present a Geotechnical Planning Review on the Indicative Development Scheme at Approved Wan Chai Outline Zoning Plan No. S/H5/31 from Comprehensive Development Area", "Residential (Group C)", "Open Space" and "Government, Institution or Community" zones and Areas shown as "Road" to "Other Specified Uses (Residential Development with Historic Building Conserved)" and "Other Specified Uses (Elevated Walkway)" at Nos. 1, 1A, 2 and 3 Hill Side Terrace, No. 55 Ship Street (a.k.a. Nam Koo Terrace), Nos. 1-5 Schooner Street, No. 53 Ship Street, No. 18 Sau Wa Fong, Inland Lot No. 9048 and adjoining Government Land, Wan Chai to illustrate how the proposed works may affect or be affected by the existing features within and in the vicinity of the Site.


As the proposed works may have impacts on some of the slopes and retaining walls, the overall stability will be examined during the detailed design stage, and if necessary, be modified to comply with the current geotechnical standards. A proposal for modifying and upgrading the features within the Site will be presented in the ELS plan or site formation plan (including Pipe Pile Work) to be submitted separately.

Additional ground investigation works will be carried out at within the Site area to obtain adequate geotechnical & geological for carrying out design of site formation, ELS and pipe foundation works of the Indicative Development Scheme .

In conclusion, the Indicative Development Scheme is geotechnically feasible to be implemented within the Site.

Figures

Plot Date: 29/Feb/2024 4:14:25 pm File Location: P:\EA01425 HOPEWELL MEGA HOTEL\E-OURDRAWINGS\GC-EA01425\CURRENT\DH ORDER\NAM KOO TERRACE\INSPECTION\2021-04-27 - COPY\FIGURE 1D.DWG



LEGEND:



Status			
Scales	1 : 1000	Original Size	A4
Height Datum	-	Grid	-
Filename:	FIGURE 1D.dwg		
© Copyright reserved			

Project	
PROPOSED AMENDMENT TO THE APPROVED WAN CHAI OUTLINE ZONING PLAN NO. S/H5/31 AT NOS. 1, 1A, 2 AND 3 HILL SIDE TERRACE, NO. 55 SHIP STREET (A.K.A. NAM KOO TERRACE), NOS 1-5 SCHOONER STREET, NO. 53 SHIP STREET, NO. 18 SAU WA FONG, INLAND LOT NO. 9048 AND ADJOINING GOVERNMENT LAND, WAN CHAI	
Title	
LOCATION PLAN	

asia infrastructure solutions

建業(亞業)工程顧問有限公司

Drawing No. FIGURE 1	Project No. EA01425	Issue D
--------------------------------	-------------------------------	-------------------

50mm on Original

Plot Date: 13/Sep/2024 2:54:04 pm File Location: P:\EA01425 HOPEWELL MEGA HOTEL VE-OURDRAWINGS\GC-EA01425\CURRENT\DH ORDER\NAM KOO TERRACE\INSPECTION\2024-02-29\FIGURE 2D.DWG



LEGEND:

- SITE BOUNDARY
- PD1
- FGS/BH1P
- BSG/TP1
- PROPOSED PRE-DRILL HOLE
- EXISTING BOREHOLE
- EXISTING TRIAL PIT

Status		
Scales	1 : 500	Original Size A4
Height Datum	-	Grid -
Filename:	FIGURE 2D.dwg	
© Copyright reserved		





Project
 PROPOSED AMENDMENT TO THE APPROVED WAN CHAI OUTLINE ZONING PLAN NO. S/H5/31 AT NOS. 1, 1A, 2 AND 3 HILL SIDE TERRACE, NO. 55 SHIP STREET (A.K.A. NAM KOO TERRACE), NOS 1-5 SCHOONER STREET, NO. 53 SHIP STREET, NO. 18 SAU WA FONG, INLAND LOT NO. 9048 AND ADJOINING GOVERNMENT LAND, WAN CHAI

Title
 EXISTING GROUND INVESTIGATION PLAN

Drawing No.
FIGURE 2

Project No.
EA01425

Issue
D



P:\EA01425 HOPEWELL MEGA HOTEL\E-OurDrawings\GC-EA01425\Current\DH_Order\Nam Koo Terrace\Inspection\2024-02-29\FIGURE 3D.dwg

PROJECT : PROPOSED AMENDMENT TO THE APPROVED WAN CHAI OUTLINE ZONING PLAN NO. S/H5/31 AT NOS. 1, 1A, 2 AND 3 HILL SIDE TERRACE, NO. 55 SHIP STREET (A.K.A. NAM KOO TERRACE), NOS 1-5 SCHOONER STREET, NO. 53 SHIP STREET, NO. 18 SAU WA FONG, INLAND LOT NO. 9048 AND ADJOINING GOVERNMENT LAND, WAN CHAI


TITLE : Geological Section

PROJECT NO : EA01425
DRAWING NO : FIGURE 3
ISSUE : D


0 5 10 15m
SCALE 1:500@A3



Plot Date: 13/Sep/2024 2:42:38 pm File Location: P:\EA01425 HOPEWELL MEGA HOTEL VE-OURDRAWINGS\GC-EA01425\CURRENT\DH-ORDER\NAM KOO TERRACE\INSPECTION\2024-02-29\FIGURE 4.DWG



LEGEND



SITE BOUNDARY
SLOPE BOUNDARY

Status		
Scales	1 : 1000	Original Size A4
Height Datum	-	Grid -
Filename:	FIGURE 4D.dwg	
© Copyright reserved		


Project
PROPOSED AMENDMENT TO THE APPROVED WAN CHAI OUTLINE ZONING PLAN NO. S/H3 AT NOS. 1, 1A, 2 AND 3 HILL SIDE TERRACE, NO. 55 SHIP STREET (A.K.A. NAM KOO TERRACE), NOS 1-5 SCHOONER STREET, NO. 53 SHIP STREET, NO. 18 SAU WA FONG, INLAND LOT NO. 9048 AND ADJOINING GOVERNMENT LAND, WAN CHAI
 Title
LOCATION PLAN OF EXISTING REGISTERED SLOPES /RETAINING WALLS



asia infrastructure solutions

Drawing No. FIGURE 4	Project No. EA01425	Issue D
--------------------------------	-------------------------------	-------------------

Existing Geotechnical Features



**Man Made Slope
Man-made
Features**

- Cut slopes
 - Disturbed terrain
 - Fill slopes
 - NT defence measures
 - NT stabilisation measures
 - Retaining walls
- Slope Features

Division

Scale 1:500


Date 22/8/2024



The Government of the Hong Kong SAR

Appendix A

Records of Existing and Proposed Ground Investigation Works



PRELIMINARY GROUND INVESTIGATION
LAYOUT PLAN



LEGEND

PROPOSED VERTICAL BOREHOLE
(TO BE TERMINATED INTO AT LEAST
5m INTO GRADE III OR BETTER MATERIAL
WITH MIN. TCR OF 85%)
DH1-DH5

PROPOSED TRIAL PIT
(MAX. 3m DIP)
TP1-TP3

PROPOSED HORIZONTAL AND
INCLINED COREHOLES (2M MAX.)
HC1-HC5
ICH1-ICH5

ENGINEER:

HYDER CONSULTING LTD.

CLIENT:


HOPEWELL CONSTRUCTION LTD.

PROJECT TITLE:

**SCHOONER STREET
DEVELOPMENT AT DEVELOPMENT
AT I.L. 9048**

DRAWING TITLE:

GROUND INVESTIGATION PLAN



Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH1
 Sheet: 1 of 3
 Date: 27.12.2015 to 03.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835534.02 N: 815180.42	Rock Corebit: T-120/T2-101
Machine Opnr.: WAN		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +21.26 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
27/12									A ● 0.50	U100	+21.26	0.00			Loose, dark brown, gravelly silty fine to coarse SAND. (FILL)
27/12		Dry PM							B ● 1.00		+20.26	1.00		V	Extremely weak, dark brown spotted white, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
30/12		Dry AM		100				7,6,7,8,9,9 N=33	C ● 1.50		+19.76	1.50		V	Extremely weak, dark brownish grey spotted white & black, completely decomposed medium to coarse grained GRANITE. (gravelly silty fine to coarse SAND.)
									1 U100						
									2 U100						
									3 U100						
									4 ● 3.55						
											+17.26	4.00		IV	Very weak, brownish grey & grey spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.)
				58	52	32	NI		T-120			4.68		III	From 4.68m to 5.00m: moderately strong, moderately decomposed.
											+16.26	5.00		V	Extremely weak, light pinkish brown spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
									5 U100						
									6 ● 5.45						
											+15.66	5.60		III	Moderately strong, light brownish grey & grey spotted white & black, moderately decomposed medium to coarse GRANITE with widely spaced & iron stained joints. (Corestone)
				100	100	97	3.2		T-120						
											+14.81	6.45		V	Extremely weak to very weak, light grey spotted white & black, completely decomposed medium to coarse grained GRANITE. (gravelly silty fine to coarse SAND.)
									7 U100						
									8 ● 6.95						
									9 U100						
									10 U100						
									11 U100						
									12 ● 8.55						
											+12.26	9.00		IV	Very weak, brownish grey spotted white & black, highly decomposed medium to coarse grained GRANITE. (very sandy fine to coarse GRAVEL.)
				100							+11.26	10.00			

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- ⊙ Permeability test
- ⊕ Piezometer tip
- ⊕ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:
 Standpipe installed at depth of 18.70m.
 Acoustic borehole televiewer(ABT) test carried out at depth of 17.20m to 24.69m.

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH1
 Sheet: 2 of 3
 Date: 27.12.2015 to 03.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835534.02 N: 815180.42	Rock Corebit: T-120/T2-101
Machine Optr.: WAN		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +21.26 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples			Reduced Level (mPD)	Depth (m)	Legend	Grade	Description			
									No.	Type	Depth								
31/12 02/01 HX	2.10m PM 11.50m AM			100				19,23,33,39,44,47 N=163	14 15 16	10.10 10.55	+11.26	10.00		IV	See sheet 1 of 3 for details.				
								50/6mm,200/60mm N=200/60mm	17 18 19	11.00 12.10 12.22									
				100				50/40mm,200/60mm N=200/60mm	20 21 22	13.00 14.10 14.20									
								50/70mm,200/60mm N=200/60mm	23	17.10 17.23									
				94	79	41	10				T2-101	14.85				+6.41	14.85	III	Moderately strong, light brownish grey & grey spotted white & black, moderately decomposed medium to coarse GRANITE.
							>20											IV	
				91	91	91	1.7				T2-101	15.67					15.67	III	14.85m to 15.25m, 16.84m to 17.10m, 17.43m to 17.90m: moderately strong, moderately decomposed. From 15.25m to 15.67m, 17.10m to 17.43m: very weak, light brown, highly decomposed medium to coarse grained granite. (sandy fine to coarse gravel.) From 18.52m to 18.72m, 19.08m to 19.21m: no recovery, assumed to be highly decomposed.
				100	96	62	15.3				T2-101	16.84					17.10	IV	
				100	100	100	2.8				T2-101	17.43					17.43	III	Moderately strong to strong, light brownish grey & grey spotted white & black, slightly decomposed medium to coarse GRANITE.
				100	100	100	5.6				T2-101	18.52					18.72	III	
100	100	100	2.1				T2-101	19.08 19.21		+2.05	19.08 19.21	IV	Joints are medium to closely, occasional very closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-30, 45-60.						
							T2-101	20.00		+1.26	20.00	II							

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH1
 Sheet: 3 of 3
 Date: 27.12.2015 to 03.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835534.02 N: 815180.42	Rock Corebit: T-120/T2-101
Machine Opnr.: WAN		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +21.26 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description	
									No.	Type						
02/01		1.60m PM		98	98	90	13.3		T2-101		+1.26	20.00	+	II	See sheet 2 of 3 for details.	
03/01		11.40m AM		100	100	93	1.3		T2-101		20.45	20.70	+	III		
									T2-101		21.20	21.20	+	II		
03/01				100	100	100			T2-101		21.90	22.40	+	III		
									T2-101		22.55	22.55	+	II		
03/01				100	100	100			T2-101		23.34	23.34	+			
									T2-101		24.74	24.74	+			
											-3.48	24.74	+			End of hole at depth of 24.74m.

- | | |
|---------------------------|-----------------------------|
| ● Small disturbed sample | ▽ Water table |
| ⬇ Large disturbed sample | ↓ Standard Penetration Test |
| ▨ SPT liner sample | ⊙ Permeability test |
| ■ U100 undisturbed sample | ⬆ Piezometer tip |
| ▩ Mazier sample | ⬆ Standpipe tip |
| P/S Piston sample | ▽ Vane shear test |

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH2
 Sheet: 1 of 3
 Date: 06.01.2015 to 09.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:
 E: 835544.46
 N: 815162.53

Rock Corebit: T2-101

Machine Opnr.: WAN

Hole Dia: PX/HX

Flushing Medium: WATER

Orientation: VERTICAL

Ground Level: +21.15 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description								
									No.	Type													
06/01	PX	1.60m PM	100	100	100	100		1,3,2,2,3,5 N=12 1,5,8,10,10,15 N=43 3,7,11,15,16,17 N=59 2,6,10,15,18,21 N=64	A	● 0.50	+21.15	0.00	[Cross-hatched pattern]	V	Loose, light greyish brown, gravelly silty fine to coarse SAND. (FILL) Extremely weak, light yellowish brown & brown spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)								
B									● 1.00	+20.15	1.00												
C									● 1.50														
									1	[Diagonal lines]	2.00												
									2	[Solid black]	3.10												
									3	[Diagonal lines]	3.50												
									4	● 3.95	4.00												
									5	[Diagonal lines]	5.10												
									6	[Solid black]	5.50												
									7	[Diagonal lines]	6.95												
06/01																	8	● 8.00					
07/01									HX	Dry AM	100	100	100				9	[Diagonal lines]	7.10			V	Extremely weak, light red spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
																	10	[Solid black]	7.50				
																	11	[Diagonal lines]	7.95				
																	12	● 8.00	8.00	+13.15	8.00		
																	13	[Diagonal lines]	9.10				
	14	[Solid black]	9.50																				
	15	[Diagonal lines]	9.95																				
	16	● 9.95	+11.15	10.00																			

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- ▩ U100 undisturbed sample
- ▨ Mozier sample
- P/S Piston sample
- ▽ Water table
- ⬇ Standard Penetration Test
- ⊙ Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ▽ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:
 Standpipe installed at depth of 18.10m.
 Acoustic borehole televiewer(ABT) test carried out at depth of 17.80m to 24.21m.

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH2
 Sheet: 2 of 3
 Date: 06.01.2015 to 09.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835544.46 N: 815162.53	Rock Corebit: T2-101
Machine Optr.: WAN		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +21.15 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
				100					17	U100	+11.15	10.00		V	See sheet 1 of 3 for details.
				100				4,6,11,18,28,38 N=95	19	U100	+9.15	12.00		IV	Very weak, light greyish brown spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.)
				100	82	61			20	U100	+8.45	12.70		III	Very weak to moderately strong, dark greyish brown & brown spotted white & black, highly decomposed medium to coarse grained GRANITE. Joints are medium to very closely spaced, extremely narrow to narrow, rough planar, smooth planar, rough undulating, iron stained, kaolin coated, dipping at 20-30, 45-60 & 60-70.
				91	86	13	8.2		21	U100		13.05		IV	
				86	82	10	>20		22	U100		14.10			From 12.70m to 13.05m & 16.78m to 17.08m: moderately strong, moderately decomposed. From 17.08m to 17.60m: very weak, light brownish grey spotted white, highly decomposed medium to coarse grained granite. (sandy fine to coarse gravel.)
				88	80	38	NI		23	U100		15.52			
07/01		3.60m PM										16.68			Moderately strong to strong, light brownish grey & grey spotted white & black, slightly decomposed medium to coarse grained GRANITE. Joints are medium to widely, occasional closely to very closely spaced, extremely narrow to tight, rough planar, rough undulating, iron stained, dipping at 10-20, 45-60 & 60-70.
08/01		12.60m AM										17.08			
				95	95	66	6					17.60			From 17.60m to 17.80m: moderately weak, moderately decomposed. From 17.80m to 18.84m, 20.00m to 20.20m: moderately strong, moderately decomposed. From 23.55m to 23.80m: strong, dark grey, slightly decomposed fine to medium grained granite.
				100	100	100						17.80			
				100	100	92	3.3					18.60			
												19.07			
												20.00			

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH2
 Sheet: 3 of 3
 Date: 06.01.2015 to 09.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835544.46	Rock Corebit: T2-101
Machine Optr.: WAN	N: 815162.53	Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +21.15 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples No. Type Depth	Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
08/01		2.60m PM		100	100	83	10.0		T2-101 20.51	+1.15	20.00 20.20	+	III	See sheet 2 of 3 for details.
09/01		11.80n AM		100	100	94	3.7		T2-101 21.91			+	II	
				100	100	93			T2-101 23.35			+		
09/01				100	100	93			T2-101 24.27	-3.12	24.27	+		
														End of hole at depth of 24.27m.

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH3
 Sheet: 1 of 3
 Date: 03.01.2015 to 06.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: T2-101

E: 835531.50

Machine Optr.: WAH

N: 815160.32

Hole Dia: PX/HX

Flushing Medium: WATER

Orientation: VERTICAL

Ground Level: +27.05 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples No. Type Depth	Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
03/01														
	PX			95					A ● 0.50 B ● 1.00 C ● 1.50	+27.05	0.00			Loose, light greyish brown dark brown, silty gravelly fine to coarse SAND. (FILL)
								3,2,3,4,4,6 N=17	1 ▨ 2.00 2 ● 3.10 3 ▨ 3.50 4 ● 3.95 4.00	+26.05	1.00		V	Extremely weak, light brown & occasional dark grey, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
				85				5,7,10,19,27,35 N=91	5 ▨ 5.10 6 ● 5.50 7 ▨ 6.50 8 ● 6.95 6.00					
				85				6.50	9 ▨ 7.10 10 ● 7.50					
								3,5,7,7,10,15 N=39	11 ▨ 7.50 12 ● 7.95 8.00	+19.05	8.00		IV	Very weak, light yellowish brown & brown spotted white & black, highly decomposed medium to coarse grained GRANITE. (very sandy fine to coarse GRAVEL.)
	HX			95				5,8,12,17,25,36 N=90	13 ▨ 9.10 14 ● 9.50 15 ▨ 9.90 16 ● 9.95	+17.05	10.00			

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- ▩ U100 undisturbed sample
- ▤ Mozier sample
- P/S Piston sample
- ▼ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ▼ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:
 Constant head permeability test carried out at depth of 6.50m to 8.00m.
 Acoustic borehole televiewer (ABT) test carried out at depth of 19.22m to 24.59m.

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH3
 Sheet: 2 of 3
 Date: 03.01.2015 to 06.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835531.50 N: 815160.32	Rock Corebit: T2-101
Machine Optr.: WAH		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +27.05 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description					
									No.	Type										
03/01 05/01	3.60m PM 03/01 Dry			95				50/50mm,200/70mm N=200/70mm	17	10.00	+17.05	10.00	[Pattern]	IV	See sheet 1 of 3 for details.					
									18	11.10										
									19	11.95										
									20	12.00										
									21	13.10										
									4	13.50		+13.45				13.60	[Pattern]	III	Moderately strong, light greyish & pink spotted white & black, moderately decomposed medium to coarse grained GRANITE. Joints are medium to very closely spaced, extremely narrow to very narrow, rough planar, rough undulating, iron stained, dipping at 10-20, 45-60 & 60-70. From 15.41m to 15.60m & 18.18m to 18.30m: moderately weak, highly decomposed. From 15.09m to 15.41m: very weak, light pinkish brown, highly decomposed medium grained granite. (sandy fine to coarse gravel.)	
									T2-101	13.60										
									T2-101	13.93										
										15.08										
										15.20										
					15.30															
					15.41															
					22		15.41	IV												
					16.07			III												
					16.07			III												
					17.48			III												
					17.48			III												
					18.58			IV												
					18.70			IV												
					18.82			IV												
					19.22	+7.83	19.22	III												
					19.22			III												
					19.75	+7.05	20.00	III												
					19.75			III												

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ▽ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ▽ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH3
 Sheet: 3 of 3
 Date: 03.01.2015 to 06.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835531.50 N: 815160.32	Rock Corebit: T2-101
Machine Opnr.: WAH		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +27.05 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
06/01											+7.05	20.00	+	ii	Moderately strong to strong, light grey spotted white & black, slightly decomposed medium to coarse grained GRANITE. Joints are medium to widely, occasional closely to very closely spaced, extremely narrow to tight, rough planar, rough undulating, iron stained, chlorite coated dipping at 10-20, 45-60 & 60-70. From 19.22m to 20.00m: moderately strong, light greyish pink, moderately decomposed medium grained granite.
				100	100	100			T2-101		20.74		+		
											21.54		+		
				100	100	96			T2-101		22.44		+		
							10.6						+		
				100	100	83	4.8		T2-101		23.89		+		
													+		
				100	100	100			T2-101		24.68		+		End of hole at depth of 24.68m.

- | | |
|---|---|
| <ul style="list-style-type: none"> ● Small disturbed sample ⬇ Large disturbed sample ▨ SPT liner sample ■ U100 undisturbed sample ▩ Mazier sample P/S Piston sample | <ul style="list-style-type: none"> ⊗ Water table ↓ Standard Penetration Test ⊙ Permeability test ⬆ Piezometer tip ⬆ Standpipe tip ⊗ Vane shear test |
|---|---|

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH4
 Sheet: 2 of 3
 Date: 24.12.2014 to 31.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835524.98 N: 815165.78	Rock Corebit: T2-101
Machine Optr.: WAH		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +29.95 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description	
									No.	Type						
27/12	1.30m PM	Dry AM		100	100	100	0.8		T2-101	10.14	+19.95 +19.81	10.00 10.14	+	IV	See sheet 1 of 3 for details.	
29/12				100	100	100			T2-101	11.10			+	II	Strong, light grey spotted white & black, slightly decomposed medium to coarse GRANITE. Joints are widely, occasional very closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-30. (CORESTONE) From 13.77m to 13.87m: moderately strong, moderately decomposed.	
				100	100	100			T2-101	11.70			+			
				100	100	100			T2-101	12.36			+			
		100	100	97			T2-101	13.78			+					
29/12	4.60m PM	12.00m AM		100				50/30mm,200/40mm ↓ N=200/40mm	12 ● 14.00 13 ▨ 14.20 14 ● 14.80		+16.08	13.87	○	IV	Very weak, dark greyish brown spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.)	
30/12										15.13		+14.82	15.13	+	III	Moderately strong, light greyish brown & dark brown spotted white & black, moderately decomposed medium to coarse GRANITE. Joints are medium to very closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-20, 45-60. (CORESTONE)
				100	92	78	6.8		T2-101	16.80		+13.51	16.44	+	IV	Very weak, dark brownish grey spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.) From 16.44m to 16.54m: very weak, highly decomposed with non-intact. From 19.61m to 19.65m: very weak to moderately weak, highly decomposed.
				0				50/50mm,200/70mm ↓ N=200/70mm	16 ▨ 18.70 17 ● 18.80 17 ● 19.00 17 ● 19.07				○			
				100	100	97	1.8	50/30mm,200/40mm ↓ N=200/40mm	T2-101	19.51		+10.34	19.61	+	II	See sheet 3 of 3 for details.
									T2-101	19.95		+9.95	20.00	+		

- Small disturbed sample
- ▨ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▨ Mazier sample
- P/S Piston sample
- ▽ Water table
- ↓ Standard Penetration Test
- Permeability test
- ↑ Piezometer tip
- ⊠ Standpipe tip
- ▽ Vane shear test

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH4
 Sheet: 3 of 3
 Date: 24.12.2014 to 31.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: T2-101

E: 835524.98

Machine Opnr.: WAH

N: 815165.78

Hole Dia: PX/HX

Flushing Medium: WATER

Orientation: VERTICAL

Ground Level: +29.95 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
	HX										+9.95	20.00	+ + +	II	Moderately strong to strong, light grey spotted white & black, slightly decomposed medium to coarse GRANITE. Joints are medium to closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-30, 45-60 & 60-70. From 22.23m to 22.46m: no recovery, assumed to be highly decomposed.
				83	83	82		↑				21.11	+ + +		
							NA					22.23 22.46	+ + +	IV	Wash boring, assumed to be highly decomposed.
30/12		3.80m PM									+7.49	22.83	+ + +		
31/12		12.10m AM		100	98	76	5.2				+7.12	23.10	+ + +	III II	Moderately strong to strong, light grey spotted white & black, slightly decomposed medium to coarse GRANITE. Joints are medium to widely, occasional closely to very closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-30, 45-60. From 22.83m to 23.10m, 25.80m to 26.70m: moderately strong, moderately decomposed.
							2.6					23.61	+ + +		
												25.13	+ + +		
				100	100	100						25.80	+ + +	III	
												26.53	+ + +		
				100	100	100						26.70	+ + +	II	
31/12							2.0					28.05	+ + +		End of hole at depth of 28.05m.

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▨ Mozier sample
- P/S Piston sample
- ⚡ Water table
- ⬇ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ⚡ Vane shear test

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH5
 Sheet: 2 of 3
 Date: 08.01.2015 to 10.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:
 E: 835537.88
 N: 815156.19

Rock Corebit: T2-101

Machine Optr.: WAH

Hole Dia: PX/HX

Flushing Medium: WATER

Orientation: VERTICAL

Ground Level: +24.18 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
				90					17	U100	+14.18	10.00		V	See sheet 1 of 3 for details.
				90				4,8,10,13,16,19 N=58	18	U100		11.10			
									19	U100		11.50			
									20	U100	+12.18	12.00		IV	Very weak, light yellowish brown spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.)
									21	U100		11.95			
									22	U100		12.00			
				100	96	47	10.0			T2-101	+10.79	13.39		III	Moderately strong, light brownish grey & grey spotted white & black, moderately decomposed medium to coarse grained GRANITE. Joints are medium to very closely spaced, extremely narrow to very narrow, rough planar, rough undulating, iron stained, kaolin coated, dipping at 10-20, 45-60 & subvertical.
				100	65	65	4.2			T2-101		13.99			
								50/30mm,200/60mm N=200/60mm				15.29		IV	From 15.29m to 15.80m: very weak, dark grey spotted white, highly decomposed medium to coarse grained granite. (sandy fine to coarse gravel.)
												15.40			
												15.80		III	
				61	55	40	9.5			T2-101	+7.75	16.43		IV	Very weak, dark brown spotted white & black, highly decomposed medium to coarse grained GRANITE. (sandy fine to coarse GRAVEL.)
												16.83		III	
				32	32	32	>20			T2-101		16.98		IV	From 16.43m to 16.83m, 16.98m to 17.30m & 17.84m to 17.98m: no recovery, assumed to be highly decomposed. From 16.83m to 16.98m: moderately strong, moderately decomposed.
								50/50mm,200/70mm N=200/70mm				17.30			
												17.40			
												17.52			
												17.74			
09/01		2.60m PM		42	21	0	NI			T2-101	+6.20	17.84		IV	
10/01		11.60m AM					NR					17.98			
				100	100	58	4.2			T2-101				III	Moderately strong to strong, light pinkish grey & grey spotted white & black, moderately decomposed medium to coarse grained GRANITE. Joints are medium to closely, occasional closely spaced, extremely narrow, rough planar, rough undulating, iron stained, chlorite coated dipping at 10-20, 45-60 & occasional subvertical.
												19.18			
				100	100	69	11.3			T2-101					
												20.00			

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ⬇ Water table
- ⬇ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ⬇ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: DH5
 Sheet: 3 of 3
 Date: 08.01.2015 to 10.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835537.88 N: 815156.19	Rock Corebit: T2-101
Machine Opnr.: WAH		Hole Dia: PX/HX
Flushing Medium: WATER	Orientation: VERTICAL	Ground Level: +24.18 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
10/01				100	100	92	3.4		T2-101	20.21	+4.18	20.00	+	III	See sheet 2 of 3 for details.
									T2-101	21.53		20.30	+	II	
				100	100	100	4.7		T2-101	23.01	+1.17	23.01	+		End of hole at depth of 23.01m.

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ▼ Water table
- ↓ Standard Penetration Test
- ⊙ Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ▼ Vane shear test

Logged by: C.B. LEE
 Date: 12-01-2015
 Checked by: LIU
 Date: 13-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: HC1
 Sheet: 1 of 1
 Date: 29.12.2014 to 29.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

E: 835529.58

Machine Optr.: KO

N: 815175.28

Hole Dia: HX

Flushing Medium: WATER

Orientation: HORIZONTAL

Ground Level: +22.21 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type Depth					
29/12	HX			100					4"	0.35	+22.21	0.00			Red, Brick fragments. (Brick Wall)
				92					4"	1.00	+21.86	0.35			From 0.00m to 0.06m: grey, concrete. (Brick wall surface)
									1	1.00 1.10	+21.21	1.00			Angular COBBLE & coarse gravel sized concrete & brick fragments. (FILL)
									2	1.50 1.60	+20.71	1.50			Loose, dark brown, clayey silty fine to coarse SAND with some angular fine to coarse gravel. (FILL)
29/12									3	2.00 2.10	+20.11	2.10			Loose, dark grey, very clayey fine to coarse SAND with some angular fine to coarse gravel. (FILL)
End of hole at depth of 2.10m.															

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 31-12-2014
 Checked by: LIU
 Date: 31-12-2014

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: HC2
 Sheet: 1 of 1
 Date: 30.12.2014 to 30.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

Machine Optr.: KO

E: 835532.96

Hole Dia: HX

N: 815171.88

Flushing Medium: WATER

Orientation: HORIZONTAL

Ground Level: +22.14 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description	
									No.	Type Depth						
30/12	HX			100					4"	0.40	+22.14	0.00			Red, Brick fragments. (Brick Wall)	
				100						0.60	+21.74	0.40			From 0.00m to 0.06m: grey, concrete. (Brick wall surface)	
				93						4"	1.10	+21.54	0.60			Grey, concrete. (Concrete wall?)
				91						3"	1.70					Angular COBBLE & coarse gravel sized concrete & brick fragments. (FILL)
				69						1	1.70					
29/12									3"	2.00	+20.14	2.00			Loose, dark brown, clayey fine to coarse SAND with some angular fine to coarse gravel. (FILL)	
									2	2.10	+20.04	2.10			End of hole at depth of 2.10m.	

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 31-12-2014
 Checked by: LIU
 Date: 31-12-2014

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: HC3
 Sheet: 1 of 1
 Date: 02.01.2015 to 02.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

E: 835534.31

Machine Optr.: KO

N: 815170.54

Hole Dia: HX

Flushing Medium: WATER

Orientation: HORIZONTAL

Ground Level: +21.74 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type/Depth					
02/01	HX			94					4"	0.40	+21.74	0.00			Red, Brick fragments. (Brick Wall)
				42					4"	1.00	+21.34	0.40			From 0.00m to 0.06m: grey, concrete. (Brick wall surface)
				32					4"	1.80	+20.74	1.00			Angular COBBLE & coarse gravel sized concrete & brick fragments. (FILL)
									1	2.20	+20.24	1.50			Angular COBBLE & coarse gravel sized concrete, rock & refuse fragments. (FILL)
02/01								2		+19.54	2.20			Loose, dark greyish brown, silty gravelly fine to coarse SAND. (FILL)	
														End of hole at depth of 5.20m.	

- Small disturbed sample
- ⚡ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▨ Mozier sample
- P/S Piston sample
- ▼ Water table
- ↓ Standard Penetration Test
- Permeability test
- ↑ Piezometer tip
- ⊕ Standpipe tip
- ▼ Vane shear test

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: HC4
 Sheet: 1 of 1
 Date: 31.12.2014 to 31.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

E: 835523.80

Hole Dia: HX

N: 815167.87

Machine Opnr.: KO

Orientation: HORIZONTAL

Ground Level: +29.18 mPD

Flushing Medium: WATER

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type Depth					
31/12	HX			100					4"		+29.18	0.00			Angular BOULDER sized moderately decomposed granite. (MASONRY WALL)
				79					4"						
										1 ● 1.20		+28.08	1.10	[Cross-hatch pattern]	
31/12									2 ● 1.50						Extremely weak, light pinkish brown spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
									3 ● 2.20		+27.18	2.00	[Dotted pattern]	V	
											+26.98	2.20			End of hole at depth of 2.20m.

- Small disturbed sample
- ⬇ Large disturbed sample
- [Cross-hatch] SPT liner sample
- [Solid black] U100 undisturbed sample
- [Dotted] Mazier sample
- P/S Piston sample
- ∇ Water table
- ⬇ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: HC5
 Sheet: 1 of 1
 Date: 31.12.2014 to 31.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835532.17 N: 815180.04	Rock Corebit: 4"
Machine Optr.: KO		Hole Dia: HX
Flushing Medium: WATER	Orientation: HORIZONTAL	Ground Level: +20.24 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Depth (m)	Legend	Grade	Description
									No.	Type				
31/12	HX			100					4"		0.00			V Red, Brick fragments. (Brick Wall) From 0.00m to 0.06m: grey, concrete. (Brick wall surface) Extremely weak, light yellowish brown spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.) End of hole at depth of 1.80m.
									1	0.13 0.30 0.40	+20.24 +20.11	0.13		
31/12									2	0.90 1.08	+19.16	1.08		

- | | |
|---|---|
| <ul style="list-style-type: none"> ● Small disturbed sample ⬇ Large disturbed sample ▨ SPT liner sample ■ U100 undisturbed sample ▩ Mazier sample P/S Piston sample | <ul style="list-style-type: none"> ∇ Water table ↓ Standard Penetration Test ● Permeability test ⬆ Piezometer tip ⬆ Standpipe tip ∇ Vane shear test |
|---|---|

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: ICH1
 Sheet: 1 of 1
 Date: 27.12.2014 to 27.11.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

E: 835529.15

Machine Opnr.: KO

N: 815175.71

Hole Dia: HX

Flushing Medium: WATER

Orientation: 45° DOWNWARD

Ground Level: +21.50 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type Depth					
27/12	HX			100					4"		+21.50	0.00			Red, Brick fragments. (Brick Wall)
									1	0.50	+20.90	0.60			From 0.00m to 0.06m: Grey, concrete. (Brick wall surface)
									2	1.00 1.10	+20.50	1.00		V	Loose, dark greyish brown, silty fine to coarse SAND. (FILL)
									3	1.50 1.60					Extremely weak to very weak, light pinkish brown spotted white & black, completely decomposed medium grained GRANITE. (gravelly silty fine to coarse SAND.)
27/12									4	2.00 2.10	+19.50 +19.40	2.00 2.10		IV	Very weak, dark brownish grey spotted white & black, highly decomposed medium grained GRANITE. (Very sandy fine to coarse GRAVEL.)
															End of hole at depth of 2.10m.

- | | |
|---------------------------|-----------------------------|
| ● Small disturbed sample | ▽ Water table |
| ⬇ Large disturbed sample | ↓ Standard Penetration Test |
| ▨ SPT liner sample | ● Permeability test |
| ■ U100 undisturbed sample | ⬆ Piezometer tip |
| ▩ Mazier sample | ⬆ Standpipe tip |
| P/S Piston sample | ▽ Vane shear test |

Logged by: C.B. LEE
 Date: 26-12-2014
 Checked by: LIU
 Date: 27-12-2014

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: ICH2
 Sheet: 1 of 1
 Date: 29.12.2014 to 30.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835532.54 N: 815172.31	Rock Corebit: 4"
Machine Opnr.: KO		Hole Dia: HX
Flushing Medium: WATER	Orientation: 45° DOWNWARD	Ground Level: +21.48 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description	
									No.	Type Depth						
29/12	HX			100					4"		+21.48	0.00	+	I	Red, Brick fragments. (Brick Wall)	
									1	0.60 0.70	+20.88	0.60	+		V	From 0.00m to 0.06m: grey, concrete. (Brick wall surface)
29/12										2	1.00 1.10			+	V	Extremely weak, light yellowish brown spotted white & black, completely decomposed medium grained GRANITE. (silty gravelly fine to coarse SAND.)
30/12										3	1.60 1.72	+19.76	1.72	+		
30/12				100	100	82	8.6		4"		+19.41	2.07	+	III	Moderately strong, light grey spotted white & black, moderately decomposed medium grained GRANITE. Joints are medium to closely spaced, extremely narrow, rough planar, rough undulating, iron stained, dipping at 10-20, 35-60. (Corestone) End of hole at depth of 2.07m.	

- Small disturbed sample
- ⬆ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 31-12-2014
 Checked by: LIU
 Date: 31-12-2014

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: ICH3
 Sheet: 1 of 1
 Date: 27.12.2014 to 27.12.2014

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY

Co-ordinates:

Rock Corebit: 4"

E: 835536.78

Machine Optr.: KO

N: 815168.06

Hole Dia: HX

Flushing Medium: WATER

Orientation: 45° DOWNWARD

Ground Level: +21.42 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type Depth					
27/12	HX			100					4"		+21.42	0.00	[Brick Wall]		Red, Brick fragments. (Brick Wall)
									1	● 0.60 ● 0.80	+20.82	0.60	[Concrete]		From 0.00m to 0.60m: Grey, concrete. (Brick wall surface)
										2	● 1.00 ● 1.60		[Sand]	V	Extremely weak, light yellowish brown spotted white & black, completely decomposed medium grained GRANITE. (gravelly silty fine to coarse SAND.)
27/12										3	● 1.50 ● 2.10	+19.32	2.10	[End of Hole]	

- Small disturbed sample
- ⬇ Large disturbed sample
- ▨ SPT liner sample
- U100 undisturbed sample
- ▩ Mazier sample
- P/S Piston sample
- ∇ Water table
- ↓ Standard Penetration Test
- ⊙ Permeability test
- ⬆ Piezometer tip
- ⬆ Standpipe tip
- ∇ Vane shear test

Logged by: C.B. LEE
 Date: 26-12-2014
 Checked by: LIU
 Date: 27-12-2014

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: ICH4
 Sheet: 1 of 1
 Date: 02.01.2015 to 02.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835524.18 N: 815167.56	Rock Corebit: 4"
Machine Optr.: KO		Hole Dia: HX
Flushing Medium: WATER	Orientation: 45° DOWNWARD	Ground Level: +28.91 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description
									No.	Type					
02/01	HX			100					4"		+28.91	0.00			Boulder sized moderately decomposed granite. (MASONARY WALL)
									+28.56	0.35		Grey, concrete. (Concrete Wall)			
									+28.16	0.75		Loose, dark brown, clayey silty fine to coarse SAND with some angular fine to coarse gravel sized brick fragments & wooden fragments. (FILL)			
				100					1 ● 1.00						
									2 ● 1.50						
									3 ● 2.00						
02/01											+26.81	2.10			End of hole at depth of 2.10m.

- | | |
|---------------------------|-----------------------------|
| ● Small disturbed sample | ∇ Water table |
| ⬇ Large disturbed sample | ↓ Standard Penetration Test |
| ▨ SPT liner sample | ● Permeability test |
| ■ U100 undisturbed sample | ⬆ Piezometer tip |
| ⊠ Mazier sample | ⬆ Standpipe tip |
| P/S Piston sample | ∇ Vane shear test |

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:

Terraform Engineering (International) Ltd.

Contract No.: _____
 Hole No.: ICH5
 Sheet: 1 of 1
 Date: 03.01.2015 to 03.01.2015

DRILLHOLE RECORD

Project: Ground Investigation Works for Schooner Street Development at I.L.9048

Method: ROTARY	Co-ordinates: E: 835527.17 N: 815165.14	Rock Corebit: 4"
Machine Optr.: KO		Hole Dia: HX
Flushing Medium: WATER	Orientation: 45° DOWNWARD	Ground Level: +27.59 mPD

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	Rock Quality Designation %	Fracture Index	Tests	Samples		Reduced Level (mPD)	Depth (m)	Legend	Grade	Description	
									No.	Type						
03/01	HX			100					4"		+27.59	0.00			Boulder sized moderately decomposed granite. (MASONARY WALL)	
				100					4"		+27.14	0.45	△ △		Grey, concrete. (Concrete Wall)	
										1 ●		+26.77	0.82	V		Extremely weak, light pinkish brown spotted white & black, completely decomposed medium to coarse grained GRANITE. (silty fine to coarse SAND.)
										2 ●						
03/01									3 ●		+25.29	2.30			End of hole at depth of 2.30m.	

- | | |
|---|---|
| <ul style="list-style-type: none"> ● Small disturbed sample ⬇ Large disturbed sample ▨ SPT liner sample ▩ U100 undisturbed sample ▧ Mazier sample P/S Piston sample | <ul style="list-style-type: none"> ▽ Water table ↓ Standard Penetration Test ● Permeability test ⬆ Piezometer tip ⬆ Standpipe tip ▽ Vane shear test |
|---|---|

Logged by: C.B. LEE
 Date: 05-01-2015
 Checked by: LIU
 Date: 06-01-2015

Remarks:



TECHNICAL SUBMISSION FORM

Project Hopewell Centre II Stage of Site Formation & Foundation

Ref. No. COBC/BGZ/B5/2017/03935

Date 09 May 2017

Previous Ref. No. N.A.

To / Attn Hyder / Mr. Brian leong

Subject **Submission of Preliminary Predrilling record for PD1 and PD2 at Nam Koo Terrace**

Anticipated date of response N.A.

We would like to submit the following item/items

For Approval For Record Others



For and on behalf of COBC Ltd.
Chris Tsang (Project Manager)

Received by WMKY

cc w/e
JPO Mr. Bruce Chan / Mr. Jeffrey Kam / Mr. Vincent Chu
WMKY Mr. Peter Mak
AECOM Mr. Sammy Ng / Mr. Alan Yuen
Hyder Ms. Deborah Lui, Mr. Ellis Lam
Site _____
H.O. _____

Material / Work Description *	Predrilling
Location	Nam Koo Terrace
Brand Name	N.A.
Model / Reference No. *	N.A.
Country of Origin	N.A.
Manufacturer / Supplier Name *	N.A.
Others (Color / Pattern, etc.) *	N.A.
Material / Work Reference *	N.A.
Specification Reference	N.A.
Related Dwg. / A.I. Ref. *	991051/RW001
Related BQ Reference	N.A.
Submission Attachment	N.A.
Sample	<input type="checkbox"/> N.A.
Catalogue / Technical Data *	<input checked="" type="checkbox"/> Preliminary Drillhole Record
Test Report / Certificate *	<input type="checkbox"/> N.A.
Equipment Schedule	<input type="checkbox"/> N.A.
Method Statement	<input type="checkbox"/> N.A.
Installation Details	<input type="checkbox"/> N.A.
Job Reference	<input type="checkbox"/> N.A.
Remarks	

Review Status / Comment

Replied by SE / Date

Replied by Architect / Date

Replied by _____ / Date

RESPONSE TO TECHNICAL SUBMISSION

Date
Comments

For and on behalf of
Hyder

Legend: A (No objection)
B (No objection, subject to comments as noted)
C (Amendment & resubmission required)
D (Rejected & resubmission required)

w/e

CT/KW/hwc

cc w/e
JPO Mr. Bruce Chan / Mr. Jeffrey Kam / Mr. Vincent Chu
WMKY _____
AECOM _____
Hyder _____
Site _____
H.O. _____

WING SHING CAISSON & FOUNDATION LTD.

DRILLHOLE RECORD

JOB NO.: _____
 HOLE NO.: PD1
 SHEET: 1 OF 3
 DATE: 27/4/17 TO 29/4/17

PROJECT: Hopewell Centre II Development Hong Kong (Nam Koo Terrace)

METHOD: ROTARY

CO-ORDINATES

ROCK COREBIT: T2-101

MACHINE & NO.: XY-2B

E 835531.256

HOLE DIA.: PX/HX

N 815138.426

FLUSHING MEDIUM: WATER

ORIENTATION: VERTICAL

GROUND LEVEL: +34.25 mPD.

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	R. Q. D.	Fracture Index	Tests	Samples		Reduced Level	Depth (m)	Legend	Grade	Zone	Description
									No.	Type						
27/4	Px										+34.25	0.00				Wash boring
	3.50 Px										+30.75	3.50				Light greyish brown and pink, angular BOULDER and COBBLE sized rock fragments. (FILL)
	Hx		96								+30.29	3.96				
																Wash boring

- Small disturbed sample
- ▲ Water sample
- ⬆ Large disturbed sample
- ▼ Water table
- SPT liner sample
- ↓ Standard penetration test
- U76 undisturbed sample
- ⊙ Permeability test
- U100 undisturbed sample
- ▲ Piezometer tip
- ⊗ Mazier sample
- ⊠ Standpipe
- P/S Piston sample

LOGGED Poon Leung
 DATE 4/5/17
 CHECKED M. Law
 DATE 5/5/17

REMARKS

WING SHING CAISSON & FOUNDATION LTD.

DRILLHOLE RECORD

JOB NO.: _____
 HOLE NO.: PD1
 SHEET: 2 OF 3
 DATE: 27/4/17 TO 29/4/17

PROJECT: Hopewell Centre II Development Hong Kong (Nam Koo Terrace)

METHOD : ROTARY	CO-ORDINATES	ROCK COREBIT: T2-101
MACHINE & NO.: XY-2B	E 835531.256 N 815138.426	HOLE DIA.: PX/HX
FLUSHING MEDIUM: WATER	ORIENTATION: VERTICAL	GROUND LEVEL: +34.25 mPD.

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	R. Q. D.	Fracture Index	Tests	Samples		Reduced Level	Depth (m)	Legend	Grade	Zone	Description
									No.	Type						
	Hx															Wash boring
	15.41 Hx															
			100	100	100					T2-101	15.41	15.41	+			Strong, greyish pink, spotted with black, slightly decomposed coarse grained GRANITE with widely to very widely spaced, rough planar, very narrow to extremely narrow, iron stained joints, dipping at 0°f-10° & 10°-20°.
			100	100	100					T2-101	15.85		+			
			100	100	100					T2-101	17.22		+			
			100	100	100	0.9				T2-101	18.52		+	II		
			100	100	100					T2-101	19.67		+			
			100	100	100					T2-101	20		+			

- Small disturbed sample
- ⬆ Large disturbed sample
- SPT liner sample
- U76 undisturbed sample
- U100 undisturbed sample
- ⊠ Mazier sample
- P/S Piston sample
- ▲ Water sample
- ⊗ Water table
- ↓ Standard penetration test
- ⊙ Permeability test
- ▲ Piezometer tip
- ⊠ Standpipe

LOGGED Poon Leung
 DATE 4/5/17
 CHECKED M. Law
 DATE 5/5/17

REMARKS

WING SHING CAISSON & FOUNDATION LTD.

DRILLHOLE RECORD

JOB NO.: _____
 HOLE NO.: PD1
 SHEET: 3 OF 3
 DATE: 27/4/17 TO 29/4/17

PROJECT: Hopewell Centre II Development Hong Kong (Nam Koo Terrace)

METHOD: ROTARY

CO-ORDINATES

ROCK COREBIT: T2-101

MACHINE & NO.: XY-2B

E 835531.256

HOLE DIA.: PX/HX

N 815138.426

FLUSHING MEDIUM: WATER

ORIENTATION: VERTICAL

GROUND LEVEL: +34.25 mPD.

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	R. Q. D.	Fracture Index	Tests	Samples		Reduced Level	Depth (m)	Legend	Grade	Zone	Description
									No.	Type						
29/4			100	100	100	0.9			T2-101		20.72	+13.53	20.72	+	II	As sheet 2 of 3
																End of hole at 20.72m.

- Small disturbed sample
- ▲ Large disturbed sample
- SPT liner sample
- U76 undisturbed sample
- U100 undisturbed sample
- ☒ Mazier sample
- P/S Piston sample
- ▲ Water sample
- ▽ Water table
- ↓ Standard penetration test
- ⊙ Permeability test
- ▲ Piezometer tip
- △ Standpipe

LOGGED Poon Leung
 DATE 4/5/17
 CHECKED M. Law
 DATE 5/5/17

REMARKS

WING SHING CAISSON & FOUNDATION LTD.

DRILLHOLE RECORD

JOB NO.: _____
 HOLE NO.: PD2
 SHEET: 1 OF 3
 DATE: 22/4/17 TO 25/4/17

PROJECT: Hopewell Centre II Development Hong Kong (Nam Koo Terrace)

METHOD: ROTARY

CO-ORDINATES

ROCK COREBIT: T2-101

MACHINE & NO.: XY-2B

E 835536.096

HOLE DIA.: PX/HX

N 815138.085

FLUSHING MEDIUM: WATER

ORIENTATION: VERTICAL

GROUND LEVEL: +33.55 mPD.

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	R. Q. D.	Fracture Index	Tests	Samples			Reduced Level	Depth (m)	Legend	Grade	Zone	Description
									No.	Type	Depth						
22/4	Px 4.00 Hx										+33.55	0.00					Wash boring

- Small disturbed sample
- ⬆ Large disturbed sample
- SPT liner sample
- U76 undisturbed sample
- U100 undisturbed sample
- ☑ Mazier sample
- P/S Piston sample
- ▲ Water sample
- ▾ Water table
- ↓ Standard penetration test
- ⊙ Permeability test
- ▲ Piezometer tip
- ⊕ Standpipe

LOGGED Poon Leung

DATE 4/5/17

CHECKED M. Law

DATE 5/5/17

REMARKS

WING SHING CAISSON & FOUNDATION LTD.

DRILLHOLE RECORD

JOB NO.: _____
 HOLE NO.: PD2
 SHEET: 3 OF 3
 DATE: 22/4/17 TO 25/4/17

PROJECT: Hopewell Centre II Development Hong Kong (Nam Koo Terrace)

METHOD: ROTARY

CO-ORDINATES

ROCK COREBIT: T2-101

MACHINE & NO.: XY-2B

E 835536.096

HOLE DIA.: PX/HX

N 815138.085

FLUSHING MEDIUM: WATER

ORIENTATION: VERTICAL

GROUND LEVEL: +33.55 mPD.

Drilling Progress	Casing Depth/Size	Water Level/Time	Water Recovery %	Total Core Recovery %	Solid Core Recovery %	R. Q. D.	Fracture Index	Tests	Samples		Reduced Level	Depth (m)	Legend	Grade	Zone	Description
									No.	Type Depth						
25/4			100	100	100	2.0			T2-101			20	+			As sheet 2 of 3
			100	100	100				T2-101	20.57			+			
			100	92	92	3.4			T2-101	20.79			+			
									T2-101	21.45			+	II		
			100	100	100	1.4			T2-101				+			
										22.85	+10.70	22.85	+			End of hole at 22.85m.

- Small disturbed sample
- ⬆ Large disturbed sample
- SPT liner sample
- U76 undisturbed sample
- U100 undisturbed sample
- ⊗ Mazier sample
- P/S Piston sample
- ▲ Water sample
- ▾ Water table
- ↓ Standard penetration test
- ⊙ Permeability test
- ⬆ Piezometer tip
- ⊠ Standpipe

LOGGED Poon Leung

DATE 4/5/17

CHECKED M. Law

DATE 5/5/17

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH1P
 SHEET 1 of 3
 DATE from 03/05/2000 to 06/05/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, L.L.2140

METHOD Rotary	CO-ORDINATES	CONTRACT NO.
RIG NO. R-4	E 835,512.56 N 815,122.94	ROCK CORE BIT T2101
FLUSHING MEDIUM	ORIENTATION Vertical	GROUND-LEVEL +47.12 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
03/05/2000	PX								INSPECTION PIT					Loose to medium dense, greyish brown, clayey SILT with occasional, subangular to subrounded, fine to medium gravel sized rock fragments. (FILL)
				85					1.1 2.1 3.2 4.3					
	PX 3.80 HX			0					5.4 6.5	43.32	3.80			Subangular to subrounded, COBBLE sized, occasionally gravel sized, fragments of moderately strong to strong, pinkish grey granite and concrete. (EXISTING WALL)
				77					7.6 8.7					Extremely weak, greyish brown spotted with black, completely decomposed medium-grained GRANITE. (Silty SAND with occasional, rock fragments)
				0					9.8 10.9	42.57	4.55		V	
				100					11.0 12.1	41.32	5.80		III/IV	Moderately strong to strong, pinkish grey, moderately to slightly decomposed, medium-grained GRANITE. (CORESTONE) Joints are widely spaced, narrow to very narrow, rough undulating, dipping at 10° to 20° and 50° to 60°
		6.32m at 18:00 Dry at 08:00		90		100	100	2.1	13.2 14.3	40.37	6.75		V	Extremely weak, greyish to yellowish brown, spotted with black, completely decomposed medium-grained GRANITE. (Silty SAND with occasional rock fragments)
03/05/2000 04/05/2000				100					15.4 16.5					
									17.6 18.7					

- Small Disturbed Sample
- Large Disturbed Sample
- ▨ SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▨ U100 Undisturbed Sample
- ▨ Mazier Sample
- ▨ Piston Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ∇ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 08/05/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS
 1. Inspection pit 1.50m deep.
 2. Standpipe installed at depth 18.64m.

JOB NO. TFGS251/2000
 HOLE NO. BH1P
 SHEET 2 of 3
 DATE from 03/05/2000 to 05/05/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES	CONTRACT NO.
RIG NO. <u>R-4</u>	<u>E 835,512.55</u> <u>N 815,122.94</u>	ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+47.12 mP.D.</u>

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
									18 18.25					SAME AS SHEET 1 OF 3.
				85				19 10.75						
				100			N.I.	20 11.16 21 11.20		34.92	12.20			
		11.93m at 18:00 Dry at 08:00		100	88	85	2.1	22 12.15		34.77	12.35	+	II	Strong, pinkish grey, slightly decomposed medium-grained GRANITE. Joints are closely spaced, very narrow, rough undulating, iron stained, dipping at 10° to 20°. From 12.20m to 12.35m: Moderately decomposed.
				100				23 13.23 24 13.45 25 13.50		33.82	13.30	+	V	Extremely weak, yellowish to pinkish brown, completely decomposed medium-grained GRANITE. (Silty SAND with fine to coarse gravel sized of rock fragment.)
				100				27 18.50						
				85				30 17.50						
				100				31 18.55 32 18.67						
		HX 19.14		100	93	85	3.4	33 19.14		27.98	19.14	+	III	Strong, pinkish grey, slightly decomposed medium-grained GRANITE. Joints are medium spaced, very narrow to extremely narrow, rough undulating, iron stained, dipping at 20° to
<ul style="list-style-type: none"> • Small Disturbed Sample • Large Disturbed Sample • SPT Liner Sample • U76 Undisturbed Sample • U100 Undisturbed Sample • Mixer Sample • Piston Sample ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Permeability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ∨ In-situ Vane Shear Test 										LOGGED <u>W.K. Ngan</u>	REMARKS			
										DATE <u>08/05/2000</u>				
										CHECKED <u>C.P. Hamilton</u>				
										DATE <u>16/05/2000</u>				

JOB NO. TFGS251/2000
 HOLE NO. BH1P
 SHEET 3 of 3
 DATE from 03/05/2000 to 06/05/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,512.56
N 815,122.94

ROCK CORE BIT T2101

FLUSHING MEDIUM

ORIENTATION Vertical


GROUND-LEVEL +47.12 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.O.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
				100	100	100	0.0		20.50			+		30° and 40° to 50°. From 19.14m to 19.54m; Moderately decomposed.
				100	100	89	2.9		21.50			+		From 22.59m to 24.18m; Fine-grained, occasionally medium-grained.
		16.10m at 18:00		100	100	83	5.1		23.20			+		From 23.88m to 23.95m; Pegmatitic.
		14.77m at 08:00							24.10	22.94	24.18			END OF DRILLHOLE AT 24.18m.
		17.02m at 11:00												

- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▦ Piston Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ∇ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 08/05/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

JOB NO. TFGS251/2000 **DRILLHOLE RECORD** Terraform-FGS 

HOLE NO. BH2P

SHEET 1 of 3

DATE from 20/04/2000 to 29/04/2000

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary CO-ORDINATES E 835,512.47 CONTRACT NO.

RIG NO. R-4 N 815,129.73 ROCK CORE BIT T2101

FLUSHING MEDIUM ORIENTATION Vertical GROUND-LEVEL +46.58 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
20/04/2000	PX								1	44.08	0.50			Loose, greyish brown, clayey SILT with occasional, subangular to subrounded, fine to medium gravel sized, quartz fragments and rootlets. (FILL)
		Dry at 18:00							2	45.08	1.50			Loose, reddish brown, sandy SILT with occasional, subangular to subrounded, fine to medium gravel sized rock fragments. (FILL)
		Dry at 08:00							3	45.08	1.50		V	Extremely weak, reddish to greyish brown, spotted with black, completely decomposed medium-grained GRANITE. (Silty fine to coarse SAND with occasional, subangular to subrounded, fine to medium gravel sized, quartz and rock fragments.)
	PX 2.45 HX			100	100	90	3.6		4	44.13 44.04 43.70 43.02	2.45 2.54 2.88 2.56		III/VI III/VI III/VI	Moderately strong to strong, pinkish grey spotted with black, moderately to slightly decomposed medium-grained GRANITE. (CORESTONE) Joints are medium spaced, rough undulating, narrow to very narrow, brown iron stained, dipping at 40° to 50° and 60° to 70°.
				85				11 12 13	5	43.18 43.03	3.40 3.55		V	From 2.45m to 2.54m: Moderately decomposed. From 2.88m to 2.86m: Moderately decomposed. From 3.40m to 3.55m: Moderately decomposed. Extremely weak, yellowish to greyish brown spotted with black, completely decomposed medium-grained GRANITE. (Silty fine to coarse SAND with occasional, fine to medium gravel sized rock fragments.)
				90				14 15	6	5.95 6.00				
		6.13m at 18:00						16 17	7	7.05 7.35 7.55 8.00				
		Dry at 08:00		90				18 19	8	9.55 9.70				

* Small Disturbed Sample ▲ Water Sample
 : Large Disturbed Sample | Impression Packer Survey
 SPT Liner Sample | Standard Penetration Test
 U76 Undisturbed Sample | Permeability Test
 U100 Undisturbed Sample | Piezometer Tip
 Mazer Sample | Standpipe Tip
 Piston Sample v In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 08/05/2000
 CHECKED G.P. Hamilton
 DATE 16/05/2000

REMARKS
 1. Inspection pit 1.50m deep.
 2. Standpipe installed at depth 18.13m.

JOB NO. TFGS251/2000
 HOLE NO. BH2P
 SHEET 2 of 3
 DATE from 20/04/2000 to 29/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,512.47

ROCK CORE BIT T2101

N 815,129.73

FLUSHING MEDIUM

ORIENTATION Vertical

GROUND-LEVEL +46.58 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
			100						18					SAME AS SHEET 1 OF 3.
									19					
									20	11.05				Extremely weak, grayish to pinkish brown, spotted with black, completely decomposed medium-grained GRANITE. (Silty fine to coarse SAND with occasional, fine to medium gravel sized rock fragments.)
									21	11.55				
			100						22	11.85	34.58	12.00	V	
									23	12.00				
									24	12.05				
									25	12.55				
		12.10m at 18:00 Dry at 08:00							26	13.15				
			100						27	14.85				
									28	16.84				
									29	15.83				
			90						30	15.90				
									31	16.00				
									32	17.06				
									33	17.58				
									34	17.28	28.45	18.13		
			100			87	75	7.5	35	18.00			II	Strong, pinkish grey, slightly decomposed medium-grained GRANITE. Joints are medium to closely spaced, rough undulating, very narrow to extremely narrow, iron stained and chlorite coated, dipping at 10° to 20°, 20° to 30° and 40° to 50°. From 18.33m to 18.85m: Fine-grained granite, occasionally medium-grained. From 19.06m to 19.44m: Pegmatitic.
		15.60m at 18:00				100	53	6.3		19.06				
		16.50m								19.50				

- ▲ Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▦ Piston Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ⊥ in-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 08/05/2000
 CHECKED C.P. Hamilton
 DATE 18/05/2000

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH2P
 SHEET 3 of 3
 DATE from 20/04/2000 to 29/04/2000








DRILLHOLE RECORD








Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES	CONTRACT NO.
RIG NO. <u>R-4</u>	<u>E 835,512.47</u> <u>N 815,129.73</u>	ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+46.58 mP.D.</u>

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
		08:00		100	100	100	1.4					+		From 20.62m to 21.16m: Fine-grained granite, occasionally medium-grained.
				100	100	91	1.7			21.23		+		From 22.21m to 22.70m: Fine-grained granite, occasionally medium-grained.
				100	100	100	0.0			22.48		+		From 22.48m to 22.86m: Fine-grained granite, occasionally medium-grained.
		13.10m at 18:00								23.28	23.30	+		END OF DRILLHOLE AT 23.28m.

-  Small Disturbed Sample
-  Large Disturbed Sample
-  SPT Liner Sample
-  U75 Undisturbed Sample
-  U100 Undisturbed Sample
-  Mazier Sample
-  Piston Sample

-  Water Sample
-  Impression Packer Survey
-  Standard Penetration Test
-  Permeability Test
-  Piezometer Tip
-  Standpipe Tip
-  In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 08/05/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH3P
 SHEET 1 of 3
 DATE from 12/04/2000 to 18/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES	CONTRACT NO.
RIG NO. <u>R-4</u>	<u>E 835,536.54</u> <u>N 815,136.25</u>	ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+33.61 mP.D.</u>


Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
12/04/2000	PX								1 INSPECTION PIT 0.45					Firm, dark greyish brown, slightly clayey, sandy SILT with occasional, rock fragments and dark brown to black, organic material. (FILL)
				90					2 0.95					
									3 1.45	32.11	1.50			
									4 1.50					Loose, light greyish brown, slightly clayey silty SAND with occasional, fine to medium gravel sized, rock fragments and quartz. (FILL)
		2.80m at 18:00							5 2.55					
12/04/2000		2.70m at 13:00		90					6 2.60					
13/04/2000	PX 500 HX								7 3.00					
		2.95m at 18:00							8 3.50					
		2.70m at 13:00							9 4.55					
									10 5.00					
13/04/2000		2.95m at 18:00							11 5.50					
14/04/2000		5.15m at 08:00		100					12 5.60					
									13 6.55					
									14 6.60					
									15 7.00					
									16 7.50					
				85					17 8.55					
									18 2.60					
									19 3.00					
									20 3.50					

<ul style="list-style-type: none"> ● Small Disturbed Sample ■ Large Disturbed Sample ▨ SPT Liner Sample ▩ U76 Undisturbed Sample ▩ U100 Undisturbed Sample ▩ Mazier Sample ▩ Piston Sample 	<ul style="list-style-type: none"> ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Penneability Test ⊥ Piezometer Tip ⊥ Standpipe Tip v In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>20/04/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>18/05/2000</u>
---	--	---

REMARKS
 1. Inspection pit 1.50m deep.
 2. Standpipe installed at depth 17.92m.

JOB NO. TFGS251/2000
 HOLE NO. BH3P
 SHEET 2 of 3
 DATE from 12/04/2000 to 18/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, LL.2140		CONTRACT NO.	
METHOD Rotary	CO-ORDINATES		ROCK CORE BIT T2101
RIG NO. R-4	E 835,536.54 N 815,136.25		GROUND-LEVEL +33.61 mP.D.
FLUSHING MEDIUM	ORIENTATION Vertical		

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.C.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
														SAME AS SHEET 1 OF 3.
		11.32m at 18:00		100					20	10.55	23.01	10.60	V	Extremely weak, reddish brown to yellowish brown, mottled with white and spotted with black, completely decomposed medium-grained GRANITE. (Silty SAND with occasional, fine gravel sized quartz fragments.)
		8.13m at 08:00		85				21	10.60					
								22	11.55					
								23	11.70					
								24	12.10					
								25	12.60					
								26	13.65					
								27	13.70					
								28	14.10					
								29	14.60					
				100				30	15.65					
								31	16.70					
								32	16.10					
				90				33	16.80					
								34	17.65					
								35	17.72	15.69	17.92		II	Strong, pinkish grey spotted with black, slightly decomposed medium-grained GRANITE. Joints are medium to widely spaced, rough undulating, extremely narrow to very narrow, brown iron stained and chlorite coated, dipping at 20° to 30°, 40° to 50° and 50° to 60°.
				100	100	2.3								
				100	100	0.0								
		11.82m at 18:00												
		11.80m at												
				100	100					13.61	20.00			

<ul style="list-style-type: none"> Small Disturbed Sample Large Disturbed Sample SPT Liner Sample U76 Undisturbed Sample U100 Undisturbed Sample Mazzer Sample Piston Sample 	<ul style="list-style-type: none"> Water Sample Impression Packer Survey Standard Penetration Test Permeability Test Piezometer Tip Standpipe Tip In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>20/04/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	--	---

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH3P
 SHEET 3 of 3
 DATE from 12/04/2000 to 18/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140		
METHOD Rotary	CO-ORDINATES E 835,536.54 N 815,136.25	CONTRACT NO.
RIG NO. R-4		ROCK CORE BIT T2101
FLUSHING MEDIUM	ORIENTATION Vertical	GROUND-LEVEL +33.61 m.P.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.O.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
		08:00	100											
		10.32m at 18:00			100	100	4.3							
		11.86m at 08:00	100											
		10.95m at 12:00			100	100	0.0							
										22.92	10.69	22.92		END OF DRILLHOLE AT 22.92m.


- Small Disturbed Sample
- Large Disturbed Sample
- ▨ SPT Liner Sample
- ▩ U75 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▩ Mazier Sample
- ▩ Piston Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ⊥ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 20/04/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH4
 SHEET 1 of 3
 DATE from 07/04/2000 to 11/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,537.74

ROCK CORE BIT T2101

N 815,138.16

FLUSHING MEDIUM

ORIENTATION Vertical

GROUND-LEVEL +33.50 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
07/04/2000	PX			88						0.80		△		Light grey, CONCRETE (CONCRETE FLOOR)
				90					1	1.00	32.50	△		Medium dense, yellowish brown to greyish brown, slightly silty fine to coarse SAND with occasional, fine gravel sized quartz and rock fragments. (FILL)
				90					2	1.45		△		
				90					3	1.50		△		
				90					4	2.55		△		
				90					5	2.60		△		
				90					6	3.00		△		
				90					7	3.50		△		
				90					8	4.55		△		
				90					9	4.60		△		
				90					10	5.00		△		
				90					11	5.50		△		
				90					12	6.55		△		
				90					13	6.60		△		
				90					14	7.00		△		
				90					15	7.50		△		
				90					16	8.55		△		
				90					17	8.60		△		
				90					18	8.65		△		
				90					19	8.70		△		
				90					20	8.70		△		

- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▦ Platon Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ⊥ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 12/04/2000
 CHECKED G.P. Hamilton
 DATE 16/05/2000

REMARKS
 1. Inspection pit 1.50m deep.

JOB NO. TFGS251/2000
 HOLE NO. BH4
 SHEET 2 of 3
 DATE from 07/04/2000 to 11/04/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,537.74
N 815,138.16


ROCK CORE BIT T2101

FLUSHING MEDIUM

ORIENTATION Vertical

GROUND-LEVEL +33.50 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.O.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
														SAME AS SHEET 1 OF 3.
				0				1.3 12.13 10-16	16 17 18	16.10 16.15				
									19	16.55 16.63	22.90	10.60	V	Extremely weak, light yellowish brown to reddish brown, mottled with white and spotted with black, completely decomposed medium-grained GRANITE. (Silty fine to coarse SAND with some, subangular to subrounded, fine to medium gravel sized, quartz and rock fragments.)
				100					20 21	11.65 11.70				
								2.5 12.18,13,14 10-16	22 23	12.75 12.80				
				90					24	13.20				
									25	13.70				
								2.7 12.18,14,20 10-16	26 27	14.75 14.80				
									28	15.20				
				90					29	15.70				
		12.60m at 18:00							30	16.75				
		4.90m at 08:00						15.23 15.28 (10/25) (16/23) (10/25)	31 32	16.80 17.10				
				0					33	17.70				
										18.65				
										18.77				
				100						14.73 14.65	18.77	18.65	II	Strong, pinkish grey to grey, spotted with black, slightly decomposed medium-grained GRANITE. Joints are medium to widely spaced, occasionally very closely spaced, rough undulating and smooth planar, extremely narrow to very narrow, brown iron stained and chlorite coated, dipping at 0° to 10°, 20° to 30° and 40° to
		HX 18.77			100	97	1.4			13.50	20.00			
<ul style="list-style-type: none"> ● Small Disturbed Sample ○ Large Disturbed Sample □ SPT Liner Sample ▨ U76 Undisturbed Sample ▩ U100 Undisturbed Sample ▧ Mazier Sample ▦ Piston Sample ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Permeability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ∨ in-situ Vane Shear Test 										LOGGED <u>W.K. Ngan</u> DATE <u>12/04/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>		REMARKS		

JOB NO.	TFGS251/2000	DRILLHOLE RECORD	Terraform-FGS 
HOLE NO.	BH4		
SHEET	3 of 3		
DATE from	07/04/2000 to 11/04/2000		
PROJECT No. 55 Ship Street, Wanchai, I.L.2140			
METHOD	Rotary	CO-ORDINATES	CONTRACT NO.
RIG NO.	R-4	E 835,537.74 N 815,138.16	ROCK CORE BIT T2101
FLUSHING MEDIUM		ORIENTATION Vertical	GROUND-LEVEL +33.50 mP.D.


Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
10/04/2000 17/04/2000		18:00 11.19m at 08:00		100	100	89	4.8		—	20.19		+	ii	50° From 18.77m to 18.85m: Moderately strong, moderately decomposed medium-grained granite.
				100					—	21.03		+		From 20.90m to 21.05m: Pegmatitic granite.
				100	100	91	6.3		—	21.63 21.50	21.63 21.70	+	ii	From 21.63m to 21.70m: Moderately strong to strong, moderately to slightly decomposed medium-grained granite.
				100	100				—	22.46		+		
				100	100		0.0		—	22.86		+		
11/04/2000		12.60m at 18:00			100	100			—	23.77	9.73	+		END OF DRILLHOLE AT 23.77m.

<ul style="list-style-type: none"> ■ Small Disturbed Sample □ Large Disturbed Sample ▨ SPT Liner Sample ▨ U76 Undisturbed Sample ▨ U100 Undisturbed Sample ▨ Mazier Sample ▨ Piston Sample ▲ Water Sample — Impression Packer Survey — Standard Penetration Test — Permeability Test □ Piezometer Tip ▨ Standpipe Tip ∨ In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>12/04/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	---

REMARKS


JOB NO. TFGS251/2000
 HOLE NO. BH5
 SHEET 1 of 3
 DATE from 01/04/2000 to 06/04/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES <u>E 835,539.81</u> <u>N 815,139.60</u>	CONTRACT NO.
RIG NO. <u>R-4</u>		ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+33.60 mP.D.</u>



- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U75 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▩ Piston Sample
- △ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- ⊥ Piezometer Tip
- ⊥ Standpipe Tip
- ∨ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 07/04/2000
 CHECKED G.P. Hamilton
 DATE 16/05/2000

REMARKS
 1. Inspection pit 1.50m deep.

JOB NO. TFGS251/2000
 HOLE NO. BH5
 SHEET 2 of 3
 DATE from 01/04/2000 to 06/04/2000

DRILLHOLE RECORD

Terraform-FGS



PROJECT No. 55 Ship Street, Wanchai, I.L. 2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,539.81
N 815,139.60

ROCK CORE BIT T2101

FLUSHING MEDIUM

ORIENTATION Vertical

GROUND-LEVEL +33.60 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
				100										SAME AS SHEET 1 OF 3.
01/04/2000 02/04/2000		13.60m at 18:00 Dry at 08:00		90				23 2.3, 2.2 70-80	12 13 14 15 16 17 18 19 20 21 22	12.20 14.25 14.50 15.30 18.00 16.85 16.90 17.30 17.20 18.25 18.05 19.40	19.84 13.76	V	Extremely weak, reddish brown mottled with white and spotted with black, completely decomposed medium-grained GRANITE. (Slightly silty SAND with some, fine to coarse gravel sized quartz fragments.)	
	HX 19.40			70				25.50 100% (rockiness)						
				100			9.6				19.40 13.80 13.60	19.40 19.80 20.00	II III	Strong, pinkish grey mottled with white and spotted with black, slightly decomposed medium-grained GRANITE. Joints are medium to widely spaced, locally closely

- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▦ Piston Sample
- ▲ Water Sample
- ┆ Impression Packer Survey
- ┆ Standard Penetration Test
- ┆ Permeability Test
- ┆ Piezometer Tip
- ┆ Standpipe Tip
- ┆ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 07/04/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH5
 SHEET 3 of 3
 DATE from 01/04/2000 to 06/04/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT **No. 55 Ship Street, Wanchai, I.L.2140**

METHOD **Rotary**

CO-ORDINATES

CONTRACT NO.

RIG NO. **R-4**

E 835,539.81

ROCK CORE BIT **T2101**

N 815,139.60

FLUSHING MEDIUM

ORIENTATION **Vertical**

GROUND-LEVEL **+33.60 mP.D.**

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
		Dry at 18:00 13.32m at 08:00		100	63	30	8.0			13.19	20.47	+	III	spaced, smooth planar and rough undulating, extremely narrow, brown iron stained, dipping at 10° to 20°, 30° to 40° and 60° to 70°. From 19.8m to 20.47m: Moderately decomposed.
				100	100	91	2.1			20.30		+	II	
				100						22.31		+		
				100						23.71		+		
		12.92m at 13:00		100	100	100	0.0			24.57	9.03	+		
														END OF DRILLHOLE AT 24.57m.


- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- U76 Undisturbed Sample
- U100 Undisturbed Sample
- Mazier Sample
- Piston Sample
- ▲ Water Sample
- ┆ Impression Packer Survey
- ┆ Standard Penetration Test
- ┆ Permeability Test
- ▲ Piezometer Tip
- ┆ Standpipe Tip
- ▼ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 07/04/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH6
 SHEET 1 of 3
 DATE from 27/03/2000 to 31/03/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES	CONTRACT NO.
RIG NO. <u>R-4</u>	<u>E 835,536.02</u> <u>N 815,142.28</u>	ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+34.36 mP.D.</u>

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.O.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
27/03/2000	PX								41 bit					Firm, black to dark brown, slightly sandy SILT with occasional, subangular to subrounded, fine to medium gravel sized rock fragments. (FILL) Medium dense, yellowish brown, slightly clayey silty, fine to coarse SAND with occasional, subangular to subrounded, fine to medium gravel sized rock fragments. (FILL) Subangular to subrounded, BOULDERS with occasional, cobble and gravel sized, fragments of moderately strong
									INSPECTION PIT	0.45	33.85	0.50		
									INSPECTION PIT	0.95				
				100					41 bit	1.45				
									41 bit	1.50				
									41 bit	1.90				
									41 bit	2.90				
									41 bit	2.40				
									18 bit	3.50				
				100					18 bit	3.30				
									18 bit	4.00				
									18 bit	4.40				
27/03/2000 28/03/2000		0.51m at 18:00 Dry at 08:00		100					14 bit	5.50				
									14 bit	5.50				
									14 bit	6.00				
									14 bit	6.40				
	PX 7.50 HX			95					14 bit	7.50				
									14 bit	8.55				
									14 bit	8.00				
									14 bit	9.00				
				93					14 bit	9.48	24.88	9.48		

<ul style="list-style-type: none"> • Small Disturbed Sample • Large Disturbed Sample • SPT Liner Sample • U76 Undisturbed Sample • U100 Undisturbed Sample • Mazier Sample • Piston Sample 	<ul style="list-style-type: none"> ▲ Water Sample — Impression Packer Survey — Standard Penetration Test — Permeability Test □ Piezometer Tip □ Standpipe Tip ∨ In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>31/03/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	--	---

REMARKS
 1. Inspection pit 1.50m deep.

JOB NO. TFGS251/2000
 HOLE NO. BH6
 SHEET 2 of 3
 DATE from 27/03/2000 to 31/03/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES	CONTRACT NO.
RIG NO. <u>R-4</u>	<u>E 835,536.02</u> <u>N 815,142.28</u>	ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+34.36 mP.D.</u>

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.O.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
27/03/2000 28/03/2000	10.50m at 18:00 Dry at 08:00			98						10.50				to strong, pinkish grey, granite with brown mortar. (EXISTING WALL FOOTING)
28/03/2000 30/03/2000	11.75m at 18:00 Dry at 08:00			75						12.55 13.65				
				94						14.10	20.26	14.10	V	Extremely weak, reddish brown mottled with white and spotted with black, completely decomposed medium-grained GRANITE. (Silty fine to coarse SAND with some, subangular to subrounded, fine to medium gravel sized quartz fragments.)
				100						15.15 15.20 15.60				
				90						15.10				
				95						14.76				
	HX 17.00									17.00	17.36	17.00	II	Strong, pinkish grey mottled with white and spotted with black, slightly decomposed medium-grained GRANITE. Joints are medium spaced, locally very closely spaced, rough undulating and smooth planar, extremely narrow, brown iron stained, dipping at 20° to 30° and 40° to 50°.
30/03/2000 31/03/2000	17.33m at 18:00 Dry at 08:00			100	95	92	5.4			18.20				
				100	100	100		3.0		19.25				
				100	100	76				19.83				

<ul style="list-style-type: none"> ● Small Disturbed Sample ○ Large Disturbed Sample □ SPT liner Sample ▨ U76 Undisturbed Sample ▩ U100 Undisturbed Sample ▧ Mazier Sample ▦ Piston Sample 	<ul style="list-style-type: none"> ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Permeability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ∨ In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>31/03/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	--	---

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH6
 SHEET 3 of 3
 DATE from 27/03/2000 to 31/03/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140		
METHOD Rotary	CO-ORDINATES E 835,536.02 N 815,142.28	CONTRACT NO.
RIG NO. R-4		ROCK CORE BIT T2101
FLUSHING MEDIUM	ORIENTATION Vertical	GROUND-LEVEL +34.36 mP.D.


Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
					100	100	0.0					+		SAME AS SHEET 2 OF 3.
				100	100	100	-			20.57		+		From 21.07m to 21.12m: Pegmatitic granite.
				100	100	100	-			21.45		+		
		21.94m at 18:00			100	100	0.9					+		
										22.53	11.83	+		END OF DRILLHOLE AT 22.53m.

<ul style="list-style-type: none"> ● Small Disturbed Sample ■ Large Disturbed Sample ▨ SPT Liner Sample ▨ U76 Undisturbed Sample ▨ U100 Undisturbed Sample ▨ Mazier Sample ▨ Piston Sample ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Penneability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ∨ In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>31/03/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	---

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH7P
 SHEET 1 of 3
 DATE from 09/05/2000 to 13/05/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary

CO-ORDINATES

CONTRACT NO.

RIG NO. R-4

E 835,530.05

ROCK CORE BIT T2101

N 815,123.75

FLUSHING MEDIUM


ORIENTATION Vertical

GROUND-LEVEL +34.45 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
09/05/2000	PX													Loose, dark greyish brown, slightly silty SAND with occasional, subangular to subrounded, rock and brick fragments. (FILL)
	PX 3.05 HX			85				14 12.2, 3 14	INSPECTION PIT 0.45 0.95 1.45 1.95 2.45 2.95 3.00					
				95				14 4.55 4.95 5.00	3.50 4.55 4.95 5.00					
				90				14 6.55 6.95 7.00	6.50 6.55 6.95 7.00	28.95	5.50		V	Extremely weak, reddish brown to greyish brown, completely decomposed medium-grained GRANITE. (Dense to very dense, slightly silty SAND with occasional, subangular to subrounded, fine to medium gravel sized rock fragments.)
				100				14 7.25 7.35 7.40	7.50					
				85				14 8.25 8.35 8.40	8.55 8.60 9.00 9.50	24.45	10.00			
<ul style="list-style-type: none"> ● Small Disturbed Sample ○ Large Disturbed Sample ▨ SPT L&er Sample ▨ U76 Undisturbed Sample ▨ U100 Undisturbed Sample ▨ Mazier Sample ▨ Piston Sample ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Permeability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ⊥ In-situ Vane Shear Test 										LOGGED <u>W.K. Ngan</u>	REMARKS			
										DATE <u>15/05/2000</u>	1. Inspection pit 1.50m deep. 2. Standpipe installed at depth 16.32m.			
										CHECKED <u>G.P. Hamilton</u>				
										DATE <u>16/05/2000</u>				

JOB NO. TFGS251/2000
 HOLE NO. BH7P
 SHEET 2 of 3
 DATE from 09/05/2000 to 13/05/2000

DRILLHOLE RECORD



PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD Rotary	CO-ORDINATES	CONTRACT NO.
RIG NO. R-4	E 835,530.05 N 815,123.75	ROCK CORE BIT T2101
FLUSHING MEDIUM	ORIENTATION Vertical	GROUND-LEVEL +34.45 mP.D.

Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description
		6.32m at 18:00 Dry at 08:00							21 10.55 22 10.60 23 11.00 24 11.50 25 12.55 26 12.60 27 13.00 28 13.50 29 14.55 30 14.65 31 16.18				V	SAME AS SHEET 1 OF 3.
		12.13m at 18:00 15.30m at 08:00		90					31 16.18	18.25 16.20	16.18	+	IV	Moderately strong, pinkish brown, moderately decomposed medium-grained GRANITE. Joints are closely spaced, narrow to very narrow, rough undulating, iron stained and kaolin infilled, dipping at 0° to 10° and 40° to 50°.
				100	42	0	N.I.			18.03 15.42	16.42	+	III	From 16.20m to 16.42m: Highly decomposed. Strong, pinkish grey, slightly decomposed medium-grained GRANITE. Joints are widely spaced, locally closely spaced, extremely narrow to very narrow, rough undulating, iron stained and chlorite coated, dipping at 40° to 50° and 70° to 80°.
				100	58	47	7.1			17.15 17.30	17.95	+	II	At 17.95m: Pegmatitic. From 18.82m to 17.30m: Moderately decomposed. From 18.58m to 18.66m: Pegmatitic.
				100	100	100	0.0			18.45	19.51	+		
				100	100	100	0.82			14.45 20.00		+		

<ul style="list-style-type: none"> • Small Disturbed Sample • Large Disturbed Sample □ SPT Liner Sample □ U76 Undisturbed Sample □ U100 Undisturbed Sample □ Mazzer Sample □ Piston Sample ▲ Water Sample ⊥ Impression Packer Survey ⊥ Standard Penetration Test ⊥ Permeability Test ⊥ Piezometer Tip ⊥ Standpipe Tip ⊥ In-situ Vane Shear Test 	LOGGED <u>W.K. Ngan</u> DATE <u>15/05/2000</u> CHECKED <u>C.P. Hamilton</u> DATE <u>16/05/2000</u>
---	---

REMARKS

JOB NO. TFGS251/2000
 HOLE NO. BH7P
 SHEET 3 of 3
 DATE from 09/05/2000 to 13/05/2000

DRILLHOLE RECORD

Terraform-FGS 

PROJECT No. 55 Ship Street, Wanchai, I.L.2140

METHOD <u>Rotary</u>	CO-ORDINATES <u>E 835,530.05</u> <u>N 815,123.75</u>	CONTRACT NO.
RIG NO. <u>R-4</u>		ROCK CORE BIT <u>T2101</u>
FLUSHING MEDIUM	ORIENTATION <u>Vertical</u>	GROUND-LEVEL <u>+34.45 mP.D.</u>


Drilling Progress	Casing size/Depth (m)	Water Level/Time	Water Recovery %	Total core Recovery %	Solid core Recovery %	R.Q.D. %	Fracture Index	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Description	
				100	100	100						+	II	SAME AS SHEET 2 OF 3.	
		10.27m at 18:00		100	100		0.0					+			
		15.36m at 08:00		100	100							+			
		10.10m at 10:00										+		END OF DRILLHOLE AT 21.86m.	

- Small Disturbed Sample
- Large Disturbed Sample
- SPT Liner Sample
- ▨ U76 Undisturbed Sample
- ▩ U100 Undisturbed Sample
- ▧ Mazier Sample
- ▦ Piston Sample
- ▲ Water Sample
- ⊥ Impression Packer Survey
- ⊥ Standard Penetration Test
- ⊥ Permeability Test
- Piezometer Tip
- Standpipe Tip
- ∇ In-situ Vane Shear Test

LOGGED W.K. Ngan
 DATE 15/05/2000
 CHECKED C.P. Hamilton
 DATE 16/05/2000

REMARKS

SLOPE REFERENCE No.
11SW - B/R 617



<p>PROPOSED SITE INVESTIGATION AND SURVEY.</p>	<p>drawn by W. K. YIU <i>Sindy</i></p>	<p>date DEC. 86</p>	<p>drawing no. GCD 4194</p>	<p>scale 1:1000</p>
	<p>approved</p>	<p>date</p>	<p>CIVIL ENGINEERING SERVICES DEPARTMENT HONG KONG</p>	
	<p>office DESIGN DIVISION GEOTECHNICAL CONTROL OFFICE</p>			

pwd 186

A4 210 x 287

BACHY SOLETANCHE GROUP
HONG KONG

IV. BOREHOLE LOG AND PHOTOGRAPHS



BACHY SOLETANCHE GROUP
SOIL & FOUNDATIONS SPECIALISTS

DRILLHOLE RECORD
(LAND INVESTIGATION)

W. O. PW7/2/19.4
HOLE No. DH 1

CONTRACT GC/87/02 OF C.E.S.D. DATE from 16/6/87 to 18/6/87

PROJECT:

LAND S.I. AT HILLSIDE TERRACE, RETAINING WALL NO.11SW-B/R617

SHEET 1 OF 2

METHOD ROTARY	CO-ORDINATES E 835512.19 N 815176.27	ROCK COREBIT T2-101
MACHINE & No. D2G 16		HOLE DIA. 0.00m - 2.50m 140mm 2.50m - 11.00m 114mm
FLUSHING MEDIUM AIR FOAM	ORIENTATION VERTICAL	GROUND-LEVEL +32.01mPD

Drilling Progress	Casing depth/size	Water level/time/date	Water Recovery %	Total core Recovery %	Solid core Recovery %	R. Q. D.	Fracture Index. /m.	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Zone	Description
16/6/87	140mm								INSPECTION PIT						
				100					1		2.00				Loose, brown, speckled white & reddish pink, silty fine to coarse SAND with gravels. (FILL)
				90				2		+29.51	2.50				
				90							3.00				Gravels & cobbles of grade II/III granite & some concrete fragments in a brown silty SAND matrix. (RETAINING WALL FILLING)
	114mm			90							4.00				
				100							5.00				
				57							6.00				
		DRY 7:30									6.70				
17/6/87											7				
				33							8				
				40							9.00				
											10				

<ul style="list-style-type: none"> ● SMALL DISTURBED SAMPLE ⊥ BULK DISTURBED SAMPLE ■ S.P.T. LINER SAMPLE ▨ U 100 UNDISTURBED SAMPLE ▩ MAZIER SAMPLE (76mm) ▲ WATER SAMPLE ▽ WATER LEVEL ⌋ STANDARD PENETRATION TEST ⊥ PERMEABILITY TEST 	LOGGED C.H. CHOW DATE 22/6/87 CHECKED S.H. LAU DATE 7/7/87	REMARKS Piezometers were installed at 10.50m & 14.60m respectively. Impression packer test from 14.60m to 11.30m. Pressurized water test from 11.50m to 15.10m.
---	---	---



BACHY SOLETANCHE GROUP
SOIL & FOUNDATIONS SPECIALISTS

DRILLHOLE RECORD
(LAND INVESTIGATION)

W. O. PH7/2/19.4
HOLE No. DH 1

CONTRACT GC/87/02 OF C.E.S.D. DATE from 16/6/87 to 18/6/87

PROJECT:

LAND S.I. AT HILLSIDE TERRACE, RETAINING WALL NO.11SW-B/R617

SHEET 2 OF 2

METHOD

ROTARY

CO-ORDINATES

E 835512.19

ROCK COREBIT

T2-101

MACHINE & No.

D2G 16

N 815176.27

HOLE DIA

0.00m - 2.50m 140mm
2.50m - 11.00m 114mm

FLUSHING MEDIUM

AIR FOAM

ORIENTATION

VERTICAL

GROUND-LEVEL

+32.01mPD

Drilling Progress	Casing depth/size	Water level/time/date	Water Recovery %	Total core Recovery %	Solid core Recovery %	R. Q. D.	Fracture Index./m	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Zone	Description			
11	114mm			40							10.50				See sheet 1 of 2.			
				72								11.00						
17/6/87				100									11.40			IV	B	
12	8.60m 19:30 10.00m 7:35			82	82	78	2				11.65	+	+		Dark greyish brown, speckled brown, fine to coarse SAND. (C. TO H.D.G.)			
												12.35	+	+				
													12.56	+		+	III	D
13					100	100	91	4					13.92	+		+		
14													14.45	+		+		
15				90	90	0	N.I.	PZ AT 14.60m			15.10	+	+	IV	Dip 70°-80° Highly decomposed zone from 14.45m to 15.10m & 12.35m to 12.56m. (M.D.G.)			
16															End of hole at 15.10m			

- SMALL DISTURBED SAMPLE ▲ WATER SAMPLE
- † BULK DISTURBED SAMPLE ▼ WATER LEVEL
- S.P.T. LINER SAMPLE † STANDARD PENETRATION TEST
- U 100 UNDISTURBED SAMPLE
- ▨ MAZIER SAMPLE (75mm) † PERMEABILITY TEST

LOGGED C.H.CHOW DATE 22/6/87

CHECKED S.H.LAU DATE 7/7/87

REMARKS
Impression packer test
from : 14.60m to 13.10m
13.60m to 12.10m
12.80m to 12.80m



BACHY SOLETANCHE GROUP
SOIL & FOUNDATIONS SPECIALISTS

DRILLHOLE RECORD W. O. FW7/2/19.4
(LAND INVESTIGATION) HOLE No. DH 2
CONTRACT GC/87/02 OF C.E.S.D. DATE from 19/6/87 to 22/6/87

PROJECT:

LAND S.I. AT HILLSIDE TERRACE, RETAINING WALL NO.11SW-B/R517

SHEET 1 OF 2

METHOD ROTARY	CO-ORDINATES E 835514.48 N 815172.39	ROCK COREBIT /
MACHINE & No. D2G 16		HOLE DIA. 0.00m - 3.00m 140mm 3.00m - 12.00m 114mm
FLUSHING MEDIUM AIR FOAM	ORIENTATION VERTICAL	GROUND-LEVEL +31.98mPD

Drilling Progress	Casing depth/size	Water level/time/date	Water Recovery %	Total core Recovery %	Solid core Recovery %	R. Q. D.	Fracture Index./m.	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Zone	Description
1	140mm									+30.48	1.50			FILL	Brown, speckled dark pink silty fine to coarse SAND. (FILL)
2				100				N=2	1		2.00				Pinkish brown, mottled white & yellow, clayey silty fine to coarse SAND. (C.D.G.)
3								N=4	2		3.00				Brown, mottled yellowish brown, speckled reddish pink & white silty fine to coarse SAND. (C.D.G.)
4				85					3		3.50				
5	114mm							N=8	4		4.50				Pinkish brown, mottled white & yellowish brown, silty fine to coarse SAND. (C.D.G.)
6		DRY 7:30							5		5.00				
7								N=8	6		6.00				Yellowish brown, mottled white & speckled pink, silty fine to coarse SAND. (C.D.G.)
8				90					7		6.50				
9								N=11	8		7.50				Yellowish brown to brown, mottled white & reddish pink, silty fine to coarse SAND. (C.D.G.)
10				80					9		8.00				
								N=16	10		9.00				
				100					11		9.50				

- SMALL DISTURBED SAMPLE
- † BULK DISTURBED SAMPLE
- S. P. T. LINER SAMPLE
- ▨ U 100 UNDISTURBED SAMPLE
- ▩ MAZIER SAMPLE (76mm)
- ▲ WATER SAMPLE
- ▼ WATER LEVEL
- ↓ STANDARD PENETRATION TEST
- I PERMEABILITY TEST

LOGGED C.H.CHOW DATE 24/6/87
CHECKED S.H.LAU DATE 7/7/87

REMARKS
Falling Head Permeability test at 6.00m & 10.50m respectively. Piezometer was installed at 11.50m.



BACHY SOLETANCHE GROUP
SOIL & FOUNDATIONS SPECIALISTS

DRILLHOLE RECORD
(LAND INVESTIGATION)

W. O. PW7/2/19.4
HOLE No. DH 2

CONTRACT GC/87/02 OF C.E.S.D. DATE from 19/6/87 to 22/6/87

PROJECT:

LAND S.I. AT HILLSIDE TERRACE, RETAINING WALL NO.11SW-B/R617

SHEET 2 OF 2

METHOD ROTARY	CO-ORDINATES E 835514.48 N 815172.39	ROCK COREBIT /
MACHINE & No. D2G 16		HOLE DIA. 0.00m - 3.00m 140mm 3.00m - 12.00m 114mm
FLUSHING MEDIUM AIR FOAM	ORIENTATION VERTICAL	GROUND-LEVEL +31.98mPD

Drilling Progress	Casing depth/size	Water level/time/date	Water Recovery %	Total core Recovery %	Solid core Recovery %	R. Q. D.	Fracture Index. /m.	Tests	Samples	Reduced Level	Depth (m)	Legend	Grade	Zone	Description
11 22/6/87	114mm			85				N=35 PZ AT 11.50m	12 13 14	+19.98	10.50 11.00 12.00		V	B	See sheet 1 of 2. Pinkish brown, mottled yellowish white, silty fine to coarse SAND. (C.D.G.)
12															End of hole at 12.00m
13															

<ul style="list-style-type: none"> ● SMALL DISTURBED SAMPLE † BULK DISTURBED SAMPLE ■ S. P. T. LINER SAMPLE □ U 100 UNDISTURBED SAMPLE ⊠ MAZIER SAMPLE (76mm) ▲ WATER SAMPLE ▼ WATER LEVEL STANDARD PENETRATION TEST I PERMEABILITY TEST 	LOGGED <u>C.H. CHOW</u> DATE <u>24/6/87</u> CHECKED <u>S.H. LAU</u> DATE <u>7/7/87</u>	REMARKS
---	---	---------

BACHY SOLETANCHE GROUP
HONG KONG

V. TRIAL PIT LOGS AND PHOTOGRAPHS

TRIAL PIT RECORD

<p>CONTRACTOR: B.S.G.</p>		<p>SHORING: NIL</p>		<p>CO-ORDINATES: E 835509.90 N 815185.13</p>		<p>PIT NO.: TP 1</p>	
<p>WORKS ORDER NO.: PW7/2/19.4</p>		<p>LOGGED BY: CHOW</p>		<p>EXCAVATION DATES: 11/7/87</p>		<p>LOCATION: HILLSIDE TERRACE</p>	
<p>SAMPLES & DEPTH DATUM = +19.541 m.P.D.</p>		<p>13/7/87</p>		<p>LEGEND</p>		<p>DESCRIPTION</p>	
		<p>GRADE</p>		<p>FILL</p>		<p>IV</p>	
<p>0 0.5 1.0 1.5 2.0 2.5 3.0 3.5 4.0 4.5 5.0 5.5</p>		<p>0 0.5 1.0 1.5 2.0 2.5 3.0 3.5 4.0 4.5 5.0 5.5</p>		<p>Concrete slab.</p>		<p>Brown, speckled white, silty fine to coarse SAND with bricks & boulders. (FILL)</p>	
<p>sewage pipe Ø 0.20m</p>		<p>H.D.G.</p>		<p>Brownish grey, mottled yellowish white & black, fine to coarse SAND. (H.D.G.)</p>		<p>End of pit at 1.30m</p>	
<p>FACE A:</p>		<p>FACE B:</p>		<p>FACE C:</p>		<p>FACE D:</p>	
<p>1.50m</p>		<p>1.00m</p>		<p>SYMBOL SAMPLES/TESTS/WATER</p>		<p>PLAN (not to scale)</p>	
<p>A</p>		<p>B</p>		<p>Small dist. samples Large dist. samples Undist. sample hori. () Undist. sample vert. () Block sample Plate bearing test In situ density test Moisture content test water sample Scrapages</p>		<p>Retaining wall footpath building quater area</p>	
<p>D</p>		<p>C</p>		<p>+</p>		<p>T.P. 1</p>	
<p>water pipe</p>		<p>sewage pipe</p>		<p>101 Y m A ↓</p>		<p>SHEET 1 OF 1</p>	

TRIAL PIT RECORD

CONTRACTOR: - B.S.G. WORKS ORDER NO.: PW7/2/19.4 SAMPLES & TESTS DEPTH DATUM = +32.34 m.P.D.		SHORING: NIL LOGGED BY: CHOW DATE: 13/7/87		CO-ORDINATES: E 835508.45 M 815181.11 EXCAVATION DATES: 11/7/87		PIT NO.: TP 2 LOCATION: HILLSIDE TERRACE	
LEGEND 		DESCRIPTION Concrete slab Brown, mottled grey, silty fine to coarse SAND with gravels & brick fragments. (FILL)		T.P. 2 SHEET 1 OF 1		FILL	
0 0.5 1.0 1.5 2.0 2.5 3.0 3.5 4.0 4.5 5.0 5.5 (m)				PLAN (not to scale) Retaining wall 		A-C SECTION Remark: End of pit at 2.14m	
FACE A:		FACE B:		FACE C:		FACE D:	
SYMBOLS: Small dist. samples Large dist. samples Undist. sample hori. Undist. sample vert. Block sample Plate bearing test In situ density test Moisture content test water sample Seepage		1.00m 2.85m		Retaining wall		140° N	

TRIAL PIT RECORD

CONTRACTOR: B.S.G.	SHORING: NIL LOGGED BY: CHOW DATE: 13/7/87	CO-ORDINATES: E 835520.79 N 815174.87 EXCAVATION DATES: 11/7/87	PIT NO.: TP 3 LOCATION: HILLSIDE TERRACE	T.P. 3 SHEET 1 OF 1	
WORKS ORDER NO: PW7/2/19.4 DEPTH DATUM: +19.68m.P.D.					
LEGEND	DESCRIPTION				
FILL	Concrete slab Dark grey brown, speckled white, silty fine to coarse SAND with gravels & brick fragments. (FILL)	Remark: End of pit at 0.87m			
IV	Yellowish brown, speckled white, fine to coarse SAND. (H.D.G.)	SYMBOL	SAMPLES/TESTS/WATER	PLAN (not to scale) Retaining wall footpath building N. 320°	
		Small dist. samples Large dist. samples Undist. sample hori. () Undist. sample vert. () Block sample Plate bearing test In situ density test Moisture content test water sample Saeppagus			
		FACE A: FACE B: FACE C: FACE D:			

TRIAL PIT RECORD

CONTRACTOR: B.S.G.			SHORING: NIL		CO-ORDINATES: E 835519.16 N 815171.40		PIT NO.: TP 4	
WORKS ORDER NO.: PW7/2/19.4			LOGGED BY: CHOW DATE: 14/7/87		EXCAVATION DATES: 11/7/87		LOCATION: HILLSIDE TERRACE	
DEPTH DATUM: +32.03 m.P.D.			LEGEND		DESCRIPTION		GRADE	
					Lean mixed cement with brick fragments Gravels, cobbles & boulder of grade II/III granite & brick fragments in a brown silty SAND matrix. (FILL) Brown, mottled yellowish white, speckled reddish pink, silty fine to coarse SAND. (C.D.G.) H.D.G. H.10M.D.G. C.D.G. Retaining wall Concrete slab boulders		FILL	
0 0.5 1.0 1.5 2.0 2.5 3.0 3.5 4.0 4.5 5.0 5.5 DEPTH (m)			FACE A: FACE B: → C FACE C: FACE D:		PLAN (not to scale) Retaining wall wooden door staircase 140° N		T.P. 4 SHEET 1 OF 1	
SYMBOL SAMPLES/TESTS/WATER Small dist. samples Large dist. samples Undist. sample hor. () Undist. sample vert. () Block sample Plate bearing test In situ density test Moisture content test Water sample Seepage			Remark: End of pit at 3-20m		A-C SECTION			

Appendix B

Summary of Existing Registered Features

Appendix B – Summary of Existing Features

Feature No.	Maintenance Responsibility	Slope/Wall Dimension (Length x max. height)	Angle	Findings
11SW-B/CR252	IL1940 IL2140 Lands D	21m x 9m (slope) 21m x 5m (wall)	60° (slope) 90° (wall)	<ul style="list-style-type: none"> - Stage 2 stability study (S2R220/2003) was carried out in 2004. - Advisory letter and follow-up action were recommended to IL1940 and Lands D, respectively.
11SW-B/CR253	IL8102 & EXT IL1669 IL1564 IL2272 & EXT Lands D	18m x 8.5 (slope) 10m x 2m (wall)	70° (slope) 88° (wall)	
11SW-B/CR235	IL8102 & EXT	80m x 18m (slope) 36m x 5.5m (wall)	45° (slope) 85° (wall)	<ul style="list-style-type: none"> - Slope upgrading works were implemented by the responsible owner, and GEO advised BD on 28/9/2011 of no geotechnical objection to the acknowledgement of Form BA14.
11SW-B/CR349	IL2140 Lands D IL8102 & EXT	15m x 4m (slope) 15m x 8m (wall)	30° (slope) 80° (wall)	<ul style="list-style-type: none"> - DH0035/HK/11/C dated 30 March 2011 served to IL2140 and slope remedial works approved by BD on 23 June 2011. The slope remedial works were completed in November 2017. - Stage 3 study on government portion deferred in 1997. - Stage 3 study report (S3R 120/2011) on government portion completed in December 2011. Installation of soil nails was proposed to upgrade the feature to the current safety standards. The upgrading works were completed in September 2012.
11SW-B/C353	Lands D	5m x 4m	80°	
11SW-B/R617	IL199 RP	25m x 11.8m	80°	<ul style="list-style-type: none"> - GEO in-house Stage 2 study (S2R 4/88) completed in 1988; no action required. - GEO Stage 2 study (S2R 23/2012) completed in 2014. - DH0038/HK/15/C dated 6 March 2015 served to IL199R.P.
11SW-B/R629	IL2140	45m x 10m	85°	<ul style="list-style-type: none"> - DH0035/HK/11/C dated 30 March 2011 served to IL2140 and slope remedial works approved by BD on 23 June 2011. The slope remedial works were completed in November 2017.
11SW-B/R663	IL8102 & EXT IL199 RP	8m x 5.5m	85°	
11SW-B/R1023	IL2140	5.6m x 12.2 m	90°	-New registration of Slope Feature, approved on 13 January 2023.

BASIC INFORMATION

Location: 1-6 SAU WAH FONG, WANCHAI, HK.
Registration Date: 16-03-1998
Ranking Score (NPRS): 43565 (Notional)
Date of Formation: post-1977
Date of Construction/ Modification:
Data Source: EI
Approximate Coordinates: Easting : 835489 Northing : 815199

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: School
Distance of Facility from Crest (m): 7
Facility at Toe: Residential building
Distance of Facility from Toe (m): 2
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

N/A

WALL PART

(1) Max. Height (m): 8.3 Length (m): 26 Face Angle (deg): 83

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 1	Private Feature	Party: IL199B4	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005
(2) Sub Div.: 2	Private Feature	Party: IL199E3	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005
(3) Sub Div.: 3	Private Feature	Party: IL199CRP	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005
(4) Sub Div.: 4	Private Feature	Party: IL199D3	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005
(5) Sub Div.: 5	Private Feature	Party: IL199A6	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005
(6) Sub Div.: 6	Private Feature	Party: IL199RP	Agent: N/A	Land Cat.: 1	Reason Code: 1	MR Endorsement Date: 30-08-2005

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 01-09-1999
Data Source: EI
Slope Part Drainage: N/A
Wall Part Drainage: (1) Position: Crest Size(mm): 275

SLOPE PART

N/A



WALL PART

Wall Part (1)
 Type of Wall: Wall Material: Masonry Wall Location: Retaining wall with level platform
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 65 Spacing (m): 2.2

SERVICES

N/A

CHECKING STATUS INFORMATION

N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B7
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 7054-5 (1963),
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 01-09-1999
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1963 After: N/A
 Related Reports/Files or Documents: File/Report: DB or DH Ref. No.: GC13/4/DH239/95/HK, GC13/4/DH483/79/HK
 File/Report: DB or DH Ref. No.: GC13/4/DH239/95/HK, GC13/4/DH483/79/HK
 File/Report: GCC Ref. No.: GCC paper No.355
 File/Report: GCC Ref. No.: GCC paper No.355
 File/Report: GEO Ref. No.: DH Order issued on 20/5/96 rpt ref: S2R 31/95
 File/Report: GEO Ref. No.: DH Order issued on 20/5/96 rpt ref: S2R 31/95
 File/Report: GEO Ref. No.: Stage 2 report S2R 31/95
 File/Report: GEO Ref. No.: Stage 2 report S2R 31/95
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 Remarks: FILE GC13/4/DH483/79/HK QUOTED ON THE DISTRICT OVERLAY DOES NOT RELATE TO THIS FEATURE.
 Follow Up Actions: N/A



DH-Order (To Be Confirmed with Buildings Department):
 Date of Recommendation to BD: 23/11/1995 File Reference: DH/0239/95/HK
 Date Served by BD: 29/01/1997 Notice No.: DH027/HK/97/C
 Date of Recommendation to BD: 23/11/1995 File Reference: DH/0239/95/HK
 Date Served by BD: 29/01/1997 Notice No.: DH028/HK/97/C
 Date of Recommendation to BD: 23/11/1995 File Reference: DH/0239/95/HK
 Date Served by BD: 20/05/1996 Notice No.: DH051/HK/96/C

Advisory Letter (To Be Confirmed with Buildings Department): None

LPMIS: Agreement No.: CE33/93 Report No.: S2R 31/95

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On:
 Weather:
 District: 1
 Section No: 1-1
 Height(m):
 Type of Toe Facility: Residential building
 Distance from Toe(m): 2
 Type of Crest Facility: School
 Distance from Crest(m): 7
 Consequence Category:
 Engineering Judgement:
 Section No: 2-2
 Type of Toe Facility:
 Distance from Toe(m):
 Type of Crest Facility:
 Distance from Crest(m):
 Consequence Category:
 Engineering Judgement:
 Sign of Seepage:
 Criterion A satisfied:
 Sign of Distress:
 Criterion D satisfied:
 Non-routine maintenance required:
 Note:
 Masonry wall/Masonry facing:
 Note:
 Consequence category (for critical section):

Observations: N/A
Emergency Action Required:
Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A
Action By: N/A
Further Study:
Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services:
Action By: N/A
Non-routine Maintenance:
Action By: N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.: 11SW-B/R 616
Location: {1-10 SAU WA FONG, WANCHAI}
District Council: Wanchai
Maintenance Responsibility (At the Time of Selection): Private
Responsible Party for Maintenance of Government Portion: N/A
Private Lot No.: NA

LPM/LPMit Study

Agreement No.: CE33/93
Study Type: Stage 2 Study
Consultant: Mott Connell Ltd.
GEO Managing Section / Engineer: LPM3 / CM62
Study Status: Study completed
Design Approach: Otherwise
Option Assessment Accepted: N/A
Study Report No.: S2R 31/95
Programme / Actual Commencement: 01-06-1994
Programme / Actual Completion: 31-08-1998
Report Recommendation (For Stage 2 Study): DH Order
District Check Status: Checked
Checking Certificate No.: N/A



GEO Engineer's Remarks: N/A

LPM/LPMit Works

Works Contract No.: N/A

GEO Managing Section / Engineer: N/A / N/A

Contractor: N/A

Progress Status: N/A

Reason of Study Termination / Works Deletion (If Necessary): N/A

Forecast Commencement Date: N/A

Forecast Completion Date: N/A

Completion Cert. Issued: N/A

Site Handed Over to Maintenance Department on: N/A

Estimated Cost for Upgrading (HK\$M): N/A

Maintenance Manual No.: N/A

Actual Works: N/A

No. of Tree Felled: N/A

No. of Tree Planted (Incl. Transplant): N/A

% Bare of Slope Surfacing: N/A


% Vegetated of Slope Surfacing: N/A

% Shotcrete of Slope Surfacing: N/A

Other Hard Surface of Slope Surfacing: N/A

PHOTO





BASIC INFORMATION

Location: No. 18 Sau Wa Fong, Hong Kong - Lot No. I.L. 199 R.P.
Registration Date: 16-03-1998
Ranking Score (NPRS): 73 (LPMit)
Date of Formation: post-1977
Date of Construction/ Modification: 24-07-2022
Data Source: AP
Approximate Coordinates: Easting : 835515 Northing : 815179

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Cottage, licensed and squatter area
Distance of Facility from Crest (m): 0
Facility at Toe: Residential building
Distance of Facility from Toe (m): 0
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

N/A

WALL PART

(1) Max. Height (m): 11.8 Length (m): 25 Face Angle (deg): 85

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 0 Private Feature Party: IL199 RP Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 25-09-2013

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 28-08-2022
Data Source: AP
Slope Part Drainage: N/A
Wall Part Drainage: (1) Position: Toe Size(mm): 300

SLOPE PART

N/A

WALL PART



Wall Part (1)

Type of Wall: Wall Material: Masonry Wall Location: Retaining wall with level platform
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 90 Spacing (m): 1.2

SERVICES

(1) Utilities Type: Water Main Size(mm): 45 Location: On slope Remark: N/A

CHECKING STATUS INFORMATION

Tagmark: SCS_20036 Part: 0 Checking Status: Feature modified/upgraded to current standard Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B8
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 6122-3 (1949),
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 28-08-2022
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1949 After: N/A
 Modification: Substantially Modified Before: N/A After: 1981
 Related Reports/Files or Documents: File/Report: DB or DH Ref. No.: GCI3/4/DH32/82/HK
 File/Report: DB or DH Ref. No.: GCI3/4/DH32/82/HK
 File/Report: Development Ref. No.: GCI3/4/1152/78
 File/Report: Development Ref. No.: GCI3/4/1152/78
 File/Report: GEO Ref. No.: Stage 1 report by planning
 File/Report: GEO Ref. No.: Stage 1 report by planning
 File/Report: GEO Ref. No.: Stage 2 report 4/88, File closed.
 File/Report: GEO Ref. No.: Stage 2 report 4/88, File closed.
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Previous Instability Ref. No.: 9/3/92 92/3/3
 File/Report: Previous Instability Ref. No.: 9/3/92 92/3/3
 Remarks: N/A
 Follow Up Actions: N/A



DH-Order (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 05/03/2021	Notice No.: DH0005/HK/21/C
	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 06/03/2015	Notice No.: DH0038/HK/15/C
Advisory Letter (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 11/11/2020	Notice No.: DH0062/HK/20/C
	Date of Recommendation to BD: 16/03/1992	File Reference: DH032/80/HK
	Date Served by BD: 26/10/1992	
LPMIS:	Date of Recommendation to BD: 16/03/1992	File Reference: D 365/75/HK
	Date Served by BD: 25/01/1996	
	Date of Recommendation to BD: 14/02/2012	File Reference: DH032/80/HK
	Date Served by BD: 04/06/2012	
	Agreement No.: CE58/2009	Report No.: S2R 23/2012
	Agreement No.: In-house Design	Report No.: S2R 4/88

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On:

Weather:

District: I

Section No: 1-1

Height(m):

Type of Toe Facility: Residential building

Distance from Toe(m): 0

Type of Crest Facility: Cottage, licensed and squatter area

Distance from Crest(m): 0

Consequence Category:

Engineering Judgement:

Section No: 2-2

Type of Toe Facility:

Distance from Toe(m):

Type of Crest Facility:

Distance from Crest(m):

Consequence Category:

Engineering Judgement:

Sign of Seepage:

Criterion A satisfied:

Sign of Distress:

Criterion D satisfied:

Non-routine maintenance required:

Note:

Masonry wall/Masonry facing:

Note:

Consequence category (for critical section):

Observations: N/A

Emergency Action Required:

Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A

Action By: N/A

Further Study:

Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services:

Action By: N/A

Non-routine Maintenance:

Action By: N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/R 617
Location:	SOUTH OF NO.18 SAN WAH FONG
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Private
Responsible Party for Maintenance of Government Portion:	N/A
Private Lot No.:	IL199 RP

LPM/LPMit Study

Agreement No.:	CE58/2009
Study Type:	Stage 2 Study
Consultant:	Atkins China Ltd.
GEO Managing Section / Engineer:	SS / SS3
Study Status:	Study completed
Design Approach:	N/A
Option Assessment Accepted:	N/A
Study Report No.:	S2R 23/2012
Programme / Actual Commencement:	20-02-2012

Programme / Actual Completion: 27-10-2012
Report Recommendation (For Stage 2 Study): DH Order
District Check Status: Exempted from checking
Checking Certificate No.: N/A
GEO Engineer's Remarks: N/A

LPM/LPMit Works

Works Contract No.: N/A
GEO Managing Section / Engineer: N/A / N/A
Contractor: N/A
Progress Status: N/A
Reason of Study Termination / Works Deletion (If Necessary): N/A
Forecast Commencement Date: N/A
Forecast Completion Date: N/A
Completion Cert. Issued: N/A
Site Handed Over to Maintenance Department on: N/A
Estimated Cost for Upgrading (HK\$M): N/A
Maintenance Manual No.: N/A
Actual Works: N/A
No. of Tree Felled: N/A
No. of Tree Planted (Incl. Transplant): N/A
% Bare of Slope Surfacing: N/A
% Vegetated of Slope Surfacing: N/A
% Shotcrete of Slope Surfacing: N/A
Other Hard Surface of Slope Surfacing: N/A

LPM/LPMit Details Report

LPM Study Feature No.: 11SW-B/R 617
Location: SOUTH OF NO.18 SAN WAH FONG
District Council: Wanchai
Maintenance Responsibility (At the Time of Selection): Private
Responsible Party for Maintenance of Government Portion: N/A
Private Lot No.: NA

LPM/LPMit Study

Agreement No.: In-house Design
Study Type: Stage 2 Study
Consultant: N/A
GEO Managing Section / Engineer: LPM2 / N/A
Study Status: Study completed
Design Approach: Conventional (G1 + Analysis)
Option Assessment Accepted: N/A
Study Report No.: S2R 4/88
Programme / Actual Commencement: N/A





Programme / Actual Completion:	N/A
Report Recommendation (For Stage 2 Study):	No action required
District Check Status:	Not checked
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	NO FURTHER ACTION

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO





BASIC INFORMATION

Location: 66 Schooner Street, Wan Chai
Registration Date: 16-03-1998
Ranking Score (NPRS): 0 (EI)
Date of Formation: pre-1977
Date of Construction/ Modification:
Data Source: EI(Lands D)
Approximate Coordinates: Easting : 835527 Northing : 815168

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Residential building
Distance of Facility from Crest (m): 0
Facility at Toe: Road/footpath with moderate traffic density
Distance of Facility from Toe (m): 0
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

(1) Max. Height (m): 4 Length (m): 5 Average Angle (deg): 80

WALL PART

N/A

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 1 Private Feature Party: IL 9048 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 04-06-2018
(2) Sub Div.: 2 Private Feature Party: IL 199 RP Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 04-06-2018

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 11-11-2016
Data Source: EI(Lands D)
Slope Part Drainage: N/A
Wall Part Drainage: N/A

SLOPE PART

Slope Part (1)
Surface Protection (%): Bare: 0 Vegetated: 0 Chunam: 100 Shotcrete: 0 Other Cover: 0
Material Description: Material type: Soil Geology: N/A
Berm: No. of Berms: N/A Min. Berm Width (m): N/A
Weepholes: Size (mm): 50 Spacing (m): 1



WALL PART

N/A

SERVICES

N/A

CHECKING STATUS INFORMATION

N/A

BACKGROUND INFORMATION


GIU Cell Ref.:	11SW14B8
Map Sheet Reference (1:1000):	11SW-14B
Aerial Photos:	N/A
Nearest Rainguage Station (Station Number):	25 Borrett Road(H17)
Data Collected On:	11-11-2016
Date of Construction, Subsequent Modification and Demolition:	N/A
Related Reports/Files or Documents:	N/A
Remarks:	FILE GCI 3/4/DH32/80/HK QUOTED ON THE DISTRICT OVERLAY RELATES ONLY TO ANOTHER FEATURE AT THE SAME PREMISES
Follow Up Actions:	N/A
DH-Order (To Be Confirmed with Buildings Department):	None
Advisory Letter (To Be Confirmed with Buildings Department):	None
LPMIS:	Agreement No.: CE79/95 Report No.: N/A

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On: 23-04-1996
 Weather: Mainly Fine
 District: I



Section No: 1-1
 Height(m): H1 : 3 , H2 : 0
 Type of Toe Facility: Road/footpath with moderate traffic density
 Distance from Toe(m): 0
 Type of Crest Facility: Residential building
 Distance from Crest(m): 0
 Consequence Category: 1
 Engineering Judgement: P
 Section No: 2-2
 Type of Toe Facility: Licensed and squatter area
 Distance from Toe(m): 0
 Type of Crest Facility: Road with very low traffic
 Distance from Crest(m): 0
 Consequence Category: 1
 Engineering Judgement: P
 Sign of Seepage: Slope : No signs of seepage
 Wall : N/A
 Criterion A satisfied: N
 Sign of Distress: Slope : Reasonable (near crest, mid-portion, at toe)
 Wall : N/A
 Criterion D satisfied: N
 Non-routine maintenance required: N
 Note: N/A
 Masonry wall/Masonry facing: N
 Note: N/A
 Consequence category (for critical section): 1
 Observations: N/A
 Emergency Action Required: N
 Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D:	N/A
Action By:	N/A
Further Study:	Y
Action By:	Mixed

OTHER EXTERNAL ACTION

Check / repair Services:	N
Action By:	N/A
Non-routine Maintenance:	N
Action By:	N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/C 251
Location:	SCHOONER STREET
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Government
Responsible Party for Maintenance of Government Portion:	FEHD
Private Lot No.:	N/A

LPM/LPMit Study

Agreement No.:	CE79/95
Study Type:	Stage 2 Study
Consultant:	Binnie Consultants Ltd.
GEO Managing Section / Engineer:	LPM1 / CM11
Study Status:	Stage 2 study suspended as MR found to rest with GOVERNMENT
Design Approach:	N/A
Option Assessment Accepted:	N/A
Study Report No.:	N/A
Programme / Actual Commencement:	N/A
Programme / Actual Completion:	N/A
Report Recommendation (For Stage 2 Study):	N/A
District Check Status:	N/A
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	FEATURE IS NOT PRIVATE.


LPM/LPMit Works


Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A



Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO







BASIC INFORMATION

Location: North East of No. 55 Ship Street, Wan Chai
 Registration Date: 16-03-1998
 Ranking Score (NPRS): 7 (Notional)
 Date of Formation: pre-1977
 Date of Construction/ Modification: 20-11-2017
 Data Source: AP
 Approximate Coordinates: Easting : 835543 Northing : 815136

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Residential building
 Distance of Facility from Crest (m): 2
 Facility at Toe: Residential building
 Distance of Facility from Toe (m): 1
 Consequence-to-life Category: 1
 Remarks: N/A

SLOPE PART

N/A

WALL PART

(1) Max. Height (m): 10 Length (m): 45 Face Angle (deg): 85

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 0 Private Feature Party: IL 2140 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 02-06-1997

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 28-12-2018
 Data Source: AP
 Slope Part Drainage: N/A
 Wall Part Drainage: (1) Position: Crest Size(mm): 150
 (2) Position: Downpipe Size(mm): 150

SLOPE PART

N/A

WALL PART



Wall Part (1)
 Type of Wall: Wall Material: Masonry Wall Location: Retaining wall with level platform
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 65 Spacing (m): 1.2

SERVICES

N/A

CHECKING STATUS INFORMATION

Tagmark: SCS_18107 Part: 0 Checking Status: Feature modified/upgraded to current standard Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B8
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 6122-3 (1949),
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 28-12-2018
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1949 After: N/A
 Related Reports/Files or Documents: File/Report: GCC Ref. No.: GC14/1A/RA6E f(75,77A)
 File/Report: GCC Ref. No.: GC14/1A/RA6E f(75,77A)
 File/Report: GEO Ref. No.: Stage 1 report by existing slope
 File/Report: GEO Ref. No.: Stage 1 report by existing slope
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 Remarks: N/A
 Follow Up Actions: N/A
 DH-Order (To Be Confirmed with Buildings Department): Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 10/08/1998 Notice No.: DH161/HK/98/C
 Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 10/08/1998 Notice No.: DH161/HK/98/C
 Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 30/03/2011 Notice No.: DH0035/HK/11/C
 Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 10/08/1998 Notice No.: DH161/HK/98/C
 Advisory Letter (To Be Confirmed with Buildings Department): Date of Recommendation to BD: 12/01/1984 File Reference: DH020/84/HK
 Date Served by BD: 08/02/1984
 LPMIS: Agreement No.: CE33/93 Report No.: S2R 226/96



ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On:

Weather:

District: 1

Section No: 1-1

Height(m):

Type of Toe Facility: Residential building

Distance from Toe(m): 1

Type of Crest Facility: Residential building

Distance from Crest(m): 2

Consequence Category:

Engineering Judgement:

Section No: 2-2

Type of Toe Facility:

Distance from Toe(m):

Type of Crest Facility:

Distance from Crest(m):

Consequence Category:

Engineering Judgement:

Sign of Seepage:

Criterion A satisfied:

Sign of Distress:

Criterion D satisfied:

Non-routine maintenance required:

Note:

Masonry wall/Masonry facing:

Note:

Consequence category (for critical section):

Observations: N/A

Emergency Action Required:

Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A

Action By: N/A

Further Study:

Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services:

Action By: N/A

Non-routine Maintenance:

Action By: N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/R 629
Location:	{55 SHIP STREET, WAN CHAI}
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Private
Responsible Party for Maintenance of Government Portion:	N/A
Private Lot No.:	NA

LPM/LPMit Study

Agreement No.:	CE33/93
Study Type:	Stage 2 Study
Consultant:	Mott Connell Ltd.
GEO Managing Section / Engineer:	LPM3 / CM62
Study Status:	Study completed
Design Approach:	Otherwise
Option Assessment Accepted:	N/A
Study Report No.:	S2R 226/96
Programme / Actual Commencement:	01-05-1994
Programme / Actual Completion:	31-08-1998
Report Recommendation (For Stage 2 Study):	DH Order
District Check Status:	Checked
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	N/A

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A



Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO





BASIC INFORMATION

Location: No. 55, Ship Street, Wan Chai
Registration Date: 10-03-2023
Ranking Score (NPRS): N/A (N/A)
Date of Formation: N/A
Date of Construction/ Modification: 19-07-2021
Data Source: Districts
Approximate Coordinates: Easting : 835525 Northing : 815118

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Road/footpath with very low traffic density
Distance of Facility from Crest (m): 0
Facility at Toe: Residential building
Distance of Facility from Toe (m): 0
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

N/A

WALL PART

(1) Max. Height (m): 5.6 Length (m): 12.2 Face Angle (deg): 90

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 0 Private Feature Party: IL 2140 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 31-07-2023

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 13-12-2022
Data Source: Districts
Slope Part Drainage: N/A
Wall Part Drainage: (1) Position: Toe Size(mm): 150

SLOPE PART

N/A

WALL PART



Wall Part (1)
 Type of Wall: Wall Material: Concrete Wall Location: Wall at toe
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): N/A Spacing (m): N/A

SERVICES

N/A

CHECKING STATUS INFORMATION

N/A

BACKGROUND INFORMATION

GIU Cell Ref.:
 Map Sheet Reference (1:1000):
 Aerial Photos:
 Nearest Rainguage Station (Station Number):
 Data Collected On: 13-12-2022
 Date of Construction, Subsequent Modification and Demolition: N/A
 Related Reports/Files or Documents: N/A
 Remarks:
 Follow Up Actions:
 DH-Order (To Be Confirmed with Buildings Department): None
 Advisory Letter (To Be Confirmed with Buildings Department): None
 LPMIS: None

ENHANCED MAINTENANCE INFORMATION

STAGE 1 STUDY REPORT

Inspected On:
Weather:
District:
Section No: 1-1
Height(m):
Type of Toe Facility: Residential building
Distance from Toe(m): 0
Type of Crest Facility: Road/footpath with very low traffic density
Distance from Crest(m): 0
Consequence Category:
Engineering Judgement:
Section No: 2-2
Type of Toe Facility:
Distance from Toe(m):
Type of Crest Facility:
Distance from Crest(m):
Consequence Category:
Engineering Judgement:
Sign of Seepage:
Criterion A satisfied:
Sign of Distress:
Criterion D satisfied:
Non-routine maintenance required:
Note:
Masonry wall/Masonry facing:
Note:
Consequence category (for critical section):
Observations: N/A
Emergency Action Required:
Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A
Action By: N/A
Further Study:
Action By: N/A

OTHER EXTERNAL ACTION


Check / repair Services:
Action By: N/A
Non-routine Maintenance:



Action By:

N/A

PHOTO





BASIC INFORMATION

Location: North East of ST. Francis Canossian College, Kennedy Road, Wan Chai
 Registration Date: 23-04-1998
 Ranking Score (NPRS): 0 (LPMit)
 Date of Formation: pre-1977
 Date of Construction/ Modification:
 Data Source: EI(Lands D)
 Approximate Coordinates: Easting : 835512 Northing : 815129

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Densely-used open area/facilities
 Distance of Facility from Crest (m): 5
 Facility at Toe: Residential building
 Distance of Facility from Toe (m): 3
 Consequence-to-life Category: 1
 Remarks: N/A

SLOPE PART

(1) Max. Height (m): 4 Length (m): 15 Average Angle (deg): 30

WALL PART

(1) Max. Height (m): 8 Length (m): 15 Face Angle (deg): 80

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 1 Mixed Feature Party: IL2140 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 11-11-2002
 (2) Sub Div.: 2 Mixed Feature Party: Lands D Agent: Lands D Land Cat.: 5b(vi) Reason Code: 62 MR Endorsement Date: 11-11-2002
 (3) Sub Div.: 3 Mixed Feature Party: IL8102&EXT Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 11-11-2002

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 18-10-2006
 Data Source: EI(Lands D)
 Slope Part Drainage: N/A
 Wall Part Drainage: N/A

SLOPE PART



Slope Part (1)

Surface Protection (%): Bare: 60 Vegetated: 40 Chunam: 0 Shotcrete: 0 Other Cover: 0
 Material Description: Material type: Soil Geology: Decomposed granite
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): N/A Spacing (m): N/A

WALL PART

Wall Part (1)

Type of Wall: Wall Material: Masonry Wall Location: Wall at toe
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 80 Spacing (m): 1

SERVICES

N/A

CHECKING STATUS INFORMATION

Tagmark: SCS_18108 Part: 1 Checking Status: Feature modified/upgraded to current standard Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B8
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: N/A
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 18-10-2006
 Date of Construction, Subsequent Modification and Demolition: N/A
 Related Reports/Files or Documents: N/A
 Remarks: DH Order DH 161/HK/98 Issued is for the wall part of the feature.
 Follow Up Actions: N/A
 DH-Order (To Be Confirmed with Buildings Department): Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 30/03/2011 Notice No.: DH0035/HK/11/C
 Date of Recommendation to BD: 27/10/1997 File Reference: DH/020/84/HK
 Date Served by BD: 10/08/1998 Notice No.: DH161/HK/98/C
 Advisory Letter (To Be Confirmed with Buildings Department): None


LPMIS: Agreement No.: CE15/2009 Report No.: S3R120/2011
 Agreement No.: CE31/2005 Report No.: N/A
 Agreement No.: CE33/93 Report No.: S2R 64/95

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On: 03-12-1997
 Weather: Mainly Fine
 District: I



Section No: 1-1
 Height(m): H1 : 12 , H2 : 8
 Type of Toe Facility: Residential building
 Distance from Toe(m): 3
 Type of Crest Facility: Densely-used open area/facilities
 Distance from Crest(m): 5
 Consequence Category: 1
 Engineering Judgement: P
 Section No: 2-2
 Type of Toe Facility: N/A
 Distance from Toe(m): 0
 Type of Crest Facility: N/A
 Distance from Crest(m): 0
 Consequence Category: 1
 Engineering Judgement: P
 Sign of Seepage: Slope : No signs of seepage
 Wall : No sign of seepage
 Criterion A satisfied: N
 Sign of Distress: Slope : N/A
 Wall : Moderate(near crest, mid-portion, at toe)
 Criterion D satisfied: N
 Non-routine maintenance required: N

Note: N/A
Masonry wall/Masonry facing: Y
Note: Dressed block toe wall.
Consequence category (for critical section): 1
Observations: N/A
Emergency Action Required: N
Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A
Action By: N/A
Further Study: N
Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services: N
Action By: N/A
Non-routine Maintenance: N
Action By: N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.: 11SW-B/CR 349
Location: North East of ST. Francis Canossian College, Kennedy Road, Wan Chai
District Council: Wanchai
Maintenance Responsibility (At the Time of Selection): Mixed
Responsible Party for Maintenance of Government Portion: Lands D
Private Lot No.: IL2140, IL8102 and EXT

LPM/LPMit Study

Agreement No.: CE15/2009
Study Type: Stage 3 Study Under Schedule of Rates Contract
Consultant: AECOM Asia Co. Ltd.
GEO Managing Section / Engineer: LPM3 / CM71
Study Status: Study completed
Design Approach: Prescriptive
Option Assessment Accepted: Y
Study Report No.: S3R120/2011

Programme / Actual Commencement: 21-12-2011
Programme / Actual Completion: 01-01-2012
Report Recommendation (For Stage 2 Study): Upgrading Works
District Check Status: N/A
Checking Certificate No.: GEO/LPM155/2012
GEO Engineer's Remarks: N/A

LPM/LPMit Works

Works Contract No.: GE/2011/02
GEO Managing Section / Engineer: LPM3 / CM71
Contractor: Shun Yuen Construction Co Ltd
Progress Status: Maintenance completed
Reason of Study Termination / Works Deletion (If Necessary): N/A
Forecast Commencement Date: 16-02-2012
Forecast Completion Date: 01-09-2012
Completion Cert. Issued: 14-09-2012
Site Handed Over to Maintenance Department on: 28-10-2013
Estimated Cost for Upgrading (HK\$M): 0.2587
Maintenance Manual No.: MM155/2012
Actual Works: Soil nail
No. of Tree Felled: N/A
No. of Tree Planted (Incl. Transplant): N/A
% Bare of Slope Surfacing: N/A
% Vegetated of Slope Surfacing: 30
% Shotcrete of Slope Surfacing: N/A
Other Hard Surface of Slope Surfacing: 70

LPM/LPMit Details Report

LPM Study Feature No.: 11SW-B/CR 349
Location: North East of ST. Francis Canossian College, Kennedy Road, Wan Chai
District Council: Wanchai
Maintenance Responsibility (At the Time of Selection): Mixed
Responsible Party for Maintenance of Government Portion: Lands D
Private Lot No.: IL2140, IL8102 and Ext

LPM/LPMit Study

Agreement No.: CE31/2005
Study Type: Stage 3 Study Under Schedule of Rates Contract
Consultant: C M Wong & Associates Ltd.
GEO Managing Section / Engineer: LPM2 / CM43
Study Status: Study deferred - To be considered in other LPM/LPMit Agreement
Design Approach: N/A
Option Assessment Accepted: N/A
Study Report No.: N/A

Programme / Actual Commencement:	N/A
Programme / Actual Completion:	N/A
Report Recommendation (For Stage 2 Study):	N/A
District Check Status:	N/A
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	It is anticipated that it will take a long time to resolve the access and works area issue with the owner and inclusion of this feature into the Batch B SoR Contract is undesirable. {Deferred in LPMP due to Access}

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/R 628
Location:	{55 SHIP STREET, WANCHAI}
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Private
Responsible Party for Maintenance of Government Portion:	N/A
Private Lot No.:	NA

LPM/LPMit Study

Agreement No.:	CE33/93
Study Type:	Stage 2 Study
Consultant:	Mott Connell Ltd.
GEO Managing Section / Engineer:	LPM3 / CM62
Study Status:	Study completed
Design Approach:	Otherwise
Option Assessment Accepted:	N/A



Study Report No.:	S2R 64/95
Programme / Actual Commencement:	01-06-1994
Programme / Actual Completion:	31-08-1998
Report Recommendation (For Stage 2 Study):	DH Order
District Check Status:	Checked
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	N/A

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO



BASIC INFORMATION

Location: Behind 55 Ship Street, Wan Chai South, Hong Kong
Registration Date: 10-12-1999
Ranking Score (NPRS): 0 (LPMit)
Date of Formation: pre-1977
Date of Construction/ Modification:
Data Source: LPM
Approximate Coordinates: Easting : 835507 Northing : 815141

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: School
Distance of Facility from Crest (m): 5
Facility at Toe: Remote area or abandoned facilities
Distance of Facility from Toe (m): 2
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

(1) Max. Height (m): 9 Length (m): 21 Average Angle (deg): 60

WALL PART

(1) Max. Height (m): 5 Length (m): 21 Face Angle (deg): 90

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 1 Mixed Feature Party: IL1940 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-05-2000
(2) Sub Div.: 2 Mixed Feature Party: IL2140 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-05-2000
(3) Sub Div.: 3 Mixed Feature Party: Lands D Agent: Lands D Land Cat.: 5b(vi) Reason Code: 62 MR Endorsement Date: 22-05-2000

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 01-08-2016
Data Source: LPM
Slope Part Drainage: (1) Position: Crest Size(mm): 200
Wall Part Drainage: N/A

SLOPE PART



Slope Part (1)

Surface Protection (%): Bare: 10 Vegetated: 70 Chunam: 0 Shotcrete: 20 Other Cover: 0
 Material Description: Material type: Soil Geology: N/A
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): N/A Spacing (m): N/A

WALL PART

Wall Part (1)

Type of Wall: Wall Material: Concrete Wall Location: Wall at toe
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 50 Spacing (m): 1.8

SERVICES

N/A

CHECKING STATUS INFORMATION

N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B8
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: N/A
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 01-08-2016
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1978 After: N/A
 Related Reports/Files or Documents: File/Report: GEO Ref. No.: SIR097/86(9/86)
 File/Report: GEO Ref. No.: SIR097/86(9/86)
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 Remarks: N/A
 Follow Up Actions: N/A


DH-Order (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: 27/07/1983	File Reference: DH/0346/66/HK
	Date Served by BD: 16/02/1984	Notice No.: DH1/HK/84
	Date of Recommendation to BD: 27/07/1983	File Reference: DH/0346/66/HK
	Date Served by BD: 06/04/1984	Notice No.: DH1A/HK/84
	Date of Recommendation to BD: 27/07/1983	File Reference: DH/0002/84/HK
	Date Served by BD: 16/02/1984	Notice No.: DH2/HK/84
Advisory Letter (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: N/A	File Reference: N/A
	Date Served by BD: 21/05/2004	
LPMIS:	Agreement No.: CE62/2001	Report No.: S2R220/2003

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On: 22-02-2000
 Weather: Some Rain
 District: I



Section No:	1-1
Height(m):	H1 : 14 , H2 : 5
Type of Toe Facility:	Remote area or abandoned facilities
Distance from Toe(m):	2
Type of Crest Facility:	School
Distance from Crest(m):	5
Consequence Category:	1
Engineering Judgement:	HP
Section No:	2-2
Type of Toe Facility:	N/A
Distance from Toe(m):	0
Type of Crest Facility:	N/A
Distance from Crest(m):	0
Consequence Category:	1
Engineering Judgement:	HP

Sign of Seepage:	Slope : No signs of seepage Wall : No sign of seepage
Criterion A satisfied:	N
Sign of Distress:	Slope : N/A Wall : N/A
Criterion D satisfied:	N
Non-routine maintenance required:	N
Note:	N/A
Masonry wall/Masonry facing:	N
Note:	N/A
Consequence category (for critical section):	1
Observations:	N/A
Emergency Action Required:	N
Action By:	N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D:	N/A
Action By:	N/A
Further Study:	Y
Action By:	Private

OTHER EXTERNAL ACTION

Check / repair Services:	N
Action By:	N/A
Non-routine Maintenance:	N
Action By:	N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/CR 252
Location:	BEHIND 55 SHIP STREET, WAN CHAI SOUTH
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Mixed
Responsible Party for Maintenance of Government Portion:	Lands D
Private Lot No.:	IL1940, IL2140

LPM/LPMit Study

Agreement No.:	CE62/2001
Study Type:	Stage 2 Study


Consultant:	Maunsell Geotechnical Services Ltd.
GEO Managing Section / Engineer:	SS / SS3
Study Status:	Study completed
Design Approach:	N/A
Option Assessment Accepted:	N/A
Study Report No.:	S2R220/2003
Programme / Actual Commencement:	05-06-2003
Programme / Actual Completion:	06-03-2004
Report Recommendation (For Stage 2 Study):	Advisory Letter, No action required
District Check Status:	Checked
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	N/A

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO







BASIC INFORMATION

Location: Below St.Franeis Canoossian College, 9-13 Kennedy Road
 Registration Date: 10-12-1999
 Ranking Score (NPRS): 0 (N/A)
 Date of Formation: post-1977
 Date of Construction/ Modification:
 Data Source: EI(Lands D)
 Approximate Coordinates: Easting : 835497 Northing : 815153

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Undeveloped green belt
 Distance of Facility from Crest (m): 0
 Facility at Toe: Lightly-used open area/facilities
 Distance of Facility from Toe (m): 0
 Consequence-to-life Category: 3
 Remarks: N/A

SLOPE PART

(1) Max. Height (m): 8.5 Length (m): 18 Average Angle (deg): 70

WALL PART

(1) Max. Height (m): 2 Length (m): 10 Face Angle (deg): 88

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 1 Mixed Feature Party: IL8102 & EXT Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-05-2000
 (2) Sub Div.: 2 Mixed Feature Party: IL1669 Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-05-2000
 (3) Sub Div.: 3 Mixed Feature Party: IL1564 Agent: N/A Land Cat.: 1,5b(vi),7 Reason Code: 1 MR Endorsement Date: 22-05-2000
 (4) Sub Div.: 4 Mixed Feature Party: IL2272 & EXT Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-05-2000
 (5) Sub Div.: 5 Mixed Feature Party: Lands D Agent: Lands D Land Cat.: 5b(vi) Reason Code: 62 MR Endorsement Date: 22-05-2000

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 15-06-2006
 Data Source: EI(Lands D)
 Slope Part Drainage: (1) Position: On slope Size(mm): 150
 Wall Part Drainage: (1) Position: Downpipe Size(mm): 100

SLOPE PART



Slope Part (1)

Surface Protection (%): Bare: 0 Vegetated: 100 Chunam: 0 Shotcrete: 0 Other Cover: 0
 Material Description: Material type: Soil Geology: N/A
 Berm: No. of Berms: 1 Min. Berm Width (m): 2.8
 Weepholes: Size (mm): N/A Spacing (m): N/A

WALL PART

Wall Part (1)

Type of Wall: Wall Material: Masonry Wall Location: Retaining wall with level platform
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 50 Spacing (m): 1.8

SERVICES

(1) Utilities Type: Water Main Size(mm): 50 Location: On slope Remark: N/A

CHECKING STATUS INFORMATION

Tagmark: 7636_0_1 Part: 0 Checking Status: No checking records Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B7
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 23882-97 (1978),
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 15-06-2006
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1978 After: N/A
 Related Reports/Files or Documents: File/Report: DB or DH Ref. No.: DH 2/HK/184
 File/Report: DB or DH Ref. No.: DH 2/HK/184
 File/Report: DB or DH Ref. No.: DH1/HK/184
 File/Report: DB or DH Ref. No.: DH1/HK/184
 File/Report: GEO Ref. No.: STAGE 1 (1991/09/20) (NFA)
 File/Report: GEO Ref. No.: STAGE 1 (1991/09/20) (NFA)
 File/Report: Previous Instability Ref. No.: 18/6/83
 File/Report: Previous Instability Ref. No.: 18/6/83
 Remarks: N/A
 Follow Up Actions: N/A



DH-Order (To Be Confirmed with Buildings Department): None
 Advisory Letter (To Be Confirmed with Buildings Department): None
 LPMIS: None

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On:
 Weather:
 District: I
 Section No: 1-1
 Height(m):
 Type of Toe Facility: Lightly-used open area/facilities
 Distance from Toe(m): 0
 Type of Crest Facility: Undeveloped green belt
 Distance from Crest(m): 0
 Consequence Category:
 Engineering Judgement:
 Section No: 2-2
 Type of Toe Facility:
 Distance from Toe(m):
 Type of Crest Facility:
 Distance from Crest(m):
 Consequence Category:
 Engineering Judgement:
 Sign of Seepage:
 Criterion A satisfied:
 Sign of Distress:
 Criterion D satisfied:
 Non-routine maintenance required:
 Note:
 Masonry wall/Masonry facing:
 Note:
 Consequence category (for critical section):
 Observations: N/A
 Emergency Action Required:
 Action By: N/A




ACTION TO INITIATE PREVENTIVE WORKS


Criterion A/Criterion D: N/A
Action By: N/A
Further Study:
Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services:
Action By: N/A
Non-routine Maintenance:
Action By: N/A

PHOTO







BASIC INFORMATION

Location: ST. FRANCIS CANOSSIAN SCHOOL, ST. FRANCIS STREET, WAN CHAI
 Registration Date: 16-03-1998
 Ranking Score (NPRS): 608 (Notional)
 Date of Formation: post-1977
 Date of Construction/ Modification: 18-03-2011
 Data Source: AP
 Approximate Coordinates: Easting : 835462 Northing : 815162

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Road/footpath with low traffic density
 Distance of Facility from Crest (m): 1
 Facility at Toe: School
 Distance of Facility from Toe (m): 3
 Consequence-to-life Category: 1
 Remarks: N/A

SLOPE PART

(1) Max. Height (m): 18 Length (m): 80 Average Angle (deg): 45

WALL PART

(1) Max. Height (m): 5.5 Length (m): 36 Face Angle (deg): 90

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 0 Private Feature Party: IL8102 & EXT Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 22-07-2005

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 27-02-2012
 Data Source: AP
 Slope Part Drainage: (1) Position: Crest Size(mm): 260
 (2) Position: Downpipe Size(mm): 150
 (3) Position: Downpipe Size(mm): 600
 (4) Position: On slope Size(mm): 400
 (5) Position: On slope Size(mm): 300
 (6) Position: On slope Size(mm): 225
 (7) Position: Toe Size(mm): 800
 (8) Position: Toe Size(mm): 300



Wall Part Drainage:

(1)	Position: Crest	Size(mm): 225
(2)	Position: Crest	Size(mm): 300
(3)	Position: Downpipe	Size(mm): 275
(4)	Position: Toe	Size(mm): 150
(5)	Position: Toe	Size(mm): 300

SLOPE PART

Slope Part (1)
 Surface Protection (%): Bare: 0 Vegetated: 30 Chunam: 0 Shotcrete: 0 Other Cover: 70
 Material Description: Material type: Soil Geology: N/A
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 65 Spacing (m): 1.2

WALL PART

Wall Part (1)
 Type of Wall: Wall Material: Concrete Wall Location: Wall at toe
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 95 Spacing (m): 1.2

SERVICES

N/A

CHECKING STATUS INFORMATION

Tagmark: SCS_13923 Part: 0 Checking Status: Feature modified/upgraded to current standard Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B7
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 23897 (1978), 23882 (1978)
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 27-02-2012
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1978 After: 1978

Related Reports/Files or Documents: File/Report: Development Ref. No.: GCI3/4/1152/78, 1077/82, 2140/72, 1259/29
 File/Report: Development Ref. No.: GCI3/4/1152/78, 1077/82, 2140/72, 1259/29
 File/Report: GEO Ref. No.: Stage 1 report by design 04/93
 File/Report: GEO Ref. No.: Stage 1 report by design 04/93
 File/Report: Ground Anchors Ref. No.: No.24 1/2140/74
 File/Report: Ground Anchors Ref. No.: No.24 1/2140/74
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: LSR Ref. No.: LSR 6/2001 (HK2000/08/021)
 File/Report: LSR Ref. No.: LSR 6/2001 (HK2000/08/021)
 File/Report: Other Ref. No.: SIRST Field Sheet
 File/Report: Other Ref. No.: SIRST Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet


Remarks: N/A
 Follow Up Actions: N/A
 DH-Order (To Be Confirmed with Buildings Department): Date of Recommendation to BD: 05/10/2007 File Reference: N/A
 Date Served by BD: N/A Notice No.: N/A
 Advisory Letter (To Be Confirmed with Buildings Department): Date of Recommendation to BD: N/A File Reference: N/A
 Date Served by BD: 20/06/2007
 LPMIS: None

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On: 11-01-2000
 Weather: Mainly Fine
 District: I



Section No: I-1
 Height(m): H1 : 19 , H2 : 6
 Type of Toe Facility: School
 Distance from Toe(m): 3
 Type of Crest Facility: Road/footpath with low traffic density
 Distance from Crest(m): 1



Consequence Category: 1
 Engineering Judgement: P
 Section No: 2-2
 Type of Toe Facility: N/A
 Distance from Toe(m): 0
 Type of Crest Facility: N/A
 Distance from Crest(m): 0
 Consequence Category: 1
 Engineering Judgement: P
 Sign of Seepage: Slope : No signs of seepage
 Wall : No sign of seepage
 Criterion A satisfied: N
 Sign of Distress: Slope : N/A
 Wall : N/A
 Criterion D satisfied: N
 Non-routine maintenance required: N
 Note: N/A
 Masonry wall/Masonry facing: N
 Note: N/A
 Consequence category (for critical section): 1
 Observations: N/A
 Emergency Action Required: N
 Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A
 Action By: N/A
 Further Study: Y
 Action By: Private

OTHER EXTERNAL ACTION

Check / repair Services: N
 Action By: N/A
 Non-routine Maintenance: N
 Action By: N/A

PHOTO





BASIC INFORMATION

Location: No. 18 Sau Wa Fong, Hong Kong - Lot No. I.L. 199 R.P.
Registration Date: 16-03-1998
Ranking Score (NPRS): 73 (LPMit)
Date of Formation: post-1977
Date of Construction/ Modification: 24-07-2022
Data Source: AP
Approximate Coordinates: Easting : 835515 Northing : 815179

CONSEQUENCE-TO-LIFE CATEGORY

Facility at Crest: Cottage, licensed and squatter area
Distance of Facility from Crest (m): 0
Facility at Toe: Residential building
Distance of Facility from Toe (m): 0
Consequence-to-life Category: 1
Remarks: N/A

SLOPE PART

N/A

WALL PART

(1) Max. Height (m): 11.8 Length (m): 25 Face Angle (deg): 85

MAINTENANCE RESPONSIBILITY

(1) Sub Div.: 0 Private Feature Party: IL199 RP Agent: N/A Land Cat.: 1 Reason Code: 1 MR Endorsement Date: 25-09-2013

DETAILS OF SLOPE / RETAINING WALL

Date of Inspection: 28-08-2022
Data Source: AP
Slope Part Drainage: N/A
Wall Part Drainage: (1) Position: Toe Size(mm): 300

SLOPE PART

N/A

WALL PART



Wall Part (1)

Type of Wall: Wall Material: Masonry Wall Location: Retaining wall with level platform
 Berm: No. of Berms: N/A Min. Berm Width (m): N/A
 Weepholes: Size (mm): 90 Spacing (m): 1.2

SERVICES

(1) Utilities Type: Water Main Size(mm): 45 Location: On slope Remark: N/A

CHECKING STATUS INFORMATION

Tagmark: SCS_20036 Part: 0 Checking Status: Feature modified/upgraded to current standard Checking Certificate No.: N/A

BACKGROUND INFORMATION

GIU Cell Ref.: 11SW14B8
 Map Sheet Reference (1:1000): 11SW-14B
 Aerial Photos: 6122-3 (1949),
 Nearest Rainguage Station (Station Number): 25 Borrett Road(H17)
 Data Collected On: 28-08-2022
 Date of Construction, Subsequent Modification and Demolition: Modification: Constructed Before: 1949 After: N/A
 Modification: Substantially Modified Before: N/A After: 1981
 Related Reports/Files or Documents: File/Report: DB or DH Ref. No.: GCI3/4/DH32/82/HK
 File/Report: DB or DH Ref. No.: GCI3/4/DH32/82/HK
 File/Report: Development Ref. No.: GCI3/4/1152/78
 File/Report: Development Ref. No.: GCI3/4/1152/78
 File/Report: GEO Ref. No.: Stage 1 report by planning
 File/Report: GEO Ref. No.: Stage 1 report by planning
 File/Report: GEO Ref. No.: Stage 2 report 4/88, File closed.
 File/Report: GEO Ref. No.: Stage 2 report 4/88, File closed.
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: LRDC Ref. No.: D346/66/HK
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Pre-SIRST Ref. No.: Field Sheet
 File/Report: Previous Instability Ref. No.: 9/3/92 92/3/3
 File/Report: Previous Instability Ref. No.: 9/3/92 92/3/3
 Remarks: N/A
 Follow Up Actions: N/A



DH-Order (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 05/03/2021	Notice No.: DH0005/HK/21/C
	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 06/03/2015	Notice No.: DH0038/HK/15/C
Advisory Letter (To Be Confirmed with Buildings Department):	Date of Recommendation to BD: 13/08/2014	File Reference: DH/0032/80/HK
	Date Served by BD: 11/11/2020	Notice No.: DH0062/HK/20/C
	Date of Recommendation to BD: 16/03/1992	File Reference: DH032/80/HK
	Date Served by BD: 26/10/1992	
LPMIS:	Date of Recommendation to BD: 16/03/1992	File Reference: D 365/75/HK
	Date Served by BD: 25/01/1996	
	Date of Recommendation to BD: 14/02/2012	File Reference: DH032/80/HK
	Date Served by BD: 04/06/2012	
	Agreement No.: CE58/2009	Report No.: S2R 23/2012
	Agreement No.: In-house Design	Report No.: S2R 4/88

ENHANCED MAINTENANCE INFORMATION

From Maintenance Department: (Last Updated Date: 01/08/2024)

STAGE 1 STUDY REPORT

Inspected On:

Weather:

District: I

Section No: 1-1

Height(m):

Type of Toe Facility: Residential building

Distance from Toe(m): 0

Type of Crest Facility: Cottage, licensed and squatter area

Distance from Crest(m): 0

Consequence Category:

Engineering Judgement:

Section No: 2-2

Type of Toe Facility:

Distance from Toe(m):

Type of Crest Facility:

Distance from Crest(m):

Consequence Category:

Engineering Judgement:

Sign of Seepage:

Criterion A satisfied:

Sign of Distress:

Criterion D satisfied:

Non-routine maintenance required:

Note:

Masonry wall/Masonry facing:

Note:

Consequence category (for critical section):

Observations: N/A

Emergency Action Required:

Action By: N/A

ACTION TO INITIATE PREVENTIVE WORKS

Criterion A/Criterion D: N/A

Action By: N/A

Further Study:

Action By: N/A

OTHER EXTERNAL ACTION

Check / repair Services:

Action By: N/A

Non-routine Maintenance:

Action By: N/A

eLPMIS

LPM/LPMit Details Report

LPM Study Feature No.:	11SW-B/R 617
Location:	SOUTH OF NO.18 SAN WAH FONG
District Council:	Wanchai
Maintenance Responsibility (At the Time of Selection):	Private
Responsible Party for Maintenance of Government Portion:	N/A
Private Lot No.:	IL199 RP

LPM/LPMit Study

Agreement No.:	CE58/2009
Study Type:	Stage 2 Study
Consultant:	Atkins China Ltd.
GEO Managing Section / Engineer:	SS / SS3
Study Status:	Study completed
Design Approach:	N/A
Option Assessment Accepted:	N/A
Study Report No.:	S2R 23/2012
Programme / Actual Commencement:	20-02-2012

Programme / Actual Completion: 27-10-2012
Report Recommendation (For Stage 2 Study): DH Order
District Check Status: Exempted from checking
Checking Certificate No.: N/A
GEO Engineer's Remarks: N/A

LPM/LPMit Works

Works Contract No.: N/A
GEO Managing Section / Engineer: N/A / N/A
Contractor: N/A
Progress Status: N/A
Reason of Study Termination / Works Deletion (If Necessary): N/A
Forecast Commencement Date: N/A
Forecast Completion Date: N/A
Completion Cert. Issued: N/A
Site Handed Over to Maintenance Department on: N/A
Estimated Cost for Upgrading (HK\$M): N/A
Maintenance Manual No.: N/A
Actual Works: N/A
No. of Tree Felled: N/A
No. of Tree Planted (Incl. Transplant): N/A
% Bare of Slope Surfacing: N/A
% Vegetated of Slope Surfacing: N/A
% Shotcrete of Slope Surfacing: N/A
Other Hard Surface of Slope Surfacing: N/A

LPM/LPMit Details Report

LPM Study Feature No.: 11SW-B/R 617
Location: SOUTH OF NO.18 SAN WAH FONG
District Council: Wanchai
Maintenance Responsibility (At the Time of Selection): Private
Responsible Party for Maintenance of Government Portion: N/A
Private Lot No.: NA

LPM/LPMit Study

Agreement No.: In-house Design
Study Type: Stage 2 Study
Consultant: N/A
GEO Managing Section / Engineer: LPM2 / N/A
Study Status: Study completed
Design Approach: Conventional (G1 + Analysis)
Option Assessment Accepted: N/A
Study Report No.: S2R 4/88
Programme / Actual Commencement: N/A




Programme / Actual Completion:	N/A
Report Recommendation (For Stage 2 Study):	No action required
District Check Status:	Not checked
Checking Certificate No.:	N/A
GEO Engineer's Remarks:	NO FURTHER ACTION

LPM/LPMit Works

Works Contract No.:	N/A
GEO Managing Section / Engineer:	N/A / N/A
Contractor:	N/A
Progress Status:	N/A
Reason of Study Termination / Works Deletion (If Necessary):	N/A
Forecast Commencement Date:	N/A
Forecast Completion Date:	N/A
Completion Cert. Issued:	N/A
Site Handed Over to Maintenance Department on:	N/A
Estimated Cost for Upgrading (HK\$M):	N/A
Maintenance Manual No.:	N/A
Actual Works:	N/A
No. of Tree Felled:	N/A
No. of Tree Planted (Incl. Transplant):	N/A
% Bare of Slope Surfacing:	N/A
% Vegetated of Slope Surfacing:	N/A
% Shotcrete of Slope Surfacing:	N/A
Other Hard Surface of Slope Surfacing:	N/A

PHOTO



Appendix C


Architectural Plans of Indicative Development Scheme (Please refer to Appendix 1 of the SPS)

Appendix D

Layout of Piezometre P3a and P4

Appendix E

Record Plan of St. Francis' Canossian College



**SITE FORMATION WORKS – BEFORE DEMOLITION
LAYOUT PLAN FOR PHASE 1
(STAGE 0)**

Plan Approved
WAI PAN
 Senior Building Surveyor
 for BUILDING AUTHORITY
 - 5 AUG 2010

BD REF No. BD / 3036/09

NOTES:
 1. ALL LOWEST GROUND FLOOR SLAB IS TO BE RETAINED AFTER DEMOLITION.

- LEGEND**
- SITE BOUNDARY
 - - - EXISTING FEATURE
 - - - EXISTING RETAINING
 - [Green Hatched] PROPOSED MASS CONCRETE FILL
 - [Green Solid] PROPOSED 4% MAX MASS CONCRETE FILL
 - [Diagonal Hatched] EXISTING SCREEN WALL TO BE RETAINED
 - [Cross-hatched] EXISTING RETAINING WALL INSIDE EXISTING BUILDING TO BE RETAINED
 - [Square] PROPOSED RAIN PIT
 - [Triangle] DEVELOPED ELEVATION
 - [Circle] SECTION MARK
 - [+52.2] EXISTING GROUND LEVEL
 - [Circle with +] EXISTING FRESH WATER MAIN
 - [Circle with -] EXISTING GAS MAIN
 - [Circle with X] EXISTING DRAINAGE
 - [Circle with L] EXISTING LIGHTING CABLE
 - [Circle with D] EXISTING HDG. DUCT
 - [Circle with P] EXISTING FIBRE OPTIC/PRIOT CABLE (FMC)
 - [Circle with W] EXISTING HWF CABLE
 - [Circle with CH] SITE SPECIFIC CDRHOLE
 - [Circle with BH] SITE SPECIFIC BOREHOLE
 - [Circle with TP] SITE SPECIFIC TRIAL PIT
 - [Circle with DR] EXISTING BOREHOLE
 - [Circle with F] EXISTING FOOTING (FOUNDING ON +57.4mPD)

SIU Koon Hoi, Carmine (邵冠剛)
 Authorized Person - APEI 9982
 Registered Structural Engineer - RSE 9682
 Registered Geotechnical Engineer - RGE 9432

BD SUBMISSION: - JUNE 2010
 REVISIONS TO DRAWING: No. DATE BY

IMPORTANT: DO NOT SCALE THIS DRAWING. ALL DIMENSIONS SHOULD BE CHECKED ON SITE.

PROJECT: **PROPOSED REDEVELOPMENT OF ST. FRANCIS CATHOLIC COLLEGE**

CLIENT: **The Mother Superiores of the Daughters of Charity of the Concessian Institute (Hong Kong)**

TITLE: **PROPOSED SITE FORMATION WORKS LAYOUT PLAN FOR PHASE 1 (STAGE 0)**

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-SF111	MAY 2010	-

SCALE	DESIGNED	DRAWN	CHECKED	APPROVED
1:150	YKT	CL	BC	PY

The ownership of the copyright in this drawing is retained by the client. It is to be used only for the purposes for which it was prepared and no other use without the written consent of the architect or his/her firm.

ARCHITECT

Aedas

Aedas Ltd.
 31/F One Island East
 1/B Westlands Road
 Quarry Bay
 Hong Kong

T: +852 2861 1728
 F: +852 2829 0419
 www.aedas.com


MEINHARDT

Meinhardt (C&S) Ltd.
 Consulting Engineers

117 Man Yee Centre
 417 Queen's Road West
 Hong Kong

Telephone: +852 2718 1118
 Fax: +852 2718 1117

PROPOSED MASS CONCRETE FILL	DRAINAGE (mm ²)	ALLOWABLE FINISHING (CENTIMETER) (mm)
MASS CONCRETE B1	29.4	70
MASS CONCRETE B2	25.6	70
MASS CONCRETE B3	33.2	70
MASS CONCRETE B4	118.1	70
MASS CONCRETE B5	100.6	70
MASS CONCRETE B6	105.5	70
MASS CONCRETE B7	117.1	70
MASS CONCRETE B8	85.5	70
MASS CONCRETE B9	27.8	70
MASS CONCRETE B10	175.8	70




LEGEND

- SITE BOUNDARY
- - - EXISTING FEATURE
- - - EXISTING RETAINING
- [Pattern] PROPOSED MASS CONCRETE FILL
- BM+ EXISTING BOREHOLE
- TP1 EXISTING TRIAL PIT
- CP1-H1 303x305x180 kg/m PREBORED SOCKET H-PILE
- FD1-1 PROPOSED PREDRILLING
- +S1.35 FILE CAP TOP LEVEL
- ⊙ SECTION MARK
- [Symbol] EXISTING FOOTING (FOUNDING ON +S7.4mPD)
- PROPOSED PIPE PILE WALL (UNDER SITE FORMATION SUBMISSION)

Plan Approved

 TAM A Ray
 Senior Structural Engineer
 for BUILDING AUTHORITY
 20 OCT 2011


 Lee Wan Chung
 Registered Structural Engineer
 (RSE 101199)

2ND AMENDMENT	A	B	SEP 2011
1ST AMENDMENT	A	A	JAN 2011
BD SUBMISSION			AUG 2010

REVISIONS TO DRAWING

No.	DATE	BY

IMPORTANT: DO NOT SCALE THIS DRAWING
 ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT: PROPOSED DEVELOPMENT OF ST. FRANCIS CANNOSIAN COLLEGE

CLIENT: The Mother Superioress of the Daughters of Charity of the Canossian Institute (Hong Kong)

TITLE: PROPOSED FOUNDATION WORKS
 PILING LAYOUT PLAN FOR PHASE 1

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-FP111	08/10	B


SCALE	DESIGNED	DRWN	CHECKED	APPROVED
1:100	YKT	CL	PY	BC

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RESERVED BY MEINHARDT (C&S) LTD. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM.

ARCHITECT: **Aedas**

Aedas Ltd.
 31/F One Island East
 1/B Westlands Road
 Quarry Bay
 Hong Kong
 T +852 2861 1728
 F +852 2859 6419
 E hongkong@aedas.com
 aedas.com

MEINHARDT
 Meinhardt (C&S) Ltd. Consulting Engineers
 4/F Hop Wing Centre
 402 Queen's Road West
 Hong Kong
 Telephone: 2858 0116
 Facsimile: 2517 9107



RECEIVED BY
 28 SEP 23 P 3:57
 BUILDING DEPARTMENT

REGISTERED

REGISTERED

11SW-B/FR 29
 NORTHERN PORTION OF SLOPE
 TO BE RECOMPACTION AND
 REINSTATE TO MAX. 3%

EXISTING FEATURE
 11SW-B/582

11SW-B/R 585

EXISTING BUILDING
 REMAIN OPERATION

St. Francis Canossian College

EXISTING SECC BUILDING

PROPOSED PIPE PILE WALL
 (UNDER SITE FORMATION
 SUBMISSION)

EXISTING FEATURE
 11SW-B/CR 349

11SW-B/R 586

11SW-B/R 643

11SW-B/R 988

11SW-B/R 584






EXISTING FEATURE

PHASE 2

PHASE 1

SITE BOUNDARY

LEGEND

-  PROPOSED MASS CONCRETE FILL
-  EXISTING SCREEN WALL OR RETAINING WALL
-  D.W.I. (+53.5)
-  DESIGN GROUND WATER LEVEL
-  EXISTING UTILITIES

WONG Hui Nam Steve
 CEng, MStrutE, MICE, RPE
 Registered Structural Engineer
 (RSE 600)

SIU Koon Hoi, Carmine (邵冠期)
 Authorized Person - AP(E)-9982
 Registered Structural Engineer - RSE-9982
 Registered Geotechnical Engineer - RGE 9982

BD SUBMISSION	NO.	DATE	BY
		JUNE 2010	

IMPORTANT: DO NOT SCALE THIS DRAWING
 ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT **PROPOSED REDEVELOPMENT OF ST. FRANCIS CASSIAN COLLEGE**

CLIENT **The Mother Superioress of the Daughters of Charity of the Cassianian Institute (Hong Kong)**

TITLE **PROPOSED SITE FORMATION WORKS SECTION A1 - A1 FOR PHASE 1**





PROJECT NO.	DRG. NO.	DATE	REV.	
CS1278	1278-SF211	MAY 2010	-	
SCALE	DESIGNED	DRAWN	CHECKED	APPROVED
1:200	YKT	CL	BC	PY

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY MEINHARDT (C&S) LTD. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE WRITTEN PERMISSION OF MEINHARDT (C&S) LTD.


ARCHITECT

Aedas
 Aedas Ltd.
 31/F One Island East
 118 Westlands Road
 Quarry Bay
 Hong Kong
 T +852 2861 1728
 F +852 2529 0419
 E hongkong@aedas.com
 aedas.com

MEINHARDT
 Meinhardt (C&S) Ltd.
 Consulting Engineers
 4/F Wah Wing Centre
 421 Queen's Road West
 Telephone: 2926 0728




2010 JUN - 8 P. 5 03
 B.D. SUBMISSION
 BALL SITE FORMATION



STAGE 0: (BEFORE DEMOLITION)


1. INSTALLATION OF MONITORING CHECK POINT (FOR DEMOLITION)
2. CONSTRUCTION MASS CONCRETE FILL A1 & MASS CONCRETE STEP.
3. CARRY OUT DEMOLITION WORKS (LOWEST GROUND FLOOR SLAB IS TO BE RETAINED AFTER DEMOLITION)

No Demolition Works until All Mass Concrete Complete and approved Design Structure




STAGE 1: (AFTER DEMOLITION)

1. COMPLETION OF DEMOLITION WORKS



STAGE 2: (SITE FORMATION)

1. INSTALLATION OF MONITORING CHECK POINT (SECTION FOR STAGE 2-3)
2. CARRY OUT SITE FORMATION WORKS (STAGE 2) - EXCAVATION & REINFORCE MASS CONCRETE FILL A1
3. CARRY OUT FOUNDATION AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)



STAGE 3: (FINAL SITE FORMATION - AFTER SUPERSTRUCTURE CONSTRUCTION)

1. COMPLETION OF FOUNDATION WORKS AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)
2. CARRY OUT FINAL FORMATION WORKS (STAGE 3) - REINFORCE MASS CONCRETE FILL A1

B.D. REF. No. BD /3036/09

LEGEND

- PROPOSED MASS CONCRETE FILL
- EXISTING SCREEN WALL OR RETAINING WALL
- PROPOSED WELL COMPACTED BACKFILL
- D.W.T. (+53.5) DESIGN GROUND WATER LEVEL
- EXISTING UTILITIES

WONG Wah Sang Steve
 CEng, MBS, MIE, MSEE, RPE
 Registered Structural Engineer
 (RSE 6/00)

SIU Koon Hoi, Carmine (邵冠賢)
 Authorized Person - APE 98/82
 Registered Structural Engineer - RSE 98/82
 Registered Geotechnical Engineer - RGE 98/82

BD SUBMISSION	--	JUNE 2010
REVISIONS TO DRAWING	No.	DATE BY

IMPORTANT: DO NOT SCALE THIS DRAWING
 ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT: **PROPOSED REDEVELOPMENT OF ST. FRANCIS CANOSSIAN COLLEGE**

CLIENT: **The Mother Superiors of the Daughters of Charity of the Canossian Institute (Hong Kong)**

TITLE: **PROPOSED SITE FORMATION WORKS SECTION B1 - B1 FOR PHASE 1**

PROJECT NO.	DRG. NO.	DATE	REV.	
CS1278	1278-SF212	MAY 2010	--	
SCALE	DESIGNED	DRAWN	CHECKED	APPROVED
1:200	YKT	CL	BC	PY

THE CONDITION OF THE COPYRIGHT IN THIS DRAWING IS REMAINED AS ISSUED BY MEINHARDT (C&S) LTD. UNLESS WRITTEN CONSENT MUST BE OBTAINED BEFORE ANY USE OR REPRODUCTION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE.

ARCHITECT

Aedas

Aedas Ltd.
 31/F One Island East
 18 Westlands Road
 Quarry Bay
 Hong Kong
 T +852 2861 1758
 F +852 2820 6419
 E hongkong@aedas.com
 aedas.com

MEINHARDT

Meinhardt (C&S) Ltd.
 4/F West Wing Centre
 421 Queen's Road West
 Hong Kong
 Consulting Engineers
 Telephone: 2859 2028
 Facsimile: 2311 8157

REVISIONS

2010 JUN - 8 P. 5 OF 8

LEGEND

- PROPOSED MASS CONCRETE FILL
- EXISTING SCREEN WALL OR RETAINING WALL
- PROPOSED WELL COMPACTED BACKFILL
- D.W.T. (+53.5)
- DESIGN GROUND WATER LEVEL
- EXISTING UTILITIES

WONG Wai Nam Steve
 CEng, MInstE, MHKIE, RPE
 Registered Structural Engineer - RSE 6002
 Registered Structural Engineer - RSE 6002

SIU Koon Hoi, Carmine (邵冠賢)
 Authorized Person - AP(CE)-0042
 Registered Structural Engineer - RSE 0962
 Registered Geotechnical Engineer - RGE 9832

BD SUBMISSION	-	JUNE 2010
REVISIONS TO DRAWING	No.	DATE BY

IMPORTANT: DO NOT SCALE THIS DRAWING
 ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT: PROPOSED REDEVELOPMENT OF ST. FRANCIS CASSIANUS COLLEGE

CLIENT: The Mother Superior of the Daughters of Charity of the Cassianus Institute (Hong Kong)


TITLE: PROPOSED SITE FORMATION WORKS SECTION C1 - C1 FOR PHASE 1

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-SF213	MAY 2010	-
SCALE	DESIGNED	DRAWN	CHECKED
1:200	YKT	CL	BC
			APPROVED
			PY

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY MEINHARDT (H.K.) LTD. WHOSE CONSENT MUST BE OBTAINED BEFORE ANY USE OR REPRODUCTION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE.

ARCHITECT: **Aedas**
 Aedas Ltd.
 31/F One Island East
 18 Westlands Road
 Quarry Bay
 Hong Kong
 T +852 2851 1728
 F +852 2528 0419
 E HongKong@aedas.com
 aedas.com


MEINHARDT
 C&S Ltd.
 4/F Mei King Centre
 421 Queen's Road West
 Hong Kong
 Consulting Engineers
 Telephone: 2522 0728
 2524 2975
 Facsimile: 2511 8177



SECTION C1-C1
 STAGE 0 (BEFORE DEMOLITION)
 1. INSTALLATION OF MONITORING CHECK POINT (LOCATION OF STAGE 2-3)
 2. CONSTRUCTION OF MASS CONCRETE FILL C1
 3. CARRY OUT SITE FORMATION WORKS (TYPE 1) LOCATION UNTIL 2.5m FROM 115W-B/C636
 4. CARRY OUT FOUNDATION AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)

SECTION C1-C1
 STAGE 1 (AFTER DEMOLITION)
 1. INSTALLATION OF MONITORING CHECK POINT (LOCATION OF STAGE 2-3)
 2. CONSTRUCTION OF MASS CONCRETE FILL C1
 3. CARRY OUT SITE FORMATION WORKS (TYPE 1) LOCATION UNTIL 2.5m FROM 115W-B/C636
 4. CARRY OUT FOUNDATION AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)



SECTION C1-C1
 STAGE 2 (SITE FORMATION)
 1. INSTALLATION OF MONITORING CHECK POINT (LOCATION OF STAGE 2-3)
 2. CARRY OUT SITE FORMATION WORKS AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)
 3. CARRY OUT FOUNDATION AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)




SECTION C1-C1
 STAGE 1 (AFTER DEMOLITION)
 1. COMPLETION OF DEMOLITION WORKS

SECTION C1-C1
 STAGE 2 (SITE FORMATION)
 1. INSTALLATION OF MONITORING CHECK POINT (LOCATION OF STAGE 2-3)
 2. CARRY OUT SITE FORMATION WORKS AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)
 3. CARRY OUT FOUNDATION AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)

SECTION C1-C1
 STAGE 3 (FINAL SITE FORMATION - AFTER SUPERSTRUCTURE CONSTRUCTION)
 1. COMPLETION OF FOUNDATION WORKS AND SUPERSTRUCTURE WORKS (SEE SEPARATE SUBMISSION)
 2. CARRY OUT FINAL FORMATION WORKS (STAGE 3) - REINFORCE MASS CONCRETE FILL C1 WITH 115W-B/C636 & 115W-B/R988
 PERFORM 115W-B/C636 & 115W-B/R988



RECEIVED
 THE JUN - 6 P. 5:08



AS-BUILT SITE FORMATION WORKS - FINAL FORMATION AFTER SUPERSTRUCTURE WORKS
LAYOUT PLAN FOR PHASE 1
(STAGE 3 - FINAL)

LEGEND :

- PROPOSED SOCKET
H-PILE & PILE CAP
(UNDER SEPARATE
SUBMISSION)
- AS-BUILT
HYDROSEEDING
- DEVELOPED ELEVATION
- SECTION MARK

B.D. REF No. BD /30.36/09

- LEGEND**
- AS-BUILT 35° OPEN CUT SLOPE WITH 50mm THK. SHOTCRETE
 - AS-BUILT 30° MAX WELL COMPACTED BACKFILL WITH 50mm THK. SHOTCRETE
 - AS-BUILT RECOMPACTION AND PENSTATE TO MAX. 30° SLOPE WITH 50mm THK. SHOTCRETE
 - EXCAVATION LEVEL
 - EXISTING CATCH PIT
 - SITE BOUNDARY
 - EXISTING SOIL NAIL
 - MASS CONCRETE FILL CONSTRUCTED BEFORE DEMOLITION
 - AS-BUILT WELL COMPACTED BACKFILL
 - 45° MAX MASS CONCRETE FILL CONSTRUCTED BEFORE DEMOLITION
 - EXISTING SCREEN WALL TO BE RETAINED
 - EXISTING RETAINING WALL INSIDE EXISTING BUILDING TO BE RETAINED
 - AS-BUILT RECOMPACTION OF EXISTING FILL
 - AS-BUILT HYDRO SEEDING
 - AS-BUILT CATCH PIT
 - AS-BUILT U-CHANNEL
 - 225UC
 - 2255C
 - AS-BUILT STEPPED-CHANNEL
 - EXISTING FRESH WATER MAIN
 - EXISTING GAS MAIN
 - EXISTING DRAINAGE
 - EXISTING LIGHTING CABLE
 - EXISTING HGC DUCT
 - EXISTING FIBRE OPTIC/PILOT CABLE (H/E)
 - EXISTING HKE CABLE
 - PROPOSED BUILDING OUTLINE
 - EXISTING FEATURE
 - EXISTING RETAINING WALL

REVISIONS TO DRAWING	No.	DATE	BY

IMPORTANT: DO NOT SCALE THIS DRAWING
ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT **PROPOSED REDEVELOPMENT OF ST. FRANCIS CASSIAN COLLEGE**

CLIENT **The Mother Superior of the Daughters of Charity of the Cassian Institute (Hong Kong)**

TITLE **AS-BUILT SITE FORMATION WORKS LAYOUT PLAN FOR PHASE 1 (STAGE 3)**

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-SF114		

SCALE	DESIGNED	DRAWN	CHECKED	APPROVED
1:150				

THE COPYRIGHT OF THIS DRAWING IS RESERVED BY MEINHARDT (H.K.) LTD. WHOSE CONSENT MUST BE OBTAINED BEFORE ANY USE OR REPRODUCTION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE.

ARCHITECT

Aedas

Aedas Ltd.
31/F One Island East
18 Westlands Road
Quarry Bay
Hong Kong

T +852 2861 1728
F +852 2529 6419
E hongkong@aedas.com
aedas.com


MEINHARDT

Meinhardt (C&S) Ltd. Consulting Engineers
4/F One World Centre
421 Queen's Road West
Hong Kong

Telephone: 2822 0228
2822 2818
2822 8107

Main Contractor

Chinney Construction Co., Ltd.
BLOCK A&B 9/F, HONG KONG SPINNERS INDUSTRIAL BUILDING,
PHASE IV 41-43 SUEDE ROAD, KOWLOON, HONG KONG.



BD. REF. No. BD 3/3036/09

LEGEND

- SITE BOUNDARY
- EXISTING FEATURE
- EXISTING RETAINING
- [Symbol] AS-BUILT MASS CONCRETE FILL
- BH1 EXISTING BOREHOLE
- TP1 EXISTING TRIAL PIT
- CP1-H1 303x305x180 kg/m PREBORED SOCKET H-PILE
- PD1-1 AS-BUILT PREDRILLING
- +51.35 PILE CAP TOP LEVEL
- [Symbol] SECTION MARK
- [Symbol] EXISTING FOOTING (FOUNDING ON +57.4mPD)
- OOOOO AS-BUILT PIPE PILE WALL (UNDER SITE FORMATION SUBMISSION)

REVISIONS TO DRAWING No. DATE BY

IMPORTANT: DO NOT SCALE THIS DRAWING. ALL DIMENSIONS SHOULD BE CHECKED ON SITE.

PROJECT: PROPOSED DEVELOPMENT OF ST. FRANCIS CANOSSIAN COLLEGE

CLIENT: The Mother Superiores of the Daughters of Charity of the Canossian Institute (Hong Kong)

TITLE: AS-BUILT FOUNDATION WORKS PILING LAYOUT PLAN FOR PHASE 1

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-FP111 (AB)		
SCALE	DESIGNED	DRAWN	CHECKED
1:100			

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY MEINHARDT (C&S) LTD. REPRODUCED WITHOUT THE WRITTEN CONSENT OF MEINHARDT (C&S) LTD. OR PERMISSION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE.

ARCHITECT

Aedas

Aedas Ltd.
31/F One Island East
18 Westlands Road
Quarry Bay
Hong Kong

T +852 2881 1728
F +852 2529 8419
E hongkong@aedas.com
aedas.com






MEINHARDT






Meinhardt (C&S) Ltd. Consulting Engineers
4/F Wai Ming Centre
402 Queen's Road West
Hong Kong

Telephone: 2854 0738
Facsimile: 2517 6107

建築地盤有限公司
CHINNEY CONSTRUCTION CO., LTD.
8/F, 80-82 WING LEE BUILDING, 100 QUEEN'S ROAD WEST, HONG KONG
TEL: 2871 8100 FAX: 2871 1022

LEGEND

-  AS-BUILT MASS CONCRETE FILL
-  EXISTING SCREEN WALL OR RETAINING WALL
-  AS-BUILT WELL COMPACTED BACKFILL
-  D.W.T. (+53.5) DESIGN GROUND WATER LEVEL
-  EXISTING UTILITIES



REVISIONS TO DRAWING	No.	DATE	BY

IMPORTANT: DO NOT SCALE THIS DRAWING
ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT **PROPOSED REDEVELOPMENT OF ST. FRANCIS CANTONIAN COLLEGE**

CLIENT
The Mother Superior of the Daughters of Charity of the Cantonian Institute (Hong Kong)

TITLE
AS-BUILT SITE FORMATION WORKS SECTIONS FOR PHASE 1 (SHEET 2 OF 3)

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-SF212 (AB)		


SCALE	DESIGNED	DRAWN	CHECKED	APPROVED
AS SHOWN				

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY MEINHARDT (C&S) LTD. NO PART OF THIS DRAWING OR REPRODUCTION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE


ARCHITECT
Aedas
Aedas Ltd.
31/F One Island East
18 Westlands Road
Quarry Bay
Hong Kong
T +852 2851 1728
F +852 2528 8410
E hongkong@aedas.com
aedas.com

MEINHARDT
Meinhardt (C&S) Ltd. Consulting Engineers
4/F Wan Ming Centre
421 Queen's Road West
Hong Kong
Telephone: 2558 0738
2558 7918
Facsimile: 2517 8107


Main Contractor
Chinney Construction Co., Ltd.
BLOCK A&B 8/F, HONG KONG SPINNERS INDUSTRIAL BUILDING,
PHASE V 481-483 CASTLE PEAK ROAD, KOWLOON, HONG KONG




SECTION G1-G1
(1:200)



SECTION H1-H1
(1:200)








SECTION I1-I1
(1:200)



SECTION J1-J1
(1:200)

B.D. REF. No. BD /3036/09

LEGEND

-  AS-BUILT MASS CONCRETE FILL
-  EXISTING SCREEN WALL OR RETAINING WALL
-  AS-BUILT WELL COMPACTED BACKFILL
-  D.W.T. (+53.5) DESIGN GROUND WATER LEVEL
-  EXISTING UTILITIES

REVISIONS TO DRAWING	No.	DATE	BY

IMPORTANT: DO NOT SCALE THIS DRAWING
ALL DIMENSIONS SHOULD BE CHECKED ON SITE

PROJECT PROPOSED REDEVELOPMENT OF
ST. FRANCIS CANOSSIAN COLLEGE

CLIENT
The Mother Superiores of the Daughters of
Charity of the Canossian Institute (Hong Kong)

TITLE
AS-BUILT SITE FORMATION WORKS
SECTIONS FOR PHASE 1
(SHEET 3 OF 3)

PROJECT NO.	DRG. NO.	DATE	REV.
CS1278	1278-SF213 (AB)		
SCALE	DESIGNED	DRAWN	CHECKED
AS SHOWN			

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY
MEINHARDT (HONG KONG) LTD. ANY REPRODUCTION OR USE OF THIS DRAWING
WITHOUT THE WRITTEN PERMISSION OF MEINHARDT (HONG KONG) LTD. IS
STRICTLY PROHIBITED.

ARCHITECT

Aedas

Aedas Ltd.
31/F One Island East
18 Westlands Road
Country, Bay
Hong Kong

T +852 2861 1728
F +852 2529 8419
E hongkong@aedas.com
aedas.com

MEINHARDT

Meinhardt (C&S) Ltd. Consulting Engineers
4/F Sun Ming Centre
401 Queen's Road West
Hong Kong

Telephone: 2858 2788
2858 2918
2817 4107

Main Contractor

Chinney Construction Co., Ltd.
Block A&B 9/F, Hong Kong Spinners Industrial Building,
Phase II 401-403 Castle Peak Road, Kowloon, Hong Kong

A. GENERAL NOTES

- 1. SCALE OF DRAWINGS IS AS SHOWN.
2. ALL LEVELS ARE IN METRES ABOVE PRINCIPAL DATUM (MAD).
3. ALL DIMENSIONS SHOWN ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
4. NAM KOO TERRACE IS A LEVEL 1 HISTORICAL BUILDING AND THE CONTRACTOR SHALL EXERCISE EXTRA CARE IN CARRYING OUT THE WORKS.

- 5. THE CONTRACTOR SHALL CARRY OUT A DETAILED CONDITION / DEFECT SURVEY BY A QUALIFIED REGISTERED SURVEYOR WITH PHOTOGRAPHIC EVIDENCE OF NAM KOO TERRACE PRIOR TO THE REMEDIAL WORKS. A SURVEY SHALL ALSO BE CARRIED OUT AFTER COMPLETION OF THE REMEDIAL WORKS TO CONFIRM THAT THE CONTRACTOR'S WORKS HAVE NOT RESULTED IN ANY DAMAGE.
6. THE CONTRACTOR SHALL PROVIDE ANY ADDITIONAL MEASURES WHICH MAY BE NECESSARY TO ENSURE THAT THE REMEDIAL WORKS WILL NOT AFFECT THE BUILDING. THESE SHOULD BE APPROVED BY THE ENGINEER PRIOR TO IMPLEMENTATION BY THE CONTRACTOR.

C. CONCRETE AND STRUCTURAL STEEL

- 1. ALL STRUCTURAL STEEL - SECTION TO BE GRADE 434 (D54500) UNLESS OTHERWISE SPECIFIED.
2. ALL TEMPORARY WATERS ARE TO BE GRADE 434 (D54500) UNLESS OTHERWISE SPECIFIED.
3. ALL WELDING ARE TO BE PERFORMED BY A QUALIFIED WELDER TO THE SATISFACTION OF THE ENGINEER.

C. HEAVY RAINFALL PRECAUTIONS

- 1. SURFACE WATER FLOWING INTO THE SITE FROM UPHILL SHALL BE INTERCEPTED AND CONDUCTED FROM THE SITE TO AN INDICATED SAFE DISCHARGE POINT. TEMPORARY CHANNELS SHALL BE PLASTERED AND PROTECTED FROM DAMAGE.
2. WHERE PARTIALLY COMPLETED DRAINAGE WORKS DISCHARGE WITHIN THE SITE A TEMPORARY CONDUIT SHALL BE PROVIDED TO THE DISCHARGE POINT.

D. FILL MATERIAL

- 1. FILL MATERIAL SHALL NOT CONTAIN ANY OF THE FOLLOWING:
1.1.1 MATERIAL SUSCEPTIBLE TO VOLUME CHANGE, INCLUDING MARINE MUD, SOIL WITH A LIQUID LIMIT EXCEEDING 60% OR A PLASTICITY INDEX OF MORE THAN 30%, SHELLS, CLAYS AND COLLAPSIBLE SOILS.
1.1.2 PEAT, VEGETATION, TIMBER, ORGANIC, SOLUBLE OR PUSHERABLE MATERIAL.

- 4.2. EARTHWORKS FINAL SURFACES SHALL BE COMPLETED TO SMOOTH ALIGNMENTS WITHOUT ABRUPT BENTONLINES.
4.3. EARTHWORKS FINAL SURFACES AND FORMATIONS SHALL BE MAINTAINED IN A STABLE CONDITION AND SHALL BE PROTECTED PRIOR TO WATER OR OTHER CAUSES AND FROM EXPOSURE TO CONDITIONS WHICH MAY ADVERSELY AFFECT THE SURFACE.
4.4. SOLE PROTECTION SYSTEM - GRASSSEED OR HYDROSEEDING IS TO BE PROVIDED ON THE CUT AND FILL SLOPES.

E. NOTES ON SOIL NAILS

- 1. THE MINIMUM DIAMETER OF THE DRILLHOLES FOR SOIL NAIL INSTALLATION SHALL BE 120mm UNLESS OTHERWISE STATED. AIR OR FOAM FLUSH MEDIUM MUST BE USED DURING DRILLING. WATER SHALL NOT BE USED FOR FLUSHING.
2. THE SOIL NAILS SHALL BE INSTALLED WITHIN 24 HOURS OF COMPLETION OF THE DRILLING UNLESS OTHERWISE STATED BY THE ENGINEER'S REPRESENTATIVE. DRILLHOLES SHALL BE CLEARED OF ALL DEBRIS IMMEDIATELY BEFORE TENDRING.

F. NOTES ON PULL OUT TEST FOR SOIL NAILS

- 1. PULL OUT TEST ON ALL THE TEST NAILS SHALL BE CARRIED OUT AT LOCATIONS AS SPECIFIED IN THE DRAWINGS OR AS DIRECTED BY THE ENGINEER AND SHALL BE CARRIED OUT BY THE CONTRACTOR PRIOR TO INSTALLATION OF THE WORKING NAILS.
2. THE SOIL NAIL PULL OUT TEST SHALL BE CARRIED OUT ON THE SCHEDULED BOND LENGTH IN ACCORDANCE WITH THE SCHEDULE OF TEST NAILS SHOWN ON THIS DRAWING.

- 3. WORKS SHALL CEASE AND THE ENGINEER AND BUILDINGS DEPARTMENT NOTIFIED IF ANY UNDEGROUND MOVEMENT OR GROUNDWATER DRAWING IS RECORDED. MEASURES TO BE AGREED AND COMPLETED PRIOR TO RE-COMMENCEMENT OF WORKS.
4. DRAINAGE AND MONITORING STATIONS ARE TO BE RENAISSANCE TO WATER AND FROM EXPOSURE TO CONDITIONS WHICH MAY ADVERSELY AFFECT THE SURFACE.

I. GENERAL WORK SEQUENCE FOR REMEDIAL WORKS

- 1. CONDUIT SURVEY TO BE CONDUCTED.
2. ESTABLISH ALL MONITORING STATIONS.
3. REMOVE SURFACE AND ANY FEATURES SUCH AS THE CONCRETE PERGOLA, FOUNTAIN AND CONCRETE GARDEN ETC. WITHOUT DAMAGING THEM.

J. WORK SEQUENCE FOR TEMPORARY EXCAVATION

- 1. WALL B OF 115W-B/R629
1.1. EXCAVATE TRENCH TO EXPOSE THE TIER OF THE RETAINING WALL ALONG ST. LUKE'S COLLEGE.
1.2. DETERMINE THE EXTENT OF SHORING REQUIRED REFER TO SECTION F-F ON DRAWING.
1.3. THE SETTING OUT OF THIS IS TO BE AGREED WITH THE ENGINEER PRIOR TO INSTALLATION.

K. NOTES ON PROTECTION OF EXISTING FOUNDATION

- 1. SHOULD ANY OBSTRUCTION BE ENCOUNTERED DURING THE DRILLING FOR SOIL NAIL INSTALLATION, THE CONTRACTOR SHOULD CEASE DRILLING, INVESTIGATE AND REPORT ON THE RETURN OF THE OBSTRUCTION.
2. THE DRILLHOLE IS TO BE BACKFILLED WITH GROUT AND DRILLING RESIDUE WHERE NECESSARY.

L. RECORD PLANS AND MAINTENANCE

- 1. UPDATED RECORD INFORMATION IN COMPLIANCE WITH PAPER 188 IS TO BE SUBMITTED UPON COMPLETION OF THE WORKS.
2. ANY NEWLY CONSTRUCTED SERVICES OR EXISTING BURIED SERVICES ENCOUNTERED DURING THE WORKS ARE TO BE PROPERLY IDENTIFIED BY THE CONTRACTOR AND DETAILS SHALL BE RECORDED IN THE RECORD INFORMATION TO BE SUBMITTED TO THE BUILDING DEPARTMENT.


M. ALERT ALARM AND ACTION LEVEL FOR MONITORING WORKS

- 1. IF THE ALERT OR ACTION LEVEL IS REACHED, THE CONTRACTOR SHALL INFORM THE REGISTERED SURVEYOR IMMEDIATELY. THE MONITORING CHECK POINTS SHALL BE INCREASED AT THE AFFECTED AREA OF THE WORKS.
2. IF THE ACTION LEVEL IS REACHED, THE CONTRACTOR SHALL CEASE THE WORKS. THE WORKS SHALL NOT RECOMMENCE UNTIL REMEDIAL PROPOSALS TO THE SATISFACTION OF THE ENGINEER AND BUILDING AUTHORITY HAS BEEN IMPLEMENTED.




N. NON-DESTRUCTIVE TESTING - TIME DOMAIN REFLECTOMETRY (TDR)

- 1. NON-DESTRUCTIVE TESTING SHALL COMPLY WITH APP-135.
2. FOR ALL COMPLETED SOIL NAILING WORKS, KEY RECORDS ON SUPERVISION OF SOIL NAILING WORKS SHALL BE SUBMITTED TO THE ENGINEER BY THE CATEGORY B QUALIFIED SUPERVISION SHALL BE SUBMITTED TO BO BY AP.
3. THE TDR METHOD FOR CHECKING THE LENGTH OF INSTALLED SOIL NAIL SHALL ADAPT AND COMPLY WITH THE TDR METHOD FOR CHECKING THE LENGTH OF INSTALLED SOIL NAIL.

O. SOIL NAIL TYPICAL CROSS SECTION



P. TYPICAL SECTION FOR SOIL NAIL



R. NOTES ON PREDRILLING

- 1. THE SPECIFICATION TO BE READ IN CONJUNCTION WITH THE FOLLOWING DOCUMENTS:
1.1. GEOTECHNICAL SURVEY TO SITE INVESTIGATION REPORT (GEO. WORKS CONSULTING).
1.2. GEOTECHNICAL SURVEY TO SITE INVESTIGATION REPORT (GEO. WORKS CONSULTING).

S. NOTES ON MONITORING WORKS

- 1. THE MONITORING WORKS SHALL BE CARRIED OUT TO OBTAIN BOND LENGTHS OF NOT LESS THAN 30mm DIAMETER.
2. THE LOCATION OF DRILLING HOLES ARE SHOWN IN DWG. NO. 91051/RW002. THE FINAL LOCATION SHALL BE CONFIRMED BY THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.

T. NOTES ON MONITORING WORKS

- 1. THE MONITORING WORKS SHALL BE CARRIED OUT TO OBTAIN BOND LENGTHS OF NOT LESS THAN 30mm DIAMETER.
2. THE LOCATION OF DRILLING HOLES ARE SHOWN IN DWG. NO. 91051/RW002. THE FINAL LOCATION SHALL BE CONFIRMED BY THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.

U. NOTES ON MONITORING WORKS

- 1. THE MONITORING WORKS SHALL BE CARRIED OUT TO OBTAIN BOND LENGTHS OF NOT LESS THAN 30mm DIAMETER.
2. THE LOCATION OF DRILLING HOLES ARE SHOWN IN DWG. NO. 91051/RW002. THE FINAL LOCATION SHALL BE CONFIRMED BY THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.

84 DH20/84/HK

NOTES: THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS AND HAZARDOUS WASTE CONTROL REGULATIONS (CAP 354) AND ENVIRONMENTAL IMPROVEMENT AND CONTROL ACT (EIA) AND ENVIRONMENTAL IMPROVEMENT AND CONTROL ACT (EIA) AND ENVIRONMENTAL IMPROVEMENT AND CONTROL ACT (EIA).

LEGEND: LOT BOUNDARY, FEATURE BOUNDARY



MAX CHAI CHEUNG, PETER CHAN, REGISTERED ARCHITECT (No. 1611)

LEUNG HOON YU, REGISTERED STRUCTURAL ENGINEER (No. 1611)

Plan Approval: (Signature) Chief Building Surveyor for BUILDING AUTHORITY

11 JAN 2013

Table with columns: Description, Date, By, For. Includes entries for Minor Amendment, Approval, and Update Comment.

Plan Approval: (Signature) Chief Building Surveyor for BUILDING AUTHORITY

11 JAN 2013

Table with columns: Description, Date, By, For. Includes entries for Minor Amendment, Approval, and Update Comment.

Plan Approval: (Signature) Chief Building Surveyor for BUILDING AUTHORITY

11 JAN 2013

Hyder

FEATURES NOS. 115W-B/CR349 (WALL PORTION OF SUB-DIVISION NO.1) AND 115W-B/R629 55 SHIP STREET, WANCHAI

RETAINING WALL REMEDIAL WORKS GENERAL NOTES & BLOCK PLAN

Project: 991051/RW001

NOTE:
 1. THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING 991051/RW001 & RW002.
 2. THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS URUSIDE ORDER NO. DH0035/86/11C FOR FEATURE NOS. 115W-B/CR349 (WALL PORTION OF SUB-DIVISION NO. 1) AND 115W-B/8629.

LEGEND:
 --- LOT BOUNDARY



LEUNG Kwok-Yiu
 BRITISH COLONY REGISTERED PROFESSIONAL ENGINEER
 Registered Electrical Engineer

Fan Sui Kay
 Registered Structural Engineer
 (Reg. No. R105047)

Plan Approval
 (CHONG Wing-hong)
 Chief Building Surveyor
 for BUILDING AUTHORITY
 11 MAR 2003

Rev. No.	Description	Date	By	CHK	APP
E	MINOR AMENDMENT	19.12.12	A	B	PL
D	MINOR AMENDMENT	10.03.11	KL	ML	RL
C	AD BE APPROVED UPDATE BE COMMENT	20.06.03	FL	LM	JC
B	IF'S DRAINAGE DETAILS ADDED DETAILS 'C' & DETAILS 'D'	26.02.03	LM	ESH	JT
A	AD BE APPROVED UPDATE BE COMMENT	19.11.01	EX	LM	JT




PROJECT
 FEATURES NOS. 115W-B/CR349
 (WALL PORTION OF SUB-DIVISION NO. 1)
 AND 115W-B/R629
 55 SHIP STREET, WANCHAI


RETAINING WALL REMEDIAL WORKS
 ELEVATION AND DETAILS

Drawn By	Checked	Scale	Date	Proj No.	Rev No.
AK	AK	1:6.07.01	16.07.01	991051	1051RW3
DL	DL	1:6.07.01	16.07.01	AS SHOWN	












Drawing No.: 991051/RW003 Rev: E



ELEVATION OF WALL A OF 115W-B/R629










ELEVATION OF WALL B OF 115W-B/R629



REINFORCEMENT	NORMAL SIZE (mm)	T	B
< 300	100	100	NIL
375-675	150	150	NIL
750-900	175	175	125

CEMENT SAND MORTAR TO FILL GAP
 75#
 PROPOSED MASS CONCRETE WALL
 PROPOSED WEPHOLES CONSTRUCTED OF SINGLE CONTINUOUS PVC PIPES EXTENDED FROM ALL EXISTING WEPHOLES TO THE OUTER FACE OF THE STONE PITCH FACING

NOTES:
 1. TIES SHALL BE 3 THK. 40 WIDE HOT-DIP GALVANIZED MILD STEEL PLAST.
 2. TIES SHALL BE CAST INTO THE CONCRETE WALL DURING CONCRETING
 3. TIES SHALL BE LAID AT A RATE OF 5 NOS. PER M²



Scale Reference No. BD DH20/84/HK

NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH DRAWINGS 991051/RW001 & RW003
- THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS WASTE ORDER NO. 409/95/AM/11C FOR FEATURE NOS. 11SW-B/R628 & 11SW-B/R629 (WALL PORTION OF SUB-DIVISION NO.1) AND 11SW-B/R629

LEGEND

- PROPOSED SOLE NAEL
- PROPOSED DOWN BAR
- PROPOSED WATER & STRUT
- PROPOSED WEEPHOLE
- PROPOSED TRAIL PIT (TOTAL 1 NOS)
- PROPOSED TRAIL PIT (TOTAL 1 NOS)
- EXISTING GROUND SETTLEMENT MARKERS (TOTAL 6 NOS)
- EXISTING BUILDING SETTLEMENT MARKERS (TOTAL 4 NOS)
- EXISTING STAND PIPES (TOTAL 2 NOS)
- EXISTING BOREHOLES WITH STANDPIPES (TOTAL 4 NOS)
- EXISTING VERTICAL BOREHOLES (TOTAL 3 NOS)
- EXISTING HORIZONTAL COFFERHOLE (TOTAL 19 NOS)
- EXISTING INCLINED COFFERHOLES (TOTAL 6 NOS)
- EXISTING TRAIL PITS (TOTAL 7 NOS)
- EXISTING UTILITIES INSPECTION PIT (TOTAL 5 NOS)
- PROPOSED U-CHANNEL
- PROPOSED CATCHPIST
- PROPOSED DOWNPIPE
- PROPOSED SETTING MARKERS (TOTAL 9 NOS)
- PROPOSED VERMICROGRAPH LOCATIONS (TOTAL 3 NOS)
- PROPOSED PREDRILL BOREHOLE LOCATIONS (TOTAL 2 NOS)
- EXISTING BOREHOLE
- FEATURE BOUNDARY

Plan Approved
(CHONG Wing-hong)
Chief Building Surveyor
for BUILDING AUTHORITY
11 JAN 2013

Yan Sin Kuy
Registered Structural Engineer
(Reg. No. R10507)

LEUNG Kwok-Yiu
Registered Geotechnical Engineer
(Reg. No. GE1006)

WALSH LIMITED
HONG KONG

Rev	Stat	Description	Date	By	Chk	App
E	-	MINOR AMENDMENT	19.12.12	A	BR	RL
D	-	MINOR AMENDMENT	13.06.11	KL	ML	RL
C	-	MINOR AMENDMENT	10.03.11	AL	ML	RL
A	-	AD - BD APPROVED	20.06.03	LM	EST	JC
B	IF	GENERAL REVISION	26.02.03			
A	AD	BD APPROVED UPDATE BD COMMENT	18.11.01	EX	LM	UT

Hyder

Project: FEATURES NOS. 11SW-B/R628 AND 11SW-B/R629, 55 SHIP STREET, WAN CHAI

Drawing Title: RETAINING WALL REMEDIAL WORKS LAYOUT PLAN & SECTIONS

Drawn	Ek	Date	16.07.01	Rev No.	991051
Checked	AL	Date	16.07.01	Drawn By	1051HWZ
Approved	DL	Date	16.07.01	Scale	A45 SHOWN
Drawing No.	991051/RW002		File		

10 JAN 2013



YOUR REF 來函檔號：
OUR REF 本(23)號 BD DH20/84/HK(III)
FAX 圖文傳真： 2136 8200
TEL 電話： 2135 2453
www.info.gov.hk/bd

Mr. MAK Chi Cheung, Peter
c/o WMKY Limited
Room 3308, 33/F,
Hopewell Centre,
183 Queen's Road East,
Wanchai, Hong Kong

11 March 2013

39

15 MAR 2013

374

DATE	ANS TO	ANS BY	FILE
PM AM	SL JF	HL SW	FT
INF			
ACTION			

Dear Sir,

DHO No. DH0035/HK/11/C dated 30 March 2011
Feature Nos. 11SW-B/CR349 (Wall Portion of Sub-division No. 1) & 11SW-B/R629
Proposed Wall Remedial Works at
No.55 Ship Street, Hong Kong – I.L. 2140

I refer to your application dated 10 January 2013 and received on **11 January 2013** for approval of proposals in respect of **Wall Remedial Works (Major Revision)**.

- Your submission of plans has been checked under the curtailed check system announced in Practice Notes for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers ADM-19. On this basis, I am satisfied that your submission is fundamentally acceptable and may be approved.
- You are reminded that the curtailed check system covers only the fundamental issues of a building proposal. Although non-fundamental issues will not be raised as reasons for disapproving a submission, I expect that all contravention of the Buildings Ordinance and its subsidiary legislation are rectified as and when they are discovered and in any event, before completion of the works is certified. In this connection, I ask you to note that the Building Authority attaches great importance to the proper assumption of duties and responsibilities by authorized persons, registered structural engineers and registered geotechnical engineers.
- In accordance with the provisions of regulation 30(1) of the Building (Administration) Regulations, this is to notify that the above - mentioned plans submitted with your application received on 11 January 2013 are hereby approved. One set of the said plans, on which I have signified my approval, is enclosed. Your client has been sent a copy of this letter but I would request that you ensure that the contents are understood by him.
- This approval should not be deemed to confer any title to land or to act as a waiver of any term in any lease or licence. This approval does **NOT** authorize the commencement or the carrying out of any works shown in the approved plans. Section 14(2) of the Buildings Ordinance refers.

/...2

6. As conditions of this approval under Section 17(1) of the Buildings Ordinance, the following are required:-

- (a) Qualified site supervision requirement, sampling and testing of soil nail works as stipulated in Appendix A.
- (b) Qualified site supervision requirement, sampling and testing of reinforced concrete works as stipulated in Appendix B.
- (c) Qualified site supervision requirement of retaining wall works as stipulated in Appendix C.

To ensure full compliance of the Buildings Ordinance, it is prudent for the authorized person who acts as the co-ordinator of the building works, to inform the registered contractor all the imposed conditions attached to this approval.

7. The checking of submission has been substantially curtailed and greater emphasis is placed on the integrity and competence of the authorized persons. You are expected to comply with the requirement of Buildings Ordinance section 4(3)(b) in respect of any contravention of the regulations.

8. Chief Geotechnical Engineer/Island of the Geotechnical Engineering Office, Civil and Engineering Development Department (Contact Person: Mr. Roy K. C. HUNG on Tel. No. 2762 5282) has the following comments:

- (a) Prior to consent application for commencement of the works, a report on condition survey of the adjacent existing building/structure, including the Graded historic building Nam Koo Terrace, shall be submitted and acknowledged by the Buildings Department.
- (b) In addition to the TCP T3 and T5 site supervision personnel under the RGE's stream, a Directorate Site Supervisor (DSS) shall be provided for the proposed retaining wall remedial works. He/she shall carry out inspections at the critical stages of the works at least monthly, or more frequently as necessary. The name of the DSS shall also be given in the site supervision plan.
- (c) The AP/RSE/RGE are advised that the extent of supervision to be provided for different stages of the soil nailing works is given in the Code of Practice for Site Supervision 2009.
- (d) The AP/RSE/RGE are advised that the TCP T3 shall carry out site inspection of the works and prepare and certify the key records on supervision of soil nailing works in accordance with the Code of Practice for Site Supervision 2009.
- (e) The AP/RSE/RGE are advised that the following shall be submitted and accepted by the BA prior to submission for the Form BA14 for the slope/retaining wall remedial works:

/...3

- (i) Pull-out test report, records of installation and non-destructive test report (if any) for the soil nails;
- (ii) Results of the confirmatory ground investigation fieldworks for pre-drilled holes PD1 and PD2 as shown in Drawing No. 991051/RW002(Rev.E) and an assessment report of the ground condition interpreted from the ground investigation fieldworks results in comparison with the relevant design assumptions.

- (f) It is noted that construction of the proposed retaining wall remedial works for Feature No. 11SW0B/R629 will inevitably require working space outside the lot boundary of the subject private lot. The AP is reminded to seek permission from the relevant parties for temporary occupation of the required working space for execution of the proposed works.

9. Chief Highway Engineer/Hong Kong, Highways Department (Contact Person: Mr. C M CHONG on Tel. No. 2231 5722) has the following comments:

- (a) You are required to advise whether any existing slope / features / retaining wall maintained by this Office would be affected by the proposed works.
- (b) You are required to advise whether the proposed works, including any slope reinforcing works and proposed drainage, would be constructed at Government land and would be handed over to this Office for maintenance.
- (c) You are required to seek DSD's comments for any proposed connection of drains / channels to public drainage system.

It is noted that you have made reply on the above comments via email dated 7 March 2013 and HyD has no further comment on your proposal.

10. The Antiquities and Monuments Office (AMO) of the Leisure and Cultural Services Department (Contact Person: Ms. Rammy LAI on Tel. no. 2721 2673) has the following comments:-

- (a) The subject works site is located very close to the Grade 1 historic building Nam Koo Terrace. The AP/RSE/RGE shall ascertain the potential impacts on this graded building and recommend appropriate precautionary measures so as to ensure that the structural integrity and fabrics of the graded building will not be damaged by the proposed slope works.
- (b) It is noted that no movement or tilting monitoring point locations are proposed at the captioned historic building. Therefore, the AP/RSE/RGE should propose locations for vibration, settlement and tilting check points for the Grade 1 historic building and the following monitoring table for AAA levels shall be followed as attached:

/...4

	Alert level	Alarm level	Action level
Vibration check point	3mm/s	4mm/s	5mm/s
Settlement check point	6mm	8mm	10mm
Tilting check point	1/2000	1/1500	1/1000

- (c) It is recommended that for all building settlement and tilting markers shown on Drawing No. 991051/RW003 are replaced by glued fixing with a disc and with measurement by means of an electronic tilt meter to avoid drill damage to the captioned graded building.
- (d) No adverse impact to be posed on the masonry walls should be taken into account of the works design. It is recommended that the soil nail heads shown on Drawing no. 991051/RW003 for upgrading works of other retaining walls be recessed further into the masonry wall and be made good with stone blocks in front of the soil nail head.
- (e) It is suggested that the existing stone faced retaining wall shall not be covered by mass concrete at Section AA and BB in order to preserve the historic setting. Consideration shall be given to add mass concrete behind the existing retaining wall for the upgrading work should the adjoining site also own by the same owner.
- (f) It is stated in item 8 of the General Notes that features at the forecourt, such as pavilion, fountain, planters and garden feature, etc. will be temporarily removed and shall be reinstated after completion of work. Destructive removal method to the historic features at forecourt is not recommended, AP/RSE/RGE are required to consider less destructive method, if any. The AP/RSE/RGE should adopt appropriate protective measures to the said features in the course of removal and reinstatement works. Backfilling works in the course of reinstatement shall match with the existing floor finish.
- (g) The AP/RSE/RGE is required to clarify if there will be any demolition / alteration to the existing featured boundary wall above the masonry walls requiring remedy. Appropriate protective measures to the existing features on the boundary wall such as arch doorway, column heads, etc. should be necessary.
- (h) To conclude, the AP/RSE/RGE are reminded that no disturbance should be made to the building and features in the site in the course of works, and mitigation measures should be carried out, if necessary, in consultation with this Office. Please note that any protective/ precaution measure should avoid direct fixing to the buildings and features, if required please consider using reversible fixing method as far as possible to minimize the disturbance to the fabric.

11. Commissioner for Transport, Traffic Engineering (HK) Division, Transport Department (Contact Person: Ms. TAM Kwai-fan, Irene on Tel. No. 2294 2600) has the following comments:-

- (a) If public road will be occupied by the proposed works, temporary traffic management scheme shall be submitted in advance.

12. Comments, if any, from the District Lands Officer/Hong Kong West & South of Lands Department, will be conveyed to you once available.

13. Please be reminded of the following:


- (a) To provide adequate precautionary measures prior to and during the carrying out of the retaining wall remedial works for the safety of the public, the workers and the adjoining properties. An Application for a hoarding permit is required if a hoarding is to be erected under Buildings (Planning) Regulation 64. In this connection, your attention is drawn to PNAP APP-23;
- (b) To lodge a supervision plan (2 copies) for the works prior to your consent application. Your attention is drawn to Section 16(3)(bc) of the Buildings Ordinance;
- (c) To promptly report all significant signs of distress and/or notable landslides during the construction works to the Buildings Department and the Geotechnical Engineering Office.
- (d) To give prior notice to the GEO of the date of commencement of site trials for soil nailing works and non-destructive tests for installed soil nails shown on the plans in order to facilitate GEO staff to carry out site inspection and field checks.

14. You are required, under Building (Administration) Regulation 10, to submit the following:

- (a) Initial readings of all monitoring stations for record prior to the commencement of the retaining wall remedial works;
- (b) Together with Form BA14 to certify completion of the works, you are required to submit the following:
 - (i) Two sets of record plans.
 - (ii) The Information including a soft copy of the basic data requested in PNAP ADV-8 for registration of slopes and retaining walls for which the owners have maintenance responsibility;
 - (iii) Two copies of the Maintenance Manual, as requested in PNAP APP-79;

15. It is noted that you made amendments on the plans on 28 February 2013, 8 & 11 March 2012.
16. Please provide a copy of the approved plans to GEO direct.
17. It appears that trees in or around your site may be affected by your slope stabilization works proposal. You are advised to liaise with the District Lands Office in this regard prior to commencement of works.
18. Please be reminded that due consideration should be given to incorporate landscape measures to improve the visual appearance of the feature. Landscape treatment should be provided, wherever possible, to all newly formed or newly upgraded slopes and the use of shotcrete or chunam on slopes should only be considered as a last resort. (PNAP ADV-23 refers) Please also refer to the "Layman's Guide to Landscape Treatment of Slopes" produced by the Geotechnical Engineering Office, which can be viewed/downloaded from the Civil Engineering and Development Department Website (<http://www.cedd.gov.hk/eng/publications/geo/index.htm>) through the Internet.

Yours faithfully,


(CHONG Wing-hong)
Chief Building Surveyor/Slope Safety
for Building Authority

c.c. **YUBA Company Limited**
(fax: 2865 6276)

RSE - Mr. Fan Siu Kay
(fax no. 2529 1834)

RGE - Mr. Leung Kwok Yiu
(fax no. 2805 5028)

CGE/I, GEO, CEDD
DLO/HK W&S
CHE/HK, HyD
AC for T, TD
AMO, LCSD

Ref : BD DH20/84/HK(III)

Address : No.55 Ship Street, Hong Kong - I.L. 2140

Appendix A to approval dated 11.03.2013

Soil Nail/~~Rock-Dowel~~ Works

In giving this approval of plans, I hereby impose the following conditions under item 6 in section 17(1) of the Buildings Ordinance.

- (a) Sampling and testing of steel reinforcing bars used in the soil nail/~~rock-dowel~~ works should be carried out in accordance with Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) APP-45 (previously known as PNAP 122). Testing should be carried out by a laboratory[#] accredited under the Hong Kong Laboratory Accreditation Scheme (HOKLAS) for the particular test concerned. Test results should be reported on a HOKLAS Endorsed Certificate and submitted within 60 days of the delivery of the steel reinforcing bars to the site. The test reports should be appended with a statement signed by the Authorized Person/Registered Structural Engineer to confirm the following:
- (i) All steel reinforcing bars used in the soil nail/~~rock-dowel~~ works and the test specimens covered by the test reports are in accordance with the types and grades of steel shown in the approved plans.
 - (ii) Sampling and testing of steel reinforcing bars used have been carried out in accordance with the current PNAP APP-45 (previously known as PNAP 122).
 - (iii) The acceptance criteria appropriate to each type and grade of steel reinforcing bars used have been complied with.
 - (iv) Testing of steel reinforcing bars has been carried out by a laboratory[#] accredited under HOKLAS.
- (b) The requirements of sampling and testing of grout are as follows:
- (i) For each grout mix one sample of grout shall be provided from each 10 batches of grout, or every 10 m³ from the amount of grout produced in a day, whichever is the lesser, to determine the crushing strength of the grout. Samples shall be provided not more than 1 hour after the grout has been mixed and shall be protected from weather before test cubes are made.

- (ii) Compression testing of grout test cubes should be carried out in accordance with the methods specified in CS1:1990/ CS1:2010* using 100mm size cubes. Testing should be carried out by a laboratory[#] accredited under HOKLAS for the particular test concerned. Test results should be reported on a HOKLAS Endorsed Certificate and appended with a statement signed by the Authorized Person/Registered Structural Engineer to confirm that the acceptance criteria set out in the Building (Construction) Regulation 59 have been complied with, and should be submitted within 21 days after testing.
 - (c) Qualified site supervision of the sampling of cement grout and making and curing of test cubes by an experienced and competent person should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
2. Your attention is drawn to the following conditions:
- (a) Site supervision of the soil nail works by a team of supervisors shall be provided each by the Authorized Person, Registered Geotechnical Engineer and Registered Specialist Contractor in accordance with the Technical Memorandum for Supervision Plans and the Code of Practice for Site Supervision to ensure that the quality of the works is up to standard and that the works are carried out in accordance with the plans approved and in such a manner as not to render inadequate the margin of safety of, or impair the stability of, or cause danger to any building, structure, land, street or services. The extent of supervision to be provided for different stages of the soil nailing works is provided in the Code of Practice for Site Supervision.
 - (b)* In addition to the Technically Competent Persons (TCPs) T3 and T5 under the Registered Geotechnical Engineer's (RGE's) stream, a Directorate Site Supervisor (DSS) shall be provided for the works. The name of the DSS shall also be given in the site supervision plan.
 - (c)* The TCP T5 *and/or the DSS under the RGE's stream shall submit regular reports of his/her findings and recommendations to the RGE. The RGE shall formally submit these reports to the Buildings Department and copy them to the Geotechnical Engineering Office (GEO) at monthly intervals or more frequently.
3. In connection with paragraph 2(a) above, details of site supervision of the works and of the quality of the soil nail works shall be included in the supervision plan and submitted prior to or at the time of application for consent to the commencement of the works.
- 4.* ~~A report containing results of the site trials with clear statements on buildability and whether special methods of construction need to be adopted (and if so the details) should be submitted to the Buildings Department prior to the commencement of construction of the working soil nails.~~
- /5.
- 5.* The pull-out test report, records of installation and non-destructive test report (if

any) for the soil nails should be submitted to and found satisfactory by the Building Authority prior to the submission of Form BA 14 for the proposed works.

6.* The TCP T3 shall carry out site inspection of the works and prepare and certify the key records on supervision of soil nailing works in accordance with the Code of Practice for Site Supervision.

7. Prior notice should be given to the GEO of the date of commencement of site trials for soil nailing works/non-destructive tests for installed soil nails in order to facilitate GEO to carry out site inspection and field checks.

8. All significant signs of distress and/or notable landslides during the construction works should be reported promptly to the Buildings Department and the Geotechnical Engineering Office.

A Directory of Accredited Laboratories in Hong Kong is obtainable from the Hong Kong Accreditation Service (HKAS) Executive, Innovation and Technology Commission.

Up-to-date information on accredited laboratories and their scopes of accreditation are available on the internet at the HKAS website at <http://www.info.gov.hk/itc/hkas/>.

A laboratory's accreditation for an individual test or calibration may be granted, modified or withdrawn at any time. To ensure that the test that you commission the laboratory to conduct is within its scope of accreditation, please always insist on test results be reported on a HOKLAS Endorsed Certificate.

* Delete wherever inapplicable

Ref : BD DH 20/84/HK(II)

Address : No.55 Ship Street, Hong Kong – I.L. 2140

Appendix B to approval dated 11.03.2013

Reinforced Concrete Works

In giving this approval of plans, I hereby impose the following conditions under item 6 in section 17(1) of the Buildings Ordinance:

- (a) Sampling and testing of steel reinforcing bars should be carried out in accordance with Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) APP-45 current at the date of this approval. Testing should be carried out by a laboratory* accredited under the Hong Kong Laboratory Accreditation Scheme (HOKLAS) for the particular test concerned. Test results@ should be submitted within 60 days of the delivery of the steel reinforcing bars to the site. The test reports should be appended with a statement signed by the Registered Structural Engineer to confirm the following:
- (i) All steel reinforcing bars used for the construction and the test specimens covered by the test reports are in accordance with the types and grades of steel shown in the approved plans.
 - (ii) Sampling and testing of steel reinforcing bars used have been carried out in accordance with the current PNAP APP-45.
 - (iii) The acceptance criteria appropriate to each type and grade of steel reinforcing bars used have been complied with.
 - (iv) All steel reinforcing bars tests have been carried out by a laboratory* accredited under the HOKLAS.
- (b) Sampling of concrete and compression testing of concrete test cubes should be carried out in accordance with the methods specified in CS1:2010. Testing should be carried out by a laboratory* accredited under the HOKLAS for the particular test concerned. Test results@ should be submitted within 21 days after testing. The test reports should be appended with a summary which contains information on locations of concerned structural elements, concrete grades and dates of cast. The summary should also include previous summary information of concrete cube test reports in chronological order. The test reports should also be appended with a statement signed by the Registered Structural Engineer to confirm the following:
- (i) All concrete used for the construction and concrete cubes covered by the test reports are in accordance with the concrete grades shown in the approved plans.
 - (ii) Concrete cube sizes, rates of sampling fresh concrete for testing and acceptance criteria for compressive strength set out in Building (Construction) Regulations have been complied with.

- (iii) All concrete cube tests have been carried out by a laboratory* accredited under the HOKLAS and in accordance with the methods specified in CS1:2010.

2. The following conditions in respect of qualified supervision of works are imposed under item 6 in section 17(1) of the Buildings Ordinances:

- (a) Qualified site supervision of the reinforced concrete works, including sampling of concrete and steel reinforcing bars and making and curing of test cubes, by experienced and competent persons as defined in (b) and (c), should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
- (b) The Registered Structural Engineer should assign a quality control supervisor to supervise the works, determine the necessary frequency of inspection by the quality control supervisor which should not be less than once a week, and devise inspection check lists. The minimum qualifications and experience of the quality control supervisor is to be the same as the Technically Competent Person of grade T3, as stipulated in the Code of Practice for Site Supervision 2009.
- (c) The Registered General Building Contractor/Registered Specialist Contractor should assign a quality control co-ordinator to provide full time on site supervision of the works and devise inspection check lists. The minimum qualifications and experience of the quality control co-ordinator is to be the same as the Technically Competent Person of grade T1, as stipulated in the Code of Practice for Site Supervision 2009.
- (d) The names and qualifications of the supervisory personnel representing the Registered Structural Engineer and the Registered General Building Contractor/Registered Specialist Contractor respectively should be recorded in an inspection log book. The date, time, items inspected and inspection results should be clearly recorded in the log book. The log book should be kept on site for inspection by representatives of the Buildings Department.

* A Directory of Accredited Laboratories in Hong Kong is obtainable from the Hong Kong Accreditation Service (HKAS) Executive, Innovation and Technology Commission.

A laboratory's accreditation for an individual test or calibration may be granted, modified or withdrawn at any time. Up-to-date information on accredited laboratories and their scopes of accreditation are available on the internet at the HKAS website at <http://www.info.gov.hk/itc/hkas/>.

@ The test carried out by an accredited laboratory should be within its scope of accreditation. To ensure this, test results should be reported on a HOKLAS Endorsed Certificate or equivalent Certificate/Report issued from other laboratory accreditation bodies which have reached mutual recognition agreements/arrangements with the HOKLAS.

Ref : BD DH 20/84/HK(III)

Address : No.55 Ship Street, Hong Kong - I.L.2140

Appendix C to approval dated 11.03.2013

Retaining Wall Works

In giving this approval of plans, I hereby impose the following condition under item 7 in section 17(1) of the Buildings Ordinance:

Adequate precautionary measures and suitable working procedures should be adopted in the carrying out of the above works to safeguard the stability of any building, structure, land, street or services. ~~#In this connection, two sets of excavation and lateral support plans are required to be submitted.~~

2. Also, under Building (Administration) Regulation 10, two sets of retaining wall record plans showing the characteristic features of the site and the identification, location, size, depth and level of each retaining wall as constructed are required to be submitted.

#3. You are reminded that site supervision of the retaining wall works by a team of supervisors shall be provided each by the Authorized Person, Registered Structural Engineer, #Registered Geotechnical Engineer and Registered General Building Contractor/Registered Specialist Contractor in accordance with the Technical Memorandum for Supervision Plans and the Code of Practice for Site Supervision 2009 to ensure that the works are carried out in accordance with the approved plans and in such a manner as not to render inadequate the margin of safety of, or impair the stability of, or cause danger to any building, structure, land, street or services.

#4. In connection with paragraph 3 above, details of site supervision of the retaining wall works shall be included in the supervision plan and submitted prior to or at the time of application for consent to the commencement of the retaining wall works.

#5. ~~Consent to the commencement and carrying out of the above works will not be given until the excavation and lateral support plans specified in paragraph 1 above have been submitted and found satisfactory/approved.~~

Delete wherever inapplicable

Appendix F

Record Plan of Nam Koo Terrace

A. GENERAL NOTES

- 1. SCALE OF DRAWINGS IS AS SHOWN.
2. ALL LEVELS ARE IN METRES ABOVE PRINCIPAL DATUM (MAD).
3. ALL DIMENSIONS SHOWN ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
4. NAM KOO TERRACE IS A LEVEL 1 HISTORICAL BUILDING AND THE CONTRACTOR SHALL EXERCISE EXTRA CARE IN CARRYING OUT THE WORKS.

- 5. THE CONTRACTOR SHALL CARRY OUT A DETAILED CONDITION / DEFECT SURVEY BY A QUALIFIED REGISTERED SURVEYOR WITH PHOTOGRAPHIC EVIDENCE OF NAM KOO TERRACE PRIOR TO THE REMEDIAL WORKS. A SURVEY SHALL ALSO BE CARRIED OUT AFTER COMPLETION OF THE REMEDIAL WORKS TO CONFIRM THAT THE CONTRACTOR'S WORKS HAVE NOT RESULTED IN ANY DAMAGE.
6. THE CONTRACTOR SHALL PROVIDE ANY ADDITIONAL MEASURES WHICH MAY BE NECESSARY TO ENSURE THAT THE REMEDIAL WORKS WILL NOT AFFECT THE BUILDING. THESE SHOULD BE APPROVED BY THE ENGINEER PRIOR TO IMPLEMENTATION BY THE CONTRACTOR.

C. CONCRETE AND STRUCTURAL STEEL

- 1. ALL STRUCTURAL STEEL - SECTION TO BE GRADE 434 (D54500) UNLESS OTHERWISE SPECIFIED.
2. ALL TEMPORARY WATERS ARE TO BE GRADE 434 (D54500) UNLESS OTHERWISE SPECIFIED.
3. ALL WELDING ARE TO BE PERFORMED BY A QUALIFIED WELDER TO THE SATISFACTION OF THE ENGINEER.

C. HEAVY RAINFALL PRECAUTIONS

- 1. SURFACE WATER FLOWING INTO THE SITE FROM UPHILL SHALL BE INTERCEPTED AND CONDUCTED FROM THE SITE TO AN INDICATED SAFE DISCHARGE POINT. TEMPORARY CHANNELS SHALL BE PLASTERED AND PROTECTED FROM DAMAGE.
2. WHERE PARTIALLY COMPLETED DRAINAGE WORKS DISCHARGE WITHIN THE SITE A TEMPORARY CONDUIT SHALL BE PROVIDED TO THE DISCHARGE POINT.

D. FILL MATERIAL

- 1. FILL MATERIAL SHALL NOT CONTAIN ANY OF THE FOLLOWING:
1.1.1 MATERIAL SUSCEPTIBLE TO VOLUME CHANGE, INCLUDING MARINE MUD, SOIL WITH A LIQUID LIMIT EXCEEDING 60% OR A PLASTICITY INDEX OF MORE THAN 30%, SHELLS, CLAYS AND COLLAPSIBLE SOILS.
1.1.2 PEAT, VEGETATION, TIMBER, ORGANIC, SOLUBLE OR PUSHERABLE MATERIAL.

- 4.2. EARTHWORKS FINAL SURFACES SHALL BE COMPLETED TO SMOOTH ALIGNMENTS WITHOUT ABRUPT BENTLINES.
4.3. EARTHWORKS FINAL SURFACES AND FORMATIONS SHALL BE MAINTAINED IN A STABLE CONDITION AND PROTECTED FROM DAMAGE DUE TO WATER OR OTHER CAUSES AND FROM EXPOSURE TO CONDITIONS WHICH MAY ADVERSELY AFFECT THE SURFACE.
4.4. SOLE PROTECTION SYSTEM - GRASSSEED OR HYDROSEEDING IS TO BE PROVIDED ON THE CUT AND FILL SLOPES.

E. NOTES ON SOIL NAILS

- 1. THE MINIMUM DIAMETER OF THE DRILLHOLES FOR SOIL NAIL INSTALLATION SHALL BE 120mm UNLESS OTHERWISE STATED. AIR OR FOAM FLUSH MEDIUM MUST BE USED DURING DRILLING. WATER SHALL NOT BE USED FOR FLUSHING.
2. THE SOIL NAILS SHALL BE INSTALLED WITHIN 24 HOURS OF COMPLETION OF THE DRILLING UNLESS OTHERWISE STATED BY THE ENGINEER'S REPRESENTATIVE. DRILLHOLES SHALL BE CLEARED OF ALL DEBRIS IMMEDIATELY BEFORE TENDRING.

F. NOTES ON PULL OUT TEST FOR SOIL NAILS

- 1. PULL OUT TEST ON ALL TEST NAILS SHALL BE CARRIED OUT AT LOCATIONS AS SPECIFIED IN THE DRAWINGS OR AS DIRECTED BY THE ENGINEER AND SHALL BE CARRIED OUT BY THE CONTRACTOR PRIOR TO INSTALLATION OF THE WORKING NAILS.
2. THE SOIL NAIL PULL OUT TEST SHALL BE CARRIED OUT ON THE SCHEDULED BOND LENGTH IN ACCORDANCE WITH THE SCHEDULE OF TEST NAILS SHOWN ON THIS DRAWING.


- 3. WORKS SHALL CEASE AND THE ENGINEER AND BUILDINGS DEPARTMENT NOTIFIED IF ANY UNDEVELOPED GROUND MOVEMENT OR GROUNDWATER DRAWDOWN IS RECORDED. REMEDIAL MEASURES TO BE AGREED AND COMPLETED PRIOR TO RE-COMMENCEMENT OF WORKS.
4. DRAINAGE AND MONITORING STATIONS ARE TO BE RENAISSANCE TO THE ENGINEER.
5. READINGS ARE TO BE SUBMITTED TO THE ENGINEER ON A DAILY BASIS GRAPHICAL PRESENTATION IS TO BE SUBMITTED TO THE ENGINEER ON A DAILY BASIS.

G. GENERAL WORK SEQUENCE FOR REMEDIAL WORKS


- 1. CONDUIT SURVEY TO BE CONDUCTED.
2. ESTABLISH ALL MONITORING STATIONS.
3. REMOVE SURFACE AND ANY FEATURES SUCH AS THE CONCRETE PERGOLA, FOUNTAIN AND CONCRETE GARDEN ETC. WITHOUT DAMAGING THEM.
4. DEMONSTRATION OF THE ENGINEER AN ADDITIONAL NUMBER OF TEST NAILS SHALL BE CARRIED OUT AS INSTRUCTED BY THE ENGINEER. REMEDIAL WORKS ARE TO BE CONDUCTED IF NECESSARY.

H. MONITORING

- 1. MONITORING SHALL CONSIST OF THE DAILY MEASUREMENT OF SETTLEMENT MARKERS (SEE TYPICAL SECTION FOR DETAILS) ON THE RETAINING WALL AND THE RETURN SIGNAL FROM THE ALERT NAIL.
2. MEASUREMENTS OF BUILDING SETTLEMENT MARKERS (BS1 TO BS4), DAILY MEASUREMENT OF SURFACE SETTLING MARKERS (ST1 TO ST3) AND VIBROGRAPH (VBT TO VBT3).



BLOCK PLAN 1:1000



SOIL NAIL PULL-OUT TEST ARRANGEMENT

R. NOTES ON PREDRILLING

- 1. THE SPECIFICATION TO BE READ IN CONJUNCTION WITH THE FOLLOWING DOCUMENTS:
1.1. GEOTECHNICAL GUIDE TO SITE INVESTIGATION (1987) GEO. WORKS BOARD.
1.2. GEOTECHNICAL GUIDE TO SOIL AND ROCK EXPLORATION (1988) GEO. WORKS BOARD.

O. ALERT ALARM AND ACTION LEVEL FOR MONITORING WORKS

Table with columns: SETTLEMENT, TILTING (mm), VIBRATION. Rows: ALERT, ACTION, WARNING levels for Ground and Structures.

WHERE:
t = TEST LOAD
fl = FREE LENGTH
E = YOUNG'S MODULUS OF STEEL
A = CROSS-SECTIONAL AREA OF STEEL BAR

G. SOIL NAIL PULL OUT TEST SCHEDULE

Table with columns: TAIL ELEVATION (mPD), LENGTH (m), FREE LENGTH (m), GROUDED LENGTH FOR TEST (m), DESIGN LOAD (kN), TEST LOAD (kN), BAR DIA. (mm), HOLE DIA. (mm), INCLINATION (DEGREE), SOIL NAIL LENGTH (m).

R. NOTES ON PREDRILLING (continued)

- 2. THE LOCATION OF PREDRILLING HOLES ARE SHOWN IN DWG. NO. 910101/RW002. THE FINAL LOCATION SHALL BE CONFIRMED BY THE CONTRACTOR.
3. EXISTING STRUCTURES AND SERVICES:
3.1. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO AVOID CAUSING ANY DAMAGE TO THEM.

R. NOTES ON PREDRILLING (continued)

- 4. THE CONTRACTOR SHALL PROVIDE COMPLETION TESTS TO LOG THE SAMPLES WHICH SHALL SATISFY THE REQUIREMENTS OF THE LOCAL GOVT. OR GROUND INVESTIGATION FELLOWSHIP IN ACCORDANCE WITH THE CODE FOR SITE SUPERVISION 2000.
5. DRIVING FOR HOLES SHALL NOT BE WITHHELD WITHOUT THE APPROVAL OF THE ENGINEER. AFTER THE APPROVAL OF THE ENGINEER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE HOLES.



SOIL NAIL TYPICAL CROSS SECTION


TYPICAL SECTION FOR SOIL NAIL

- a) THE HEAD OF THE STEEL SOIL NAIL SHALL ELECTRICALLY BE ACCESSIBLE ALL CLOSE MATERIALS SHALL BE REMOVED FROM THE BAR HEAD.
b) CONNECT THE TOP INSTRUMENT TO THE STEEL SOIL NAIL HEAD AND THE ELECTRIC WIRE.
c) SEND A SHORT PULSE INTO THE STEEL SOIL NAIL AND RECORD THE TIME OF REFLECTION OF THE WAVE FROM THE END OF THE STEEL SOIL NAIL. THE RETURN SIGNAL FROM THE NAIL END SHOULD GO DOWN AND VICE VERSA.

843 BD D/H20/84/HK

NOTES: THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS AND HAZARDOUS WASTE CONTROL ACT (1989) AND ENVIRONMENTAL IMPROVEMENT ACT (1996).

LEGEND: --- LOT BOUNDARY --- FEATURE BOUNDARY



1:1000

MAX CHAI CHEUNG, PETER CHAN, REGISTERED ARCHITECT (No. 1111)

LEUNG HOON YU, REGISTERED STRUCTURAL ENGINEER (No. 1111)

Plan Approval: (Signature) Chief Building Surveyor for BUILDING AUTHORITY

Table with columns: Description, Date, By, For. Rows: D - MINOR AMENDMENT, A - AD APPROVED, etc.

11 JAN 2013

CHUNG Wing-hong, Chief Building Surveyor for BUILDING AUTHORITY

FEATURES NOS. 11S-W-B/CR349 (WALL PORTION OF SUB-DIVISION NO.1) AND 11S-W-B/R629 55 SHIP STREET, WANCHAI

RETAINING WALL REMEDIAL WORKS GENERAL NOTES & BLOCK PLAN

Table with columns: Description, Date, By, For. Rows: D - MINOR AMENDMENT, A - AD APPROVED, etc.

11 JAN 2013

CHUNG Wing-hong, Chief Building Surveyor for BUILDING AUTHORITY

11 JAN 2013

NOTE:
 1. THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING 991051/RW001 & RW002.
 2. THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS URUSIDE ORDER NO. DH0332/86/11C FOR FEATURE NOS. 115W-B/CR349 (WALL PORTION OF SUB-DIVISION NO. 1) AND 115W-B/8629.

LEGEND:
 --- LOT BOUNDARY



LEUNG Kwok-Yiu
 BRANCH CHIEF, WANCHAI
 Registered Structural Engineer

Fan Sui Kay
 Registered Structural Engineer
 (Reg. No. R105047)

Plan Approval
 (CHOW Wing-hong)
 Chief Building Surveyor
 for BUILDING AUTHORITY
 11 MAR 2003


Rev. No.	Description	Date	By	CHK	APP
E	MINOR AMENDMENT	19.12.12	A	B	PL
D	MINOR AMENDMENT	10.03.11	KL	ML	RL
C	AD BE APPROVED UPDATE BD COMMENT	20.06.03	FL	LM	JC
B	IF'S DRAINAGE DETAILS ADDED, DETAILS 'C' & DETAILS 'D'	26.02.03	LM	ESH	JC
A	AD BE APPROVED UPDATE BD COMMENT	19.11.01	EX	LM	JT




PROJECT:
 FEATURES NOS. 115W-B/CR349
 (WALL PORTION OF SUB-DIVISION NO. 1)
 AND 115W-B/R629
 55 SHIP STREET, WANCHAI

RETAINING WALL REMEDIAL WORKS
 ELEVATION AND DETAILS


Drawn By:	Checked:	Scale:	Date:	Proj No.:	Rev. No.:
DL	AL	AS SHOWN	16.07.01	991051	1051RW3
DL	AL	AS SHOWN	16.07.01	991051/RW003	1


















ELEVATION OF WALL A OF 115W-B/R629










ELEVATION OF WALL B OF 115W-B/R629



TYPICAL DETAILS OF SETTLEMENT CHECK POINT FOR SENSITIVE UTILITY (PERMISSION TO BE GRANTED FROM (OWNER OR AUTHORITY PRIOR INSTALLATION))



NOTES:
 1. TIES SHALL BE 3 THK. 40 WIDE HOT-DIP GALVANIZED MILD STEEL PLAT.
 2. TIES SHALL BE CAST INTO THE CONCRETE WALL DURING CONCRETING
 3. TIES SHALL BE LAID AT A RATE OF 5 NOS. PER M²



Scale Reference No. BD DH20/84/HK

NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH DRAWINGS 991051/RW001 & RW003
- THIS DRAWING IS SUBMITTED IN COMPLIANCE WITH DANGEROUS WASTE ORDER NO. 40/2005 AND WITH FEATURE NOS. 11SW-B/R628 & 11SW-B/R629 (WALL PORTION OF SUB-DIVISION NO.1) AND 11SW-B/R629

LEGEND

- PROPOSED SOLE NAIL
- PROPOSED DOWN BAR
- PROPOSED WATER & STRUT
- PROPOSED WEEPHOLE
- PROPOSED TRAIL PIT (TOTAL 1 NOS)
- EXISTING GROUND SETTLEMENT MARKERS (TOTAL 6 NOS)
- EXISTING BUILDING SETTLEMENT MARKERS (TOTAL 4 NOS)
- EXISTING STAND PIPES (TOTAL 2 NOS)
- EXISTING BOREHOLES WITH STANDPIPES (TOTAL 4 NOS)
- EXISTING VERTICAL BOREHOLES (TOTAL 3 NOS)
- EXISTING HORIZONTAL COFFERHOLE (TOTAL 19 NOS)
- EXISTING INCLINED COFFERHOLES (TOTAL 6 NOS)
- EXISTING TRAIL PITS (TOTAL 7 NOS)
- EXISTING UTILITIES INSPECTION PIT (TOTAL 5 NOS)
- PROPOSED U-CHANNEL
- PROPOSED CATCHPIST
- PROPOSED DOWNPIPE
- PROPOSED SETTING MARKERS (TOTAL 9 NOS)
- PROPOSED VERMICROGRAPH LOCATIONS (TOTAL 3 NOS)
- PROPOSED PREDRILL BOREHOLE LOCATIONS (TOTAL 2 NOS)
- EXISTING BOREHOLE
- FEATURE BOUNDARY

Plan Approved
(CHONG Wing-hong)
Chief Building Surveyor
for BUILDING AUTHORITY
11 JAN 2013

Yan Sin Kuy
Registered Structural Engineer
(Reg. No. R10507)

LEUNG Kwok-Yiu
Registered Geotechnical Engineer
(Reg. No. GE1000)

WALSH LIMITED
HONG KONG

Rev	Stat	Description	Date	By	Chk	App
E	-	MINOR AMENDMENT	19.12.12	A	BR	RL
D	-	MINOR AMENDMENT	13.06.11	KL	ML	RL
C	-	MINOR AMENDMENT	10.03.11	AL	ML	RL
A	-	AD - BD APPROVED	20.06.03	LM	ESTY	JK
B	BS	GENERAL REVISION	26.02.03	JK	ML	RL
A	AD	BS APPROVED UPDATE BD COMMENT	18.11.01	JK	LM	UT

Hyder

Project: FEATURES NOS. 11SW-B/R628 AND 11SW-B/R629
55 SHIP STREET, WAN CHAI

Drawing Title: RETAINING WALL REMEDIAL WORKS LAYOUT PLAN & SECTIONS

Drawn: EK Date: 16.07.01 App No: 991051
Checked: AL Date: 16.07.01 Drawn By: 1051HWZ
Approved: DL Date: 16.07.01 Scale: A3 SHOWN

Drawing No: 991051/RW002

10 JAN 2013



YOUR REF 來函檔號：
OUR REF 本(23)號 BD DH20/84/HK(III)
FAX 圖文傳真： 2136 8200
TEL 電話： 2135 2453
www.info.gov.hk/bd

Mr. MAK Chi Cheung, Peter
c/o WMKY Limited
Room 3308, 33/F,
Hopewell Centre,
183 Queen's Road East,
Wanchai, Hong Kong

11 March 2013

39

15 MAR 2013

374

DATE	ANS TO	ANS BY	FILE
PM AM	SL JF	HL SW	FT
INF			
ACTION			

Dear Sir,

DHO No. DH0035/HK/11/C dated 30 March 2011
Feature Nos. 11SW-B/CR349 (Wall Portion of Sub-division No. 1) & 11SW-B/R629
Proposed Wall Remedial Works at
No.55 Ship Street, Hong Kong – I.L. 2140

I refer to your application dated 10 January 2013 and received on **11 January 2013** for approval of proposals in respect of **Wall Remedial Works (Major Revision)**.

- Your submission of plans has been checked under the curtailed check system announced in Practice Notes for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers ADM-19. On this basis, I am satisfied that your submission is fundamentally acceptable and may be approved.
- You are reminded that the curtailed check system covers only the fundamental issues of a building proposal. Although non-fundamental issues will not be raised as reasons for disapproving a submission, I expect that all contravention of the Buildings Ordinance and its subsidiary legislation are rectified as and when they are discovered and in any event, before completion of the works is certified. In this connection, I ask you to note that the Building Authority attaches great importance to the proper assumption of duties and responsibilities by authorized persons, registered structural engineers and registered geotechnical engineers.
- In accordance with the provisions of regulation 30(1) of the Building (Administration) Regulations, this is to notify that the above - mentioned plans submitted with your application received on 11 January 2013 are hereby approved. One set of the said plans, on which I have signified my approval, is enclosed. Your client has been sent a copy of this letter but I would request that you ensure that the contents are understood by him.
- This approval should not be deemed to confer any title to land or to act as a waiver of any term in any lease or licence. This approval does **NOT** authorize the commencement or the carrying out of any works shown in the approved plans. Section 14(2) of the Buildings Ordinance refers.

/...2

6. As conditions of this approval under Section 17(1) of the Buildings Ordinance, the following are required:-

- (a) Qualified site supervision requirement, sampling and testing of soil nail works as stipulated in Appendix A.
- (b) Qualified site supervision requirement, sampling and testing of reinforced concrete works as stipulated in Appendix B.
- (c) Qualified site supervision requirement of retaining wall works as stipulated in Appendix C.

To ensure full compliance of the Buildings Ordinance, it is prudent for the authorized person who acts as the co-ordinator of the building works, to inform the registered contractor all the imposed conditions attached to this approval.

7. The checking of submission has been substantially curtailed and greater emphasis is placed on the integrity and competence of the authorized persons. You are expected to comply with the requirement of Buildings Ordinance section 4(3)(b) in respect of any contravention of the regulations.

8. Chief Geotechnical Engineer/Island of the Geotechnical Engineering Office, Civil and Engineering Development Department (Contact Person: Mr. Roy K. C. HUNG on Tel. No. 2762 5282) has the following comments:

- (a) Prior to consent application for commencement of the works, a report on condition survey of the adjacent existing building/structure, including the Graded historic building Nam Koo Terrace, shall be submitted and acknowledged by the Buildings Department.
- (b) In addition to the TCP T3 and T5 site supervision personnel under the RGE's stream, a Directorate Site Supervisor (DSS) shall be provided for the proposed retaining wall remedial works. He/she shall carry out inspections at the critical stages of the works at least monthly, or more frequently as necessary. The name of the DSS shall also be given in the site supervision plan.
- (c) The AP/RSE/RGE are advised that the extent of supervision to be provided for different stages of the soil nailing works is given in the Code of Practice for Site Supervision 2009.
- (d) The AP/RSE/RGE are advised that the TCP T3 shall carry out site inspection of the works and prepare and certify the key records on supervision of soil nailing works in accordance with the Code of Practice for Site Supervision 2009.
- (e) The AP/RSE/RGE are advised that the following shall be submitted and accepted by the BA prior to submission for the Form BA14 for the slope/retaining wall remedial works:

/...3

- (i) Pull-out test report, records of installation and non-destructive test report (if any) for the soil nails;
- (ii) Results of the confirmatory ground investigation fieldworks for pre-drilled holes PD1 and PD2 as shown in Drawing No. 991051/RW002(Rev.E) and an assessment report of the ground condition interpreted from the ground investigation fieldworks results in comparison with the relevant design assumptions.

- (f) It is noted that construction of the proposed retaining wall remedial works for Feature No. 11SW0B/R629 will inevitably require working space outside the lot boundary of the subject private lot. The AP is reminded to seek permission from the relevant parties for temporary occupation of the required working space for execution of the proposed works.

9. Chief Highway Engineer/Hong Kong, Highways Department (Contact Person: Mr. C M CHONG on Tel. No. 2231 5722) has the following comments:

- (a) You are required to advise whether any existing slope / features / retaining wall maintained by this Office would be affected by the proposed works.
- (b) You are required to advise whether the proposed works, including any slope reinforcing works and proposed drainage, would be constructed at Government land and would be handed over to this Office for maintenance.
- (c) You are required to seek DSD's comments for any proposed connection of drains / channels to public drainage system.

It is noted that you have made reply on the above comments via email dated 7 March 2013 and HyD has no further comment on your proposal.

10. The Antiquities and Monuments Office (AMO) of the Leisure and Cultural Services Department (Contact Person: Ms. Rammy LAI on Tel. no. 2721 2673) has the following comments:-

- (a) The subject works site is located very close to the Grade 1 historic building Nam Koo Terrace. The AP/RSE/RGE shall ascertain the potential impacts on this graded building and recommend appropriate precautionary measures so as to ensure that the structural integrity and fabrics of the graded building will not be damaged by the proposed slope works.
- (b) It is noted that no movement or tilting monitoring point locations are proposed at the captioned historic building. Therefore, the AP/RSE/RGE should propose locations for vibration, settlement and tilting check points for the Grade 1 historic building and the following monitoring table for AAA levels shall be followed as attached:

/...4

	Alert level	Alarm level	Action level
Vibration check point	3mm/s	4mm/s	5mm/s
Settlement check point	6mm	8mm	10mm
Tilting check point	1/2000	1/1500	1/1000

- (c) It is recommended that for all building settlement and tilting markers shown on Drawing No. 991051/RW003 are replaced by glued fixing with a disc and with measurement by means of an electronic tilt meter to avoid drill damage to the captioned graded building.
- (d) No adverse impact to be posed on the masonry walls should be taken into account of the works design. It is recommended that the soil nail heads shown on Drawing no. 991051/RW003 for upgrading works of other retaining walls be recessed further into the masonry wall and be made good with stone blocks in front of the soil nail head.
- (e) It is suggested that the existing stone faced retaining wall shall not be covered by mass concrete at Section AA and BB in order to preserve the historic setting. Consideration shall be given to add mass concrete behind the existing retaining wall for the upgrading work should the adjoining site also own by the same owner.
- (f) It is stated in item 8 of the General Notes that features at the forecourt, such as pavilion, fountain, planters and garden feature, etc. will be temporarily removed and shall be reinstated after completion of work. Destructive removal method to the historic features at forecourt is not recommended, AP/RSE/RGE are required to consider less destructive method, if any. The AP/RSE/RGE should adopt appropriate protective measures to the said features in the course of removal and reinstatement works. Backfilling works in the course of reinstatement shall match with the existing floor finish.
- (g) The AP/RSE/RGE is required to clarify if there will be any demolition / alteration to the existing featured boundary wall above the masonry walls requiring remedy. Appropriate protective measures to the existing features on the boundary wall such as arch doorway, column heads, etc. should be necessary.
- (h) To conclude, the AP/RSE/RGE are reminded that no disturbance should be made to the building and features in the site in the course of works, and mitigation measures should be carried out, if necessary, in consultation with this Office. Please note that any protective/ precaution measure should avoid direct fixing to the buildings and features, if required please consider using reversible fixing method as far as possible to minimize the disturbance to the fabric.

11. Commissioner for Transport, Traffic Engineering (HK) Division, Transport Department (Contact Person: Ms. TAM Kwai-fan, Irene on Tel. No. 2294 2600) has the following comments:-

- (a) If public road will be occupied by the proposed works, temporary traffic management scheme shall be submitted in advance.

12. Comments, if any, from the District Lands Officer/Hong Kong West & South of Lands Department, will be conveyed to you once available.

13. Please be reminded of the following:


- (a) To provide adequate precautionary measures prior to and during the carrying out of the retaining wall remedial works for the safety of the public, the workers and the adjoining properties. An Application for a hoarding permit is required if a hoarding is to be erected under Buildings (Planning) Regulation 64. In this connection, your attention is drawn to PNAP APP-23;
- (b) To lodge a supervision plan (2 copies) for the works prior to your consent application. Your attention is drawn to Section 16(3)(bc) of the Buildings Ordinance;
- (c) To promptly report all significant signs of distress and/or notable landslides during the construction works to the Buildings Department and the Geotechnical Engineering Office.
- (d) To give prior notice to the GEO of the date of commencement of site trials for soil nailing works and non-destructive tests for installed soil nails shown on the plans in order to facilitate GEO staff to carry out site inspection and field checks.

14. You are required, under Building (Administration) Regulation 10, to submit the following:

- (a) Initial readings of all monitoring stations for record prior to the commencement of the retaining wall remedial works;
- (b) Together with Form BA14 to certify completion of the works, you are required to submit the following:
 - (i) Two sets of record plans.
 - (ii) The Information including a soft copy of the basic data requested in PNAP ADV-8 for registration of slopes and retaining walls for which the owners have maintenance responsibility;
 - (iii) Two copies of the Maintenance Manual, as requested in PNAP APP-79;

15. It is noted that you made amendments on the plans on 28 February 2013, 8 & 11 March 2012.
16. Please provide a copy of the approved plans to GEO direct.
17. It appears that trees in or around your site may be affected by your slope stabilization works proposal. You are advised to liaise with the District Lands Office in this regard prior to commencement of works.
18. Please be reminded that due consideration should be given to incorporate landscape measures to improve the visual appearance of the feature. Landscape treatment should be provided, wherever possible, to all newly formed or newly upgraded slopes and the use of shotcrete or chunam on slopes should only be considered as a last resort. (PNAP ADV-23 refers) Please also refer to the "Layman's Guide to Landscape Treatment of Slopes" produced by the Geotechnical Engineering Office, which can be viewed/downloaded from the Civil Engineering and Development Department Website (<http://www.cedd.gov.hk/eng/publications/geo/index.htm>) through the Internet.

Yours faithfully,


(CHONG Wing-hong)
Chief Building Surveyor/Slope Safety
for Building Authority

c.c. **YUBA Company Limited**
(fax: 2865 6276)

RSE - Mr. Fan Siu Kay
(fax no. 2529 1834)

RGE - Mr. Leung Kwok Yiu
(fax no. 2805 5028)

CGE/I, GEO, CEDD
DLO/HK W&S
CHE/HK, HyD
AC for T, TD
AMO, LCSD

Ref : BD DH20/84/HK(III)

Address : No.55 Ship Street, Hong Kong - I.L. 2140

Appendix A to approval dated 11.03.2013

Soil Nail/~~Rock-Dowel~~ Works

In giving this approval of plans, I hereby impose the following conditions under item 6 in section 17(1) of the Buildings Ordinance.

- (a) Sampling and testing of steel reinforcing bars used in the soil nail/~~rock-dowel~~ works should be carried out in accordance with Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) APP-45 (previously known as PNAP 122). Testing should be carried out by a laboratory[#] accredited under the Hong Kong Laboratory Accreditation Scheme (HOKLAS) for the particular test concerned. Test results should be reported on a HOKLAS Endorsed Certificate and submitted within 60 days of the delivery of the steel reinforcing bars to the site. The test reports should be appended with a statement signed by the Authorized Person/Registered Structural Engineer to confirm the following:
- (i) All steel reinforcing bars used in the soil nail/~~rock-dowel~~ works and the test specimens covered by the test reports are in accordance with the types and grades of steel shown in the approved plans.
 - (ii) Sampling and testing of steel reinforcing bars used have been carried out in accordance with the current PNAP APP-45 (previously known as PNAP 122).
 - (iii) The acceptance criteria appropriate to each type and grade of steel reinforcing bars used have been complied with.
 - (iv) Testing of steel reinforcing bars has been carried out by a laboratory[#] accredited under HOKLAS.
- (b) The requirements of sampling and testing of grout are as follows:
- (i) For each grout mix one sample of grout shall be provided from each 10 batches of grout, or every 10 m³ from the amount of grout produced in a day, whichever is the lesser, to determine the crushing strength of the grout. Samples shall be provided not more than 1 hour after the grout has been mixed and shall be protected from weather before test cubes are made.

- (ii) Compression testing of grout test cubes should be carried out in accordance with the methods specified in CS1:1990/ CS1:2010* using 100mm size cubes. Testing should be carried out by a laboratory[#] accredited under HOKLAS for the particular test concerned. Test results should be reported on a HOKLAS Endorsed Certificate and appended with a statement signed by the Authorized Person/Registered Structural Engineer to confirm that the acceptance criteria set out in the Building (Construction) Regulation 59 have been complied with, and should be submitted within 21 days after testing.
 - (c) Qualified site supervision of the sampling of cement grout and making and curing of test cubes by an experienced and competent person should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
2. Your attention is drawn to the following conditions:
- (a) Site supervision of the soil nail works by a team of supervisors shall be provided each by the Authorized Person, Registered Geotechnical Engineer and Registered Specialist Contractor in accordance with the Technical Memorandum for Supervision Plans and the Code of Practice for Site Supervision to ensure that the quality of the works is up to standard and that the works are carried out in accordance with the plans approved and in such a manner as not to render inadequate the margin of safety of, or impair the stability of, or cause danger to any building, structure, land, street or services. The extent of supervision to be provided for different stages of the soil nailing works is provided in the Code of Practice for Site Supervision.
 - (b)* In addition to the Technically Competent Persons (TCPs) T3 and T5 under the Registered Geotechnical Engineer's (RGE's) stream, a Directorate Site Supervisor (DSS) shall be provided for the works. The name of the DSS shall also be given in the site supervision plan.
 - (c)* The TCP T5 *and/or the DSS under the RGE's stream shall submit regular reports of his/her findings and recommendations to the RGE. The RGE shall formally submit these reports to the Buildings Department and copy them to the Geotechnical Engineering Office (GEO) at monthly intervals or more frequently.
3. In connection with paragraph 2(a) above, details of site supervision of the works and of the quality of the soil nail works shall be included in the supervision plan and submitted prior to or at the time of application for consent to the commencement of the works.
- 4.* ~~A report containing results of the site trials with clear statements on buildability and whether special methods of construction need to be adopted (and if so the details) should be submitted to the Buildings Department prior to the commencement of construction of the working soil nails.~~
- /5.
- 5.* The pull-out test report, records of installation and non-destructive test report (if

any) for the soil nails should be submitted to and found satisfactory by the Building Authority prior to the submission of Form BA 14 for the proposed works.

6.* The TCP T3 shall carry out site inspection of the works and prepare and certify the key records on supervision of soil nailing works in accordance with the Code of Practice for Site Supervision.

7. Prior notice should be given to the GEO of the date of commencement of site trials for soil nailing works/non-destructive tests for installed soil nails in order to facilitate GEO to carry out site inspection and field checks.

8. All significant signs of distress and/or notable landslides during the construction works should be reported promptly to the Buildings Department and the Geotechnical Engineering Office.

A Directory of Accredited Laboratories in Hong Kong is obtainable from the Hong Kong Accreditation Service (HKAS) Executive, Innovation and Technology Commission.

Up-to-date information on accredited laboratories and their scopes of accreditation are available on the internet at the HKAS website at <http://www.info.gov.hk/itc/hkas/>.

A laboratory's accreditation for an individual test or calibration may be granted, modified or withdrawn at any time. To ensure that the test that you commission the laboratory to conduct is within its scope of accreditation, please always insist on test results be reported on a HOKLAS Endorsed Certificate.

* Delete wherever inapplicable

Ref : BD DH 20/84/HK(II)

Address : No.55 Ship Street, Hong Kong – I.L. 2140

Appendix B to approval dated 11.03.2013

Reinforced Concrete Works

In giving this approval of plans, I hereby impose the following conditions under item 6 in section 17(1) of the Buildings Ordinance:

- (a) Sampling and testing of steel reinforcing bars should be carried out in accordance with Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) APP-45 current at the date of this approval. Testing should be carried out by a laboratory* accredited under the Hong Kong Laboratory Accreditation Scheme (HOKLAS) for the particular test concerned. Test results@ should be submitted within 60 days of the delivery of the steel reinforcing bars to the site. The test reports should be appended with a statement signed by the Registered Structural Engineer to confirm the following:
 - (i) All steel reinforcing bars used for the construction and the test specimens covered by the test reports are in accordance with the types and grades of steel shown in the approved plans.
 - (ii) Sampling and testing of steel reinforcing bars used have been carried out in accordance with the current PNAP APP-45.
 - (iii) The acceptance criteria appropriate to each type and grade of steel reinforcing bars used have been complied with.
 - (iv) All steel reinforcing bars tests have been carried out by a laboratory* accredited under the HOKLAS.
- (b) Sampling of concrete and compression testing of concrete test cubes should be carried out in accordance with the methods specified in CS1:2010. Testing should be carried out by a laboratory* accredited under the HOKLAS for the particular test concerned. Test results@ should be submitted within 21 days after testing. The test reports should be appended with a summary which contains information on locations of concerned structural elements, concrete grades and dates of cast. The summary should also include previous summary information of concrete cube test reports in chronological order. The test reports should also be appended with a statement signed by the Registered Structural Engineer to confirm the following:
 - (i) All concrete used for the construction and concrete cubes covered by the test reports are in accordance with the concrete grades shown in the approved plans.
 - (ii) Concrete cube sizes, rates of sampling fresh concrete for testing and acceptance criteria for compressive strength set out in Building (Construction) Regulations have been complied with.

- (iii) All concrete cube tests have been carried out by a laboratory* accredited under the HOKLAS and in accordance with the methods specified in CS1:2010.

2. The following conditions in respect of qualified supervision of works are imposed under item 6 in section 17(1) of the Buildings Ordinances:

- (a) Qualified site supervision of the reinforced concrete works, including sampling of concrete and steel reinforcing bars and making and curing of test cubes, by experienced and competent persons as defined in (b) and (c), should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
- (b) The Registered Structural Engineer should assign a quality control supervisor to supervise the works, determine the necessary frequency of inspection by the quality control supervisor which should not be less than once a week, and devise inspection check lists. The minimum qualifications and experience of the quality control supervisor is to be the same as the Technically Competent Person of grade T3, as stipulated in the Code of Practice for Site Supervision 2009.
- (c) The Registered General Building Contractor/Registered Specialist Contractor should assign a quality control co-ordinator to provide full time on site supervision of the works and devise inspection check lists. The minimum qualifications and experience of the quality control co-ordinator is to be the same as the Technically Competent Person of grade T1, as stipulated in the Code of Practice for Site Supervision 2009.
- (d) The names and qualifications of the supervisory personnel representing the Registered Structural Engineer and the Registered General Building Contractor/Registered Specialist Contractor respectively should be recorded in an inspection log book. The date, time, items inspected and inspection results should be clearly recorded in the log book. The log book should be kept on site for inspection by representatives of the Buildings Department.

* A Directory of Accredited Laboratories in Hong Kong is obtainable from the Hong Kong Accreditation Service (HKAS) Executive, Innovation and Technology Commission.

A laboratory's accreditation for an individual test or calibration may be granted, modified or withdrawn at any time. Up-to-date information on accredited laboratories and their scopes of accreditation are available on the internet at the HKAS website at <http://www.info.gov.hk/itc/hkas/>.

@ The test carried out by an accredited laboratory should be within its scope of accreditation. To ensure this, test results should be reported on a HOKLAS Endorsed Certificate or equivalent Certificate/Report issued from other laboratory accreditation bodies which have reached mutual recognition agreements/arrangements with the HOKLAS.

Ref : BD DH 20/84/HK(III)

Address : No.55 Ship Street, Hong Kong - I.L.2140

Appendix C to approval dated 11.03.2013

Retaining Wall Works

In giving this approval of plans, I hereby impose the following condition under item 7 in section 17(1) of the Buildings Ordinance:

Adequate precautionary measures and suitable working procedures should be adopted in the carrying out of the above works to safeguard the stability of any building, structure, land, street or services. ~~#In this connection, two sets of excavation and lateral support plans are required to be submitted.~~

2. Also, under Building (Administration) Regulation 10, two sets of retaining wall record plans showing the characteristic features of the site and the identification, location, size, depth and level of each retaining wall as constructed are required to be submitted.

#3. You are reminded that site supervision of the retaining wall works by a team of supervisors shall be provided each by the Authorized Person, Registered Structural Engineer, #Registered Geotechnical Engineer and Registered General Building Contractor/Registered Specialist Contractor in accordance with the Technical Memorandum for Supervision Plans and the Code of Practice for Site Supervision 2009 to ensure that the works are carried out in accordance with the approved plans and in such a manner as not to render inadequate the margin of safety of, or impair the stability of, or cause danger to any building, structure, land, street or services.

#4. In connection with paragraph 3 above, details of site supervision of the retaining wall works shall be included in the supervision plan and submitted prior to or at the time of application for consent to the commencement of the retaining wall works.

#5. ~~Consent to the commencement and carrying out of the above works will not be given until the excavation and lateral support plans specified in paragraph 1 above have been submitted and found satisfactory/approved.~~


Delete wherever inapplicable

Appendix G

Record Plan of Dragon Villa

Appendix H

Schematic Sections




PROPOSED
RETAINING
WALL

PROPOSED STORAGE
SYSTEM

GROUND FLOOR PLAN

1/2 P
FL
1/ FL
SCA



A1					
A	RESUBMISSION	27/04/2015			
HD.	ITEMS	2/3	2/3	2/3	2/3
	AMENDMENTS				

WAI KWAI ARCHITECTS ENGINEERS
 2308-10 Hoiwadi Centre, 182 Queen's Road East Hong Kong Tel: 25288895

AUTHORIZED PERSON ARCHITECT

 MARK CHI CHEUNG, PETER
 STRUCTURAL ENGINEER
 REGISTERED STRUCTURAL ENGINEER

PROJECT:
 PROPOSED RESIDENTIAL DEVELOPMENT
 ON LL 2093 R.P. & LL 2093 S.A. R.P.
 NO. 53 SHIP STREET
 WANCHAI, HONG KONG

TITLE:
 SECTION 'A' & 'B' & 'C'

DESIGNED BY	PM	JOB NO.	1645
DRAWN BY	CM	ED APP. DATE	
CHECKED BY	SYC	F.S.D. APP. DATE	
SCALE	1:100	CAD FILE	
DATE	02/02/15	DRAWING NO.	
REF. NO.	6/6	1645GP006 A	

FOR SUBMISSION TO B. D.
 27 APR 2015

B.D. (B) REF. NO. BD 2 / 3011 / 15
 F.S.D. REF. NO. FDS 8/ 7918